



Arboricultural Impact Report

Prepared for:

Nick Vlahandreas Mountain Planning 0409 723 259 nickv@mountainplanning.com

Prepared by:

Rhys Oldmeadow Diploma of Arboriculture <u>rhys@oldarb.com.au</u> 0412 199 628

Site assessment:

04 June 2021

Report date:

07 June 2021

Report reference:

2031 gar0521oldarb





Table of Contents

Τá	able o	f Contents	2		
1.	Int	roduction	3		
	1.1	Purpose	3		
	1.2	Scope	3		
	1.3	Method	3		
	1.4	Limitations	3		
	1.5	Document control	4		
	1.6	Planning schemes and applicable overlays	4		
2.	Ob	servations	5		
	2.1	Site summary	5		
	2.2	Tree data	6		
3.	Dis	scussion	. 13		
	3.1	Encroachment / impacts on trees	. 13		
	3.2	Construction related activities	. 13		
	3.3	Pre-existing structures within tree protection zones	. 13		
	3.4	Eucalyptus pauciflora	. 13		
4.	Co	nclusion	. 14		
5.	Re	commendations	. 14		
6.	References		. 14		
7.	. Appendix 1: Arboricultural descriptors				
8.	3. Appendix 2. Protection of retained trees				
9	Arboricultural consultancy: Assumptions				

ADVERTISED PLAN





1. Introduction

1.1 Purpose

Oldmeadow Arboriculture has been engaged to undertake an objective assessment of any trees within the vicinity of the proposed construction of a 2-story dwelling located at 130 Great Alpine Road, Hotham Heights, Vic 3741.

The proposal involves the addition of a basement garage to the existing dwelling as well as other renovations including a deck to the north.

The purpose of this report is to identify and assess construction related impacts relating to assessed trees, and to provide a summary of the assessment herein.

1.2 Scope

- Based on the current proposal, determine which trees (the subject trees) within the area
 of assessment may be impacted by the proposed works.
- Visually assess trees from ground and collect the following data:
 - Tree number
 - Tree species
 - Approximate height and canopy spread (widest point)
 - Condition (health/structure)
 - Age/maturity
 - DBH (at 1.4 m above ground)
 - Defects This
- This copied document to be made available
- Assess the impact the proposed works are in each of the subject trees.
- The consideration and review as Comment on measure likely to be required to enable the protection of subject trees proposed to be retained a planning process under the proposed to be retained within the north facing declaration must not be used for any purpose which may breach any

1.3 Method

- A site visit was undertaken by Rhys Oldmeadow on 04 June 2021.
- All observations were taken at ground level, using stage 1 of the Visual Tree Assessment (VTA) method (Mattheck and Breloer 1994).

Documents viewed during the preparation of this report

 New Basement Plan. Project number AB01. Dated 16 Feb 2021. Prepared by Mango Property Services PTY LTD. Dd02 Rev L

1.4 Limitations

- The assessment was undertaken from ground and did not involve excavation; root condition was not investigated unless above ground signs were observed such as surface roots or cracking/heaving of the soil
- No instruments were used to record internal tree structure
- No aerial examination (climbing) was undertaken of the upper canopy
- Only noteworthy trees that might be significantly impacted by the proposed works (regardless of property boundaries) are included in this report
- Weeds, shrubs, dead trees and juvenile exotic trees of low amenity/retention value were not assessed individually



1.5 Document control

Current	Title	Туре	Date	Version	Author
>	2031 gar0521oldarb	Arboricultural impact report	07//06/2021	Α	Rhys Oldmeadow

1.6 Planning schemes and applicable overlays

The property is covered by the Alpine Planning Scheme and zoned as Comprehensive Development Zone – Schedule 1 (CDZ1)

Applicable overlays

- Bushfire management overlay (BMO)
- Erosion management overlay (EMO)
- Designated bushfire prone area





2. Observations

2.1 Site summary





ADVERTISED PLAN

The 1307sqm property supports an existing 2 story dwelling with stone foundations and shingle walls. The property is surrounded on 3 sides by indigenous *Eucalyptus pauciflora*, snow gums.

An existing, rudimentary drive approaches the property from the north west (behind where the photo in plate 1 was taken). There is also access to the rear of the property from Davenport Drive.



2.2 Tree data

2.2 Tree data	I	
TREE #	1	
NUM OF TREES	1	
SPECIES	Eucalyptus pauciflora	
COMMON NAME	Snow Gum	
DBH (CM)	33	
TPZ (M)	4	
HEIGHT (M)	5	
SPREAD (M)	6	
STRUCTURE	Good	
HEALTH	Good	
AGE	Mature	
AMENITY VALUE	Medium	
ULE (YRS)	>40	
NOTES	4m to existin	g decking
IMPACT	basement ex	4% encroachment from proposed driveway upgrade and underground cavation. Prune any exposed roots during excavation to Australian 73.
RECOMMENDATIONS	Install new d	nis copied document to be made available riveway others de Fract Descript a wrong ding the TPZ to protect oments described and review as
		part of a planning process under the
TREE #	2	Planning and Environment Act 1987. The document must not be used for any
NUM OF TREES		purpose which may breach any
SPECIES	Eucalyptus pauciflora	toorgott V
COMMON NAME	Snow Gum	
DBH (CM)		
TPZ (M)	2	
HEIGHT (M)	0	
SPREAD (M)	0	
STRUCTURE N/A		
HEALTH	N/A	
AGE	N/A	
AMENITY VALUE	Nil	
ULE (YRS)	0	
NOTES	Stump	
IMPACT	High. Propos	ed to be removed
RECOMMENDATIONS	Remove stun tree roots.	np to ground level or grind out carefully to prevent damage to adjacent





		TREE ARBO	
TREE #	3		
NUM OF TREES	3		
SPECIES	Eucalyptus pauciflora		
COMMON NAME	Snow Gum		
DBH (CM)	25		
TPZ (M)	3		
HEIGHT (M)	6		
SPREAD (M)	4		
STRUCTURE	Good		
HEALTH	Good		
AGE	Mature		
AMENITY VALUE	Medium		
ULE (YRS)	>40		
NOTES	Average DBH	of tree group. Several trees with multiple stems.	
IMPACT	Moderate ~15% encroachment from basement excavation. The trees will likely tolerate this degree of incursion; however, they may have some minor adverse impacts.		
RECOMMENDATIONS		ging surrounding the TPZ to protect from development related impacts. Stopped doors during excavation to Australian standard 4373. Tor the sole purpose of enabling	
		its consideration and review as	
TREE #	4	part of a planning process under the Planning are Engineers Act 1987.	
NUM OF TREES	1 7	The document most shot he used to care.	
SPECIES	Eucalyptus pauciflora	purpose which way breach are	
COMMON NAME	Snow Gum		
DBH (CM)	35		
TPZ (M)	4.2		
HEIGHT (M)	6		
SPREAD (M)	5		
STRUCTURE	Good		
HEALTH	Good		
AGE	Mature		
AMENITY VALUE	Medium		
ULE (YRS)	>40		
NOTES	Single tree wi	ith leaning form.	
IMPACT		6% encroachment from basement excavation. This tree will likely degree of incursion; however, it may have some minor adverse impacts.	
RECOMMENDATIONS		cing surrounding the TPZ to protect from development related impacts. posed roots during excavation to Australian standard 4373.	





	1	ARB TREI	
TREE #	5		
NUM OF TREES	1		
SPECIES	Eucalyptus pauciflora		
COMMON NAME	Snow Gum		
DBH (CM)	49		
TPZ (M)	5.9		
HEIGHT (M)	6		
SPREAD (M)	9		
STRUCTURE	Good		
HEALTH	Good		
AGE	Mature		
AMENITY VALUE	Medium		
ULE (YRS)	>40		
NOTES	DBH estima	ited from multiple stem calculation.	
IMPACT	Low – All w	orks should be outside of the TPZ. May be impacted by construction vities.	
RECOMMENDATIONS	Erect TPZ fo	encing surrounding the TPZ to protect from development related impacts.	
	7	This copied document to be made available	
TREE #	6	for the sole purpose of enabling its consideration and severe as	
NUM OF TREES	3	part of a planning process under the	
SPECIES	Eucalyptus	Planning and Eurocomment Act 198	
	pauciflora	The document must not be used for any purpose which may break it must	
COMMON NAME	Snow Gum	spreacht	
DBH (CM)	49		
TPZ (M)	5.9		
HEIGHT (M)	6		
SPREAD (M)	9		
STRUCTURE	Good		
HEALTH	Good		
AGE	Mature		
AMENITY VALUE	Medium		
ULE (YRS)	>40		
NOTES	Average DE	H of tree group estimated. 4m from existing dwelling.	
IMPACT	Low – No ground works are proposed within the TPZ of these trees. Could be impacted by construction related activities.		
RECOMMENDATIONS	Erect TPZ fo	encing surrounding the TPZ to protect from development related impacts	





		ARB TRE
TREE #	7	
NUM OF TREES	4	
SPECIES	Eucalyptu. pauciflora	
COMMON NAME	Snow Gun	
DBH (СМ)	45	
TPZ (M)	5.4	
HEIGHT (M)	6	
SPREAD (M)	4	
STRUCTURE	Good	
HEALTH	Good	
AGE	Mature	
AMENITY VALUE	Medium	
ULE (YRS)	>40	
NOTES	Average D	BH of tree group estimated. 5m from existing dwelling
IMPACT		ground works are proposed within the TPZ of these trees. Could be by construction related activities.
RECOMMENDATIONS	Erect TPZ	fencing surrounding the TPZ to protect from development related impacts
		This copied document to be made available
TREE #	8	for the sole purpose of enabling its consideration and reviewes
NUM OF TREES	15	part of a planning process under the
SPECIES	Eucalyptu pauciflora	The document must not be used for any
COMMON NAME	Snow Gun	purpose Watch may breach any
DBH (СМ)	22	
TPZ (M)	2.6	
HEIGHT (M)	6	
SPREAD (M)	4	
STRUCTURE	Good	
HEALTH	Good	A STATE OF THE STA
AGE	Mature	
AMENITY VALUE	Medium	
ULE (YRS)	>40	
NOTES	Average D trees	BH of tree group estimated. 4m from existing dwelling. Large group of
IMPACT		ground works are proposed within the TPZ of these trees. Could be by construction related activities.
RECOMMENDATIONS	Erect TPZ	fencing surrounding the TPZ to protect from development related impacts





		ARB TRE
TREE #	9	
NUM OF TREES SPECIES	Eucalyptu pauciflord	
COMMON NAME	Snow Gur	n
DBH (СМ)	37	
TPZ (M)	4.4	Carlo William
HEIGHT (M)	5	
SPREAD (M)	5	
STRUCTURE	Good	
HEALTH	Fair	
AGE	Mature	
AMENITY VALUE	Medium	
ULE (YRS)	15 > 40	
NOTES	Thin cano	py. 4m to existing dwelling.
IMPACT	excavatio May be fu pruning.	6 encroachment from basement car park excavation and concrete slab n. Depth of excavation unknown. urther impact by proposed deck depending on height, may require canopy
RECOMMENDATIONS	far as pra	plans to remove car space 3 to reduce impact. Or minimise excavation as cticable and undertaken in the presence of a chalified arborist. Prune any oots during excavation and such a chalified arborist.
		part of a planning process under the Planning and Environment Act 1987.
TREE #	10	The document most as the used for any
NUM OF TREES		purpose which may breach any
SPECIES	Eucalyptu pauciflord	
COMMON NAME	Snow Gur	n
DBH (СМ)	35	
TPZ (M)	4.2	
HEIGHT (M)	6	
SPREAD (M)	7	
STRUCTURE	Good	
HEALTH	Good	
AGE	Mature	
AMENITY VALUE	Medium	And the second
ULE (YRS)	>40	
NOTES	2 of 4 ste	ms removed already.
IMPACT	High. Pro	posed for removal
	1	



RECOMMENDATIONS Proposed for removal




		TRE	
TREE #	11		
NUM OF TREES	6		
SPECIES	Eucalyptus pauciflora		
COMMON NAME	Snow Gum		
DBH (CM)	21		
TPZ (M)	2.5		
HEIGHT (M)	6		
SPREAD (M)	3		
STRUCTURE	Good		
HEALTH	Good		
AGE	Mature	A WIND	
AMENITY VALUE	Medium		
ULE (YRS)	>40		
NOTES	Average DBH of tree group thin canopy		
IMPACT	Moderate ~14% encroachment. Impact could be less than calculated if the stone wall is built on grade without excavation. These trees will likely tolerate this degree of encroachment with some minor adverse impacts possible.		
RECOMMENDATIONS	Erect TPZ fencing surrounding the TPZ to protect from development related impacts.		

ADVERTISED PLAN

ADVERTISED PLAN



2.3 Site map





3. Discussion

3.1 Encroachment / impacts on trees

Works such as site cut and fill, re-grading, trenching, installation of underground services, building footings, landscaping or reducing the rain catchment within Tree Protection Zones (TPZ) are considered as encroachment. These activities may damage trees; this may be via direct (physical wounding) or indirect (soil alteration or compaction) impacts. Encroachment may result in wounds, decay, increased deadwood, thinning foliage, decreased health, instability, failures and death.

Likely impacts are assessed based on the degree of encroachment, the type of proposed works, the tree, and surrounding conditions.

3.2 Construction related activities

Trees without encroachment but in the vicinity of works may be impacted by construction related activities including, (but not limited to); compaction from vehicle parking, positioning of plant and/or foot traffic, and mechanical damage to trunk/branches from delivery/drop off of materials, etc.

Adequate tree protection measures including fencing or ground protection are important in preventing these impacts during construction.

3.3 Pre-existing structures within tree protection zones

None of the trees adjacent to the property and to the south have been detailed on the site plan as there are no planned earth works due to the pre-existing structure being retained. However, these trees are still at risk of construction related activities, see 3.2.

3.4 Eucalyptus pauciflora

E. pauciflora is a species of eucalypt to 30m tall or forming a mallee structure. Typically, when found in high altitudes (Hotham Heights), the tree presents as a small mallee structure forming a lignotuber. This makes it hard to determine if it is a single tree with multiple stems, or multiple small trees in close proximity.

E. pauciflora is a lignotuberous species of Eucalypt: "woody tubers developed in the axils of the cotyledons or the first few leaf pairs, becoming massive in many mature trees or mallees, possessing embedded vegetative buds for regeneration following crown destruction, for example by fire" (Brooker, M.I.H & Kleinig, D.A (2006)). As such they tend to regenerate from crown damage by producing new stems. However, *E. pauciflora* is fairly susceptible to the ingress and spread of decay. Root or canopy pruning can result in decay and cause dieback.







4. Conclusion

The arboricultural assessment undertaken at 130 Great Alpine Road, Hotham Heights, comprised 11 trees/tree groups. All trees assessed were *Eucalyptus pauciflora*, snow gums.

There are several trees not marked on the site plan to the south of the property that should not be directly impacted by the proposed works but may be exposed to construction related activities.

The below table illustrates the degree of impact vs the arboriculture/amenity value of the subject trees.

	Arboricultural/amenity value.		
Impact	Low	Medium	High
Low		2, 5, 6, 7, 8	
Moderate		1, 3, 4, 11	
High	2	9, 10	

Plate 2 Degree of impact x Retention value

5. Recommendations

This copied document to be made available

Tree 1 - Install new driveway on gradehe sade that sale that and review as the TPZ to protect from development related impacts its consideration and review as

part of a planning process under the

Tree 2, 10 – Remove tree/stumpling groundd Evel ion gried to Act to Bfully to prevent damage to adjacent tree roots.

The document must not be used for any

purpose which may breach any
Tree 3-4 - Erect TPZ fencing surrounding the TPZ to brotect from development related impacts.
Prune any exposed roots during excavation to Australian standard 4373.

Tree 5-8, 11 - Erect TPZ fencing surrounding the TPZ to protect from development related impacts. Prune any exposed roots during excavation to Australian standard 4373.

Tree 13 - Redesign plans to remove car space 3 to reduce impact. Or minimise excavation as far as practicable and undertake in the presence of a qualified arborist. Prune any exposed roots during excavation to Australian standard 4373.

General

- Install TPZ fencing at the extent of the provided TPZ radius in metres, except where truncated by proposed works, to prevent unnecessary access beneath tree canopies.
- Trees to be retained should be protected according to Australian Standard AS 4970-2009
 Protection of trees on development sites. Appendix 2. Protection of retained trees, provides guidance on activities restricted in Tree Protection Zones.
- Do no excavate or install underground services through Tree Protection Zones.

6. References

Australian Standard AS 4970-2009: Protection of Trees on Development Sites.

Australian Standard AS 4373-2007: Pruning of Amenity Trees





7. Appendix 1: Arboricultural descriptors

Age

Relates to the physiological stage of the tree's life cycle.

Category	Description
Juvenile	A young tree, given normal environmental conditions for that tree it will not yet flower or fruit.
Semi-mature	Able to reproduce yet still to achieve expected size in situation
Maturing	Specimen approaching expected size in situation, with reduced incremental growth
Over-mature	Tree is senescent and in decline

Arboricultural Rating/Amenity value

Arboricultural rating relates to a combination of tree condition factors, including health and structure (arboricultural merit), and also conveys an amenity value. Amenity relates to the trees biological, functional and aesthetic characteristics (Hitchmough 1994) within an urban landscape context. The presence of any serious disconnecting dependent to the sole purpose of enabling

Category	Description its consideration and review as	
High	Tree of high quality in good to fair condition. Ger erally a prominent arboricultural/landscape feature. These trees have the potential to be a medium – to long-term component of the landscape if managed appropriately. Retention of these trees is highly desirable.	
Moderate	Tree of moderate quality, in fair or better condition. Tree may have a condition, and or structural problem that will respond with arboricultural treatment. Often the majority of a mature tree population will fit into this category. It is therefore often further divided into classes A, B and C with A being the more desirable for retention. These trees have the potential to be a medium – to long-term component of the landscape if managed appropriately. Retention of these trees is generally desirable.	
Low	Unremarkable tree of low quality or little amenity value. Tree in either poor health or with poor structure or a combination. Tree is not significant because of either its size or age, such as young trees with a stem diameter below 15cm. These trees are easily replaceable. Tree (species) is functionally inappropriate to specific location and would be expected to be problematic if retained. Retention of such trees may be considered if not requiring a disproportionate expenditure of resources for a tree in its condition and location.	
None	Trees of low quality with an estimated remaining life expectancy of less that 5 years.	





Tree has either a sever structural defect or health problem or combination that cannot be sustained with practical arboricultural techniques and the loss of the tree would be expected in the short term.

Trees that are dead or are showing signs of significant, immediate, and irreversible overall decline. Tree infected with pathogens of significance to either the health or safety of the tree or other adjacent trees.

Trees whose retention would no be viable after the removal of adjacent trees (including trees that have developed in close spaced groups and would not be expected to acclimatise to severe alterations to surrounding environment – removal of adjacent shelter trees).

Tree has a detrimental effect on the environment, for example, the tree is recognised environmental woody weed with potential to spread into waterways or natural areas.

Unremarkable tree of no material landscape, conservation or other cultural value.

Trees have many values, not all of which are considered when an arboricultural assessment is undertaken. However, individual trees or tree group features may be considered important community resources because of unique or noteworthy characteristics or values other than their age, dimensions, health or structural condition. Recognition of one or more of the following criteria is designed to high light other considerations that may influence the future management of such trees.

This copied document to be made available

Significant	Description for the sole purpose of enabling
Horticultural Value/Rarity	Outstanding his consideration and review as Outstanding his consideration and review as outstanding profice the propagating stock, including specimens that are particularly resistance to disease or exposure, Any tree of a species or variety that is rare.
Historic, Aboriginal Cultural or Heritage Value.	Tree could have value as a remnant of a site or activity no longer in action. Tree has a recognised association with historic aboriginal activities, including scar trees. Tree commemorates a particular occasion, including plantings by notable people, or having association with an important event in local history.
Ecological Value	Tree could have value as habitat for indigenous wildlife, including providing breeding, foraging or roosting habitat, or is a component of a wildlife reserve. Remnant indigenous vegetation that contributes to biological diversity.

Condition

The assessment of tree condition evaluates factors of health and structure. The descriptors of

health and structure attributed to a tree evaluate the individual specimen to what could be considered typical for that species growing in its location. For example, some species can display inherently poor branching architecture, such as multiple acute branch attachments with included bark. Whilst these structural defects may technically be considered arboriculturally poor, they are typical for the species and may not constitute an increased risk of failure. These trees may be assigned a structural rating of fair-poor (rather than poor) at the discretion of the author.




Figure 1 Tree condition\ (Health & Structure)
Indicative normal distribution curve for tree
condition



Diagram 1, provides an indicative distribution curve for tree condition to illustrate that within a normal tree population the majority of specimens are centrally located within the condition range (normal distribution curve). Furthermore, that those individual trees with an assessed condition approaching the outer ends of the spectrum occur less often.

Diameter at Breast Height (DBH)

Indicates the trunk diameter (expressed in centimetres) of an individual tree measured at 1.4m above the existing ground level or where otherwise indicated, multiple leaders are measured individually. Plants with multiple leader habit may be measured at the base. The range of methods to suit particular trunk shapes, configurations and site conditions can be seen in Appendix A of Australian Standard *AS 4970-2009 Protection of trees on development sites*. Measurements undertaken with foresters Ø tape or builders tape.

HealthAssesses various attributes to describe the overall health and vigour of the tree.

Category	Vigour/Extensio growth	n Decline symptoms/Deadwo od	Foliage density, colour, size, intactness	Pests and or disease
Good	Above typical	None or minimal	Better than typical	None or minimal
Fair	Typical	Typical or expected copied document to be for the sole purpose o		Typical, within damage thresholds
Fair to Poor	Below typical	MS fensideration and part of a planning proce	revieliviting sølafidiendies	Exceeds damage thresholds
Poor	Minimal	The document must pot be purpose which may be amount/size	· •	Extreme and contributing to decline
Dead	N/A	N/A	N/A	N/A

Height and Width

Indicates height and width of the individual tree; dimensions are expressed in metres. Crown heights are measured with a laser height meter where possible. Due to the topography of some sites and/or the density of vegetation it may not be possible to do this for every tree. Tree heights may be estimated in line with previous height meter readings in conjunction with author's experience. Crown widths are generally paced (estimated) at the widest axis or can be measured on two axes and averaged. In some instances the crown width can be measured on the four cardinal direction points (North, South, East and West).

Name

Provides botanical name, (genus, species, variety and cultivar) according to accepted international code of taxonomic classification, and common name.







Structure

Assesses principal components of tree structure (Diagram 2).

Descriptor	Zone 1 - Root plate & lower stem	Zone 2 - Trunk	Zone 3 - Primary branch support	Zone 4 - Outer crown and roots
Good	No damage, disease or decay; obvious basal flare / stable in ground	No damage, disease or decay; well tapered	Well formed, attached, spaced and tapered	No damage, disease, decay or structural defect
Fair	Minor damage or decay. Basal flare present.	Minor damage or decay	Typically formed, attached, spaced and tapered	Minor damage, disease or decay; minor branch end- weight or over- extension
Fair to Poor	Moderate damage or decay; minimal basal flare	Moderate damage or decay; approaching recognised thresholds	Weak, decayed or with acute branch attachments; previous branch failure evidence	Moderate damage, disease or decay; moderate branch end-weight or over-extension
Poor	Major damage, disease or decay; fungal fruiting bodies present. Excessive lean placing pressure on root plate	Major damage, disease or decay; exceeds recognised thresholds; fungal fruiting bodies present. Acute lean. Stump resprout	Decayed, cavities or has acute branch attachments with included bark; excessive compression flaring; failure likely	Major damage, disease or decay; fungal fruiting bodies present; major branch end- weight or over- extension
Very Poor	Excessive damage, disease or decay; unstable / loose in ground; altered exposure; failure probable	Excessive damage, disease or decay; cavities. Excessive lean. Stump resprout	Decayed, cavities or branch attachments with active split; failure imminent	Excessive damage, disease or decay; excessive branch end-weight or over-extension






Structure ratings will also take into account general tree architecture which considers aspects of stem taper, live crown ratio, branch distribution or bias and crown position such as tree being suppressed amongst more dominant trees.

The lowest or worst descriptor assigned to the tree in any column could generally be the overall rating assigned to the tree. The assessment for structure is limited to observations of external and above ground tree parts. It does not include any exploratory assessment of underground or

Diagram 2: Tree structure zones

- 1. Root plate & lower stem
- 2. Trunk
- 3. Primary branch support
- 4. Outer crown & roots



internal tree parts unless this is requested as part of the investigation. Trees are assessed and the given a rating for a point in time. Generally, trees with a poor or very poor structure are beyond the benefit of practical arboricultural treatments.

The management of trees in the urban environment requires appropriate arboricultural input and consideration of risk. Ripkipotential dwill taken into a squetath and impact, including the for this edicapoptence of the integral input and impact, including the for this edicapoptence of the integral input and impact, including the for this edicapoptence of the integral input and impact, including the for this edicapoptence of the integral input and impact, including the for this edicapoptence of the integral input and impact, including the for this edicapoptence of the integral input and impact, including the for this edicapoptence of the integral input and impact, including the for the integral input and impact, including the for this edicapoptence of the integral input and impact, including the for this edicapoptence of the integral input and input and impact, including the for this edicapoptence of the integral input and impact, including the for this edicapoptence of the integral input and impact, including the for the integral input and impact, including the integral input and impact, including the integral input and impact, including the integral input and impact and impact, including the integral input and impact and imp

Type

its consideration and review as part of a planning process under the

Describes the general geographic origin of the species and its 1982, e.g., deciduous or evergreen.

	The document must not be used for any				
Category	Description purpose which may breach any				
Indigenous	Occurs naturally in the area or region of the subject site				
Victorian native	Occurs naturally within some part of the State of Victoria (not exclusively) but is not indigenous				
Australian native	Occurs naturally within Australia but is not a Victorian native or indigenous				
Exotic deciduous	Occurs outside of Australia and typically sheds its leaves during winter				
Exotic evergreen	Occurs outside of Australia and typically holds its leaves all year round				
Exotic conifer	Occurs outside of Australia and is classified as a gymnosperm				
Native conifer	Occurs naturally within Australia and is classified as a gymnosperm				
Native Palm	Occurs naturally within Australia. Woody monocotyledon				
Exotic Palm	Occurs outside of Australia. Woody monocotyledon				





8. Appendix 2. Protection of retained trees

Pruning standards / Lopping

An Australian standard exists to give guidance on pruning of trees.

It is important that all remedial works are carried out by a competent contractor in accordance with the Australian Standard. (AS. 4373 2007 - Pruning of Amenity Trees).

Lopping; as defined within the Standard, is detrimental to trees, often resulting in decay and poorly attached epicormic shoots. Natural Target Pruning methods should be used wherever possible when removing sections from trees.

Establishment of Tree Protection Zones

The tree protection zone (TPZ) is the principal means of protecting trees on development sites. Usually fencing will be used to delineate the Tree Protection Zones (TPZ) as defined by AS 4970-2009 Protection of trees on development sites.

Fencing is installed following permitted vegetation removal and pruning but prior to construction site establishment. Fencing should be retained until completion of all construction related activity.

Some works and activities within the TPZ may be authorised by the Responsible Authority. These works should be supervised by the project arborist. Any additional encroachment that becomes necessary as the site works progress should be reviewed by the project arborist and be acceptable to the Responsible Authority before being carried out (AS 4970--2009).

Activities restricted within the TPZ

A TPZ area may surround a single tree or group or a patch of vegetation, activities that must NOT be carried out within a TPZ include, but are not limited to, the following:

- (a) machine excavation including trenching;
- (b) excavation for silt fencing;
- (c) cultivation;
- (d) storage;
- (e) preparation of chemicals, including preparation of cement products;
- (f) parking of vehicles and plant;
- (g) refuelling;
- (h) dumping of waste;
- (i) wash down and cleaning of equipment;
- (j) placement of fill;
- (k) lighting of fires;
- (l) soil level changes;
- (m) vehicle movement access ways;
- (n) changes of grade;
- (o) temporary or permanent installation of utilities and signs, and
- (p) damage to the tree.

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987.

The document must not be used for any purpose which may breach any

Maintaining Tree Protection Zones (TPZ)

If at any time the TPZ must be infringed upon for works such as excavation for the installation of pipes or drainage or the movement of equipment or any other interference that may cause a change in the availability of water or oxygen to the tree, a suitably qualified arborist should be consulted to supervise the works and permission from the responsible authority may be required.



It may be possible to work or construct within a TPZ without significantly impacting a tree however the size and number of roots in the area would need to be determined and the specifics of the tree and its resilience to impacts would need to be reviewed prior to commencement. Design and construction methods may need alteration to minimise adverse tree impact.

AS 4970-2009 (extract)

Variations to the TPZ

General

It may be possible to encroach into or make variations to the standard TPZ. Encroachment includes excavation, compacted fill and machine trenching.

Minor encroachment

If the proposed encroachment is less than 10% of the area of the TPZ and is outside the SRZ detailed root investigations should not be required. The area lost to this encroachment should be compensated for elsewhere and contiguous with the TPZ.

Variations must be made by the project arborist considering relevant factors listed in (see standard) ...

Major encroachment

If the proposed encroachment is greater than 10% of the TPZ or inside the SRZ, the project arborist must demonstrate that the tree(s) would remain viable.

The area lost to this encroachment should be compensated for elsewhere and contiguous with the TPZ. This may require root investigation by non-destructive methods and consideration of relevant factors listed in (see standard)

Physical / mechanical damage to trees

Physical damage to tree parts, particularly the trunk, provides entry points for pests and diseases such as fungal infections. This may cause long-term decay and can lead to partial or complete tree failure and death.

Alteration of soil levels

Alteration of soil levels around trees will affect the root zone and stability of a tree as well as tree metabolism. This may result in reduced tree health, excessive deadwood, thinning foliage and poor vigour; it can take some years for the impact to become evident at which time it is normally irreversible.

Tree protection zone fencing

Protective fencing is used to delineate the TPZ. The fence must provide high visibility and act as a physical barrier to construction vehicles. No construction activity is to be undertaken within the fenced TPZ. The fence should be adequately signed, be sturdy and prevent the entry of heavy equipment, vehicles, workers and the public.





Once erected, protective fencing must not be removed or altered without approval by the project arborist or responsible authority. The TPZ should be secured to restrict access. Tree protection fencing will consist of chain wire mesh panels held in place with concrete feet. The tree protection zone shall be clearly signed "Tree Protection Zone – No Access".



Source – AS 4970-2009 Protection of trees on development sites

(Tree Protection)



Temporary access to the TPZ

When tree protection fencing cannot be installed or requires temporary removal, other tree protection measures should be used.

Where necessary, physical protection for the trunk and branches of trees should be installed. The materials and positioning of protection will be specified by the project arborist. A minimum height of 2m is recommended.

If temporary access for machinery is required within the TPZ, ground protection measures will be required. The purpose of ground protection is to prevent root damage and soil compaction within the TPZ. Measures may include a permeable membrane such as geotextile fabric beneath a layer of mulch or crushed rock below rumble boards. These measures may also be applied to root zones beyond the TPZ (see image).






Root protection during works within the TPZ

Works that have been approved by the Responsible Authority to occur within the TPZ, such as re-grading, installation of piers or landscaping have the potential to damage roots.

If the grade is to be raised the material should be coarser or more porous than the underlying material.

Depth changes and compaction should be minimized. Manual excavation should be carried out under the supervision of the project arborist to identify roots critical to tree stability and health. Relocation or redesign of works may be required.

Where the project arborist identifies roots to be pruned within or at the outer edge of the TPZ, they should be pruned with a final cut to undamaged wood.



Source - AS 4970-2009 Protection of trees on development sites

(Ground Protection)

Pruning cuts should be made with sharp tools such as secateurs, pruners, handsaws or chainsaws. Pruning wounds should not be treated with special glocument to be made available

for the sole purpose of enabling

It is not acceptable for roots within this 162150 derationed Wife Misching Process under the part of a planning process under the

Where roots within the TPZ are exposed by extavation, temporary foot protection should be installed to prevent them drying out. This may include just the first of the street ingress multiple layers over exposed roots and excavated soil profile, extending to the full depth of the root zone. Root protection sheeting should be pegged in place and kept moist during the period that roots are exposed.

Other excavation works in proximity to trees, including landscape works such as paving, irrigation and planting can adversely affect root systems, seek advice from the project arborist.

If temporary access is required within a Tree Protection Zone this may be carried out using sheets of heavy plywood or like protection but should not be considered for long term requirements.

Installing underground services within TPZ

All services should be routed outside the TPZ. If underground services must be routed within the TPZ, they should be installed by directional drilling or in manually excavated trenches using non-destructive methods such as Air or hydro excavation.

The directional drilling bore should be at least 600 mm deep. The project arborist should assess the likely impacts of boring and bore pits on retained trees.

Driveways and paving within TPZ's

Works should not encroach into a TPZ. If encroachment is unavoidable any hard surfaces such as paving or driveways should:

1. not require any scraping or excavation – most roots, particularly small absorbing roots, are shallow; within the upper 100mm of soil.



2. be constructed of a permeable material and laid on a base and subbase specifically designed to allow the movement of water through and into the soil below.

If construction is permitted within a TPZ it should be suspended on piers leaving the ground undisturbed other than the careful placement of pier holes. The bottom of supporting beams should be above existing ground level or, if this is not possible beams should run radially away from the tree trunk. There should be NO excavation of any description, including piers, within a Structural Root Zone (SRZ)





9. Arboricultural consultancy: Assumptions

- Any legal description provided to Oldmeadow Arboriculture is assumed to be correct. Any titles and ownerships to
 any property are assumed to be correct. No responsibility is assumed for matters outside the consultant's control.
- Oldmeadow Arboriculture assumes that any property or project is not in violation of any applicable codes, ordinances, statutes or other local, state or federal government regulations.
- Oldmeadow Arboriculture has taken care to obtain all information from reliable sources. All data has been verified
 insofar as possible; however Oldmeadow Arboriculture can neither guarantee nor be responsible for the accuracy of
 the information provided by others not directly under Oldmeadow Arboriculture's control.
- No Oldmeadow Arboriculture employee shall be required to give testimony or to attend court by reason of this report unless subsequent contractual arrangements are made, including payment of an additional fee for such services.
- Loss of this report or alteration of any part of this report not undertaken by Oldmeadow Arboriculture invalidates the entire report.
- Possession of this report or a copy thereof does not imply right of publication or use for any purpose by anyone but the client or their directed representatives, without the prior consent of Oldmeadow Arboriculture.
- This report and any values expressed herein represent the opinion of Oldmeadow Arboriculture's consultant and Oldmeadow Arboriculture's fee is in no way conditional upon the reporting of a specified value, a stipulated result, the occurrence of a subsequent event, nor upon any finding to be reported.
- Sketches, diagrams, graphs and photographs in this report, being intended as visual aids, are not necessarily to scale and should not be construed as engineering or architectural drawings, reports or surveys.
- Unless expressed otherwise: i) Information contained in this report covers only those items that were covered in the project brief or that were examined during the assessment and reflect the condition of those items at the time of inspection; and ii) The inspection is limited to visual examination of accessible components without dissection, excavation or probing unless otherwise stipulated.
- There is no warranty or guarantee, expressed or implied by Oldmeadow Arboriculture., that the problems or deficiencies of the plants or site in question may not arise in the future.
- All instructions (verbal or written) that define the scope of the report have been included in the report and all documents and other materials that the Oldmeadow Arboriculture consultant has been instructed to consider or to take into account in preparing this report have been included or listed within the report.
- To the writer's knowledge all facts, matter and all assumptions upon which the report proceeds have been stated within the body of the report and all opinion contained within the report have been fully researched and referenced and any such opinion not duly researched is based upon the writers experience and observations.

Precedent disclaimer

Disclaimer: Although Oldmeadow Arboriculture uses all due care and skill in providing you the information made available in this report, to the extent permitted by law Oldmeadow Arboriculture otherwise excludes all warranties of any kind, either expressed or implied.

To the extent permitted by law, you agree the Oldmeadow Arboriculture is not liable to you or any other person or entity for any loss or damage caused or alleged to have been caused (including loss or damage resulting from negligence), either directly or indirectly, by your use of the information (including by way of example, arboricultural advice) made available to you in this report. Without limiting this disclaimer, in no event will Oldmeadow Arboriculture be liable to you for any lost revenue or profits, or for special, indirect, consequential or incidental damage (however caused and regardless of the theory of liability) arising out of or related to your use of that information, even if Oldmeadow Arboriculture has been advised of the possibility of such loss or damage.

This disclaimer is governed by the law in force in the State of Victoria, Australia.

