

Fusion Project Management Pty Ltd

22 February 2023

Ref: 30N-22-0149-GCO-50694-0

Dear Jordan Hollett,

77 Sutton Street, North Melbourne - S72 Amendment

Vipac Engineers & Scientists Ltd was commissioned by **BEG Projects Pty. Ltd.** to carry out a wind tunnel test of the likely wind conditions for the proposed development at 77 Sutton Street, North Melbourne - refer to test report:

- Pedestrian Level Winds – Wind Tunnel Testing
Document Reference: 30N-22-0149-TRP-38115-2
Issue Date: 7th September 2022

Updated architectural and landscaping plans for the development were supplied in February 2023, and a comparison was made with the findings in the September 2022 report - refer to design review letter:


- Design Review
Document Reference: 30N-22-0149-ADM-50260-1
Issue Date: 22nd February 2023

Vipac concludes that there were no significant changes to the updated design that will alter the findings and conclusions of the wind report. As such, we make no further comments or recommendations for wind amelioration.

Should you have any queries regarding the information enclosed, please do not hesitate to contact us.

Yours sincerely,

Vipac Engineers & Scientists Ltd



Rumman Islam
Consulting Engineer

Fusion Project Management Pty Ltd

22 February 2023

Ref: 30N-22-0149-ADM-50260-1

Dear Jordan Hollett,

77 Sutton Street, North Melbourne - S72 Amendment

Vipac Engineers and Scientists completed a wind tunnel test and issued a report in September 2022 on the proposed development at 77 Sutton Street, North Melbourne (30N-22-0149-TRP-38115-2). Architectural plans of the updated design were supplied in January 2023 from Point Architects; and landscaping plans of the updated design were supplied in February 2023 (produced in September 2022) from Tract Landscape Architects. A comparison was made with the findings in the September 2022 report. The observations and findings are as follows:

- i) The recommended 1m high raised planter with a tree on top north of the pedestrian link on the ground level has been included in the updated landscaping plans (Figure 1);
- ii) The recommended 1m high raised planter adjacent to the Yoga Studio south west of the pedestrian link on the ground level has been included in the updated landscaping plans (Figure 1);
- iii) Raised planters on the southern pedestrian link on the ground level has been included in the updated landscaping plans, ranging from 0.5m to 1m high (Figure 1);
- iv) The entrance to the Airlock has been relocated to the west and setback by 1.5m, as recommended (Figure 2);
- v) There is a new entrance proposed at the west of the Food & Drink Premise north of site, which can be represented by Location 13 and 32 in the wind report – both locations measured wind speeds within the standing comfort criterion. As such, no further recommendation is provided (Figure 2);
- vi) The entrance to the Gym at the south east corner has been removed (Figure 2);
- vii) The southern entrance into the building has been setback, which is expected to be beneficial to the wind environment (Figure 2);
- viii) The seating area has been relocated immediately north of the Airlock, as recommended (Figure 2);
- ix) The recommended 1.8m high solid balustrades and 2-3m high trees at the northern communal terrace on Level 6 have been included in the updated landscaping plans (Figure 3). It should be noted that trees proposed are “deciduous heights”, which typically reach the recommended height. Pergola structures have also been proposed which are expected to be beneficial to the wind environment; and
- x) The recommended 1.8m high solid balustrades at the south eastern communal terrace on Level 6 have been included in the updated landscaping plans (Figure 4).

Vipac has reviewed the updated drawings and determined that the changes listed above are in line with the wind tunnel test results carried out in September 2022.

In conclusion, the architectural and landscaping plans received in January 2023 and September 2022 respectively of the proposed development have incorporated all of the recommended wind control measures and are expected to fulfil:

- The safety wind criterion at all test locations;
- The recommended walking comfort criterion at the pedestrian footpaths and accessways;
- The recommended standing comfort criterion at building entrance areas;
- The recommended sitting comfort criterion at the ground floor alfresco dining areas; and
- The recommended walking comfort criterion at the communal terrace areas.

As there were no other significant massing changes to the updated design, Vipac makes no further recommendations for wind amelioration to the January 2023 plans.

Yours sincerely,

Vipac Engineers & Scientists Ltd



Rumman Islam
Consulting Engineer



Eric Yuen
Wind Team Leader

Attachments




Figure 1: Landscaping plan (September 2022) showing the incorporated raised planters as recommended on the ground level.









Figure 2: Ground floor plan (January 2023) showing the incorporated wind control measures as recommended.




DECIDUOUS TREES

- 

Acer palmatum
Japanese Maple
- 

Acer rubrum 'Bowhall'
Red Maple
- 

Lagerstroemia indica x fauriei
'Tuscarora'
Crepe Myrtle
- 

Ulmus parvifolia 'Burnley Select'
Chinese Elm 'Burnley Select'

Figure 3: Landscaping plan (September 2022) showing the incorporated wind control measures as recommended on the northern communal terrace on Level 6.




Figure 4: Landscaping plan (September 2022) showing the incorporated wind control measures as recommended on the south eastern communal terrace on Level 6.



Figure 5: Northern elevation of the updated design (January 2023).

BEG Projects Pty Ltd

77 Sutton Street, North Melbourne - S72 Amendment

Pedestrian Level Winds - Wind Tunnel Testing





30N-22-0149-TRP-38115-2

7 September 2022

Job Title:	77 Sutton Street, North Melbourne - S72 Amendment
Report Title:	Pedestrian Level Winds - Wind Tunnel Testing
Document Reference:	30N-22-0149-TRP-38115-2

Prepared For:	Prepared By:
BEG Projects Pty Ltd	Vipac Engineers and Scientists Limited 279 Normanby Rd, Port Melbourne, VIC 3207, Australia
Contact: James Winstanley	
Tel:	Tel: +61 3 9647 9700

Author:	Rumman Islam		Consulting Engineer
	7 September 2022		
Reviewer:	Eric Yuen		Wind Team Leader
	28 Jul 2022		
Issued By:	Rumman Islam		Consulting Engineer
	7 Sep 2022		

Revision History:

Rev. #	Comments / Details of change(s) made	Date	Revised by:
Rev. 00	Original issue	28 Jul 22	
Rev. 01	Updated wind criteria	6 Sep 22	R. Islam
Rev. 02	Minor amendments	7 Sep 22	R. Islam

NOTE: This report has been prepared solely for the benefit of the client to whom this report is addressed for use herein ("Client") unless otherwise agreed in writing by Vipac Engineers and Scientists Limited ACN 005 453 627 ("Vipac"). Neither the whole of this report or any part of it may be published, duplicated or circulated without the prior written approval of Vipac except as required by law. Vipac does not assume any responsibility or liability for any losses suffered as a result of the publication, duplication or circulation of this report and excludes all liability whatsoever to any third party who may use or rely on the whole, or any part of this report.

Vipac has prepared this report using all reasonable care, skill and due diligence within the time period, budget and resources allocated to Vipac as agreed with the Client. Vipac excludes all liability to the Client whatsoever, whether in whole or in part, for the Client's use or reliance on the report other than for the purposes set out in the report, or any matters outside the agreed scope of the work.

For the purposes of preparing this report, reliance has been placed upon the material, representations, information and instructions provided to Vipac unless otherwise stated in the report. Originals of documents provided have not been required and no audit or examination of the validity of the documentation, representations, information or instructions provided has been undertaken except to the extent otherwise stated in this report. Information and findings contained in this report are based on Vipac's interpretation of data collected.

This document contains commercial, conceptual, engineering and other information that is proprietary to Vipac. The inclusion of this information in the report does not grant the Client any license to use the information without Vipac's prior written permission.

Executive Summary

BEG Projects Pty Ltd commissioned Vipac Engineers and Scientists Pty Ltd to carry out a wind tunnel test to determine the likely pedestrian level wind conditions for the proposed development at **77 Sutton Street, North Melbourne - S72 Amendment**.

The model was constructed based on drawings supplied by **Point Architects** in **July 2022**. The proposed development and surrounding buildings covering a circular area of approximately 500 m radius were modelled at a 1:400 scale. The approaching mean and turbulent flows of the Terrain Category 2.5 (40 to 120 azimuth degrees) and Terrain Category 3 (all other wind directions) Atmospheric Boundary Layer were modelled based on Australian Standard AS 1170.2-2011.

The findings of the study are summarised as follows:

The proposed design of the development:

- fulfils the recommended criterion for **Safety** at all test locations **with recommendations**;
- fulfils the recommended criterion for **Walking** at all footpath locations;
- fulfils the recommended criterion for **Standing** at all building entrances **with recommendations**;
- fulfils the recommended criterion for **Sitting** at all outdoor seating areas **with recommendations**;
- fulfils the recommended criteria for **Walking** within the plaza **with recommendations**; and
- fulfils the recommended criteria for **Walking** at all communal terraces **with recommendations**.

The proposed development would not cause a significant adverse impact on the adjacent areas.

As a general statement, common to all new developments, educating occupants about wind conditions at high-level terraces/balconies during high-wind events and tying down loose furniture are highly recommended.

Table of Contents

1	Introduction	5
1.1	Environmental Wind Effects.....	10
2	Regional Wind Climate	11
3	Assessment Criteria.....	12
3.1.1	Use of Adjacent Pedestrian Occupied Areas & Recommended Comfort Criteria.....	13
3.1.2	Terrace / balcony Recommended Criterion Discussion	13
4	Wind Tunnel Simulation.....	18
4.1	Similarity Requirements.....	18
4.2	Approach Wind Simulation	18
5	Test Procedure	21
6	Results and Discussion	26
6.1	Safety Criterion Test	30
6.2	Comfort Criteria.....	30
6.2.1	Pedestrian Footpath and Plaza	30
6.2.2	Main Building Entrances	30
6.2.3	Outdoor Seating Areas	30
6.2.4	Communal Terraces.....	32
6.2.4.1	Level 1	32
6.2.4.2	Level 6	32
6.2.4.3	Level 11	33
7	Conclusion	34
	Appendix A References	35
	Appendix B Drawing List.....	36
	Appendix C Omni Polar Plots - Gust Wind Speed (Safety Criterion).....	38
	Appendix D Up-crossing Prediction	54
	Appendix E References	56

1 Introduction

Vipac Engineers & Scientists Ltd was commissioned by **BEG Projects Pty Ltd** to carry out a wind tunnel test of the likely wind conditions for the proposed development at **77 Sutton Street, North Melbourne - S72 Amendment**.

The proposed development is a 12-storey residential tower with a building height of approximately 38.3m from street level. The site is bounded by Sutton Street to the north and existing developments in the remaining directions. A satellite image of the proposed development site, the south elevation of the building, and the ground floor plan with approximate dimensions overlaid are shown in Figure 1, Figure 2 and Figure 3, respectively.

The proposed development is predominantly surrounded within a 2.3 km radius by residential dwellings, with parklands and a golf course to the east and the Melbourne CBD to the southeast. Considering the immediate surroundings and terrain, the site of the proposed development is assumed to be within Terrain Category 2.5 for 40-120 azimuth degrees and Terrain Category 3 for all other directions (Figure 4).

This report details the pedestrian level wind assessment results of the tests carried out on a 1:400 scale model of the proposed development in Vipac's Boundary Layer Wind Tunnel in Melbourne, during July 2022. The results show the wind effects in ground level public areas adjacent to the development as proposed.

The pedestrian wind environment study of the development was conducted using Omni-directional pressure sensor techniques to predict wind velocities. The study investigated safety and comfort in ground level pedestrian access-ways adjacent to the project.

The model was constructed to drawings supplied by **Point Architects** in **July 2022**. Figure 5 and Figure 6 show the 1:400 scaled models in the wind tunnel. A complete list of the drawings used to construct the model is provided in Appendix A of this report.



Figure 1: Aerial view of the proposed development site.




Figure 2: Southern elevation of the proposed development.




Figure 3: Ground level plan with the overall dimensions overlaid.




Figure 4: Assumed terrain roughness for wind speed estimation.



Figure 5: Overall view from north of the 1:400 scale model of the proposed development in the wind tunnel.



Figure 6: Close up view from the north east of the 1:400 scaled model in the wind tunnel.

1.1 Environmental Wind Effects

Atmospheric Boundary Layer

As wind flows over the earth it encounters various roughness elements and terrain such as water, forests, houses and buildings. To varying degrees, these elements reduce the mean wind speed at low elevations and increase air turbulence. The wind above these obstructions travels with un-attenuated velocity, driven by atmospheric pressure gradients. The resultant increase in wind speed with height above ground is known as a wind velocity profile. When this wind profile encounters a tall building, some of the fast-moving wind at upper elevations is diverted down to ground level resulting in local adverse wind effects.

The terminology used to describe the wind flow patterns around the proposed Development is based on the aerodynamic mechanism, direction and nature of the wind flow.



Downwash – refers to a flow of air down the exposed face of a tower. A tall tower can deflect a fast-moving wind at higher elevations downwards.

Corner Accelerations – when wind flows around the corner of a building it tends to accelerate in a similar manner to airflow over the top of an aeroplane wing.

Flow separation – when wind flowing along a surface suddenly detaches from that surface and the resultant energy dissipation produces increased turbulence in the flow. Flow separation at a building corner or at a solid screen can result in gusty conditions.

Flow channelling – the well-known “street canyon” effect occurs when a large volume of air is funnelled through a constricted pathway. To maintain flow continuity the wind must speed up as it passes through the constriction. Examples of this might occur between two towers, in a narrowing street or under a bridge.

Direct Exposure – a location with little upstream shielding for a wind direction of interest. The location will be exposed to the unabated mean wind and gust velocity. Piers and open water frontage may have such exposure.



2 Regional Wind Climate

The mean and gust wind speeds have been recorded in the Melbourne area for over 30 years. The data from Melbourne International Airport wind station has been analysed and the directional probability distribution of wind speeds has been determined. The directional distribution of hourly mean wind speed at the gradient height, with a probability of 0.1% of time and 20% of time exceeded are shown in Figure 7. The wind data at this free stream height is common to all Melbourne city sites and may be used as a reference to assess ground level wind conditions at the site.




Figure 7: Directional Distribution of Mean Hourly Wind Velocities (m/s) for 0.1% and 20% exceeded at Gradient Height for Melbourne.

3 Assessment Criteria

The Better Apartment Guidelines Environment and Clause 58.04-4 criteria for wind impact were applied in the study. The document recommends the following wind comfort criteria (Table 1).

Table 1: Wind criteria.

Unsafe	Comfortable
Annual maximum 3 second gust wind speed exceeding 20m/sec with a probability of exceedance of 0.1% considering at least 16 wind directions.	Hourly mean wind speed or gust equivalent mean speed from all wind directions combined with probability of exceedance less than 20% of the time, equal to or less than: 3m/sec for sitting areas (outdoor cafés) 4m/sec for standing areas (window shopping, queuing) 5m/sec for walking areas (steady steps for most pedestrians)

This criterion specifically calls for the safety criterion to be used to assess infrequent winds (e.g. peak event of $\leq 0.1\%$ of the time); and the perceived pedestrian comfort to be assessed based on frequently occurring winds (e.g. winds that occurs 80% of the time).

The mean wind speed is hourly mean speed or gust equivalent mean (3 sec gust divided by 1.85), whichever is greater.

The Schedule specifies that safe and comfortable wind conditions must be achieved in publicly accessible areas within a distance equal to half the longest width of the building measured from all facades or half the overall height of the building, whichever is greater, as shown in Figure 8.




Figure 8: Assessment distance as detailed in Clause 58.04-4.

3.1.1 Use of Adjacent Pedestrian Occupied Areas & Recommended Comfort Criteria

The following table lists the specific areas adjacent to the proposed development and the corresponding criteria applications recommended.

Table 3 – Recommended applications of criteria.

Area	Specific location	Recommended Criteria
Public Footpaths and Accessways	Along Sutton Street and within site	Walking (Figure 9)
Plaza	West and south of the site	Walking (Figure 9)
Building Entrances	Along Sutton Street and within site	Standing (Figure 9)
Outdoor Seating Areas* ¹	Within the plaza	Sitting (Figure 9)
Communal Terraces	On Levels 1, 6 and 11	Walking (Figure 10 to Figure 12) (see discussion below)


Note 1: While the architectural plans do not show any outdoor seating areas, discussions with the client have indicated that seating areas will be proposed.

3.1.2 Terrace / balcony Recommended Criterion Discussion

Vipac recommends as a minimum that communal terrace areas meet the criterion for walking since:

- these areas are not public spaces;
- the use of these areas is optional;
- many similar developments in Melbourne and other Australian capital cities experience wind conditions on balconies and elevated deck areas in the vicinity of the criterion for walking.

However, it should be noted that meeting the walking criterion on elevated recreation areas will be no guarantee that occupants will find wind conditions in these areas acceptable at all times.



Recommended to fulfil Walking
 Recommended to fulfil Standing
 Recommended to fulfil Sitting

Figure 9: Ground level plan of the proposed development with the recommended wind criteria overlaid.





Figure 10: Level 1 floor plan with the recommended wind criteria overlaid.





 Recommended to fulfil Walking

Figure 11: Level 6 floor plan with the recommended wind criteria overlaid.




 Recommended to fulfil Walking

Figure 12: Level 11 floor plan with the recommended wind criteria overlaid.

4 Wind Tunnel Simulation

4.1 Similarity Requirements

The validity of wind tunnel testing relies on the similarity between model and full-scale parameters. This requires undistorted length scaling (ie. geometric similarity), similarity of flow parameters (i.e. kinematic similarity) and finally similarity of pressures and forces.

Complete similarity is usually impossible to obtain because of the competing requirements of the various non-dimensional parameters, (e.g. Reynolds Number, Rossby Number and Richardson Number). Some requirements (i.e. Reynolds Number equality) can be waived for sharp edged structures immersed in a neutrally stable atmospheric boundary layer and geometric and kinematic similarity suffice. These are the requirements specified in Section C1.4, AS/NZS 1170.2 Supplement 1: 2011 [4] and are employed in this study.

4.2 Approach Wind Simulation

The wind effects tests were carried out in the 3m wide × 2m tall × 16m long Boundary Layer Wind Tunnel at Vipac Engineers and Scientists Ltd in Melbourne. The Boundary Layer Wind Tunnel is designed to simulate the flow incident on a proposed development by modelling the upstream terrain characteristic roughness. To this end, an estimate of the upstream terrain properties for the Development has been made and reproduced in the wind tunnel.

The approaching mean and turbulent flows of the Terrain Categories 2.5 and 3 Atmospheric Boundary Layers based on different exposures were modelled based on Australia Standard AS 1170.2-2011. The wind tunnel calibration velocity and turbulence intensity profiles for Terrain Categories 2.5 and 3 are shown in Figure 13 and Figure 14. These represent the wind velocity and turbulence intensity profiles approaching the model of the development. Closer to the ground the wind moves more slowly but with increased turbulence. The simulated approach is indicative of full-scale planetary boundary layer velocity and turbulence intensity profiles.

Velocity correction factors are used to adjust the measured wind speed to ensure that the ratio of mean roof-height to reference height wind speed in the wind tunnel matches expected full-scale values.





Figure 13: Mean Velocity and Turbulence Intensity Profiles for Terrain Category 2.5 (1:400 scale).





Figure 14: Mean Velocity and Turbulence Intensity Profiles for Terrain Category 3 (1:400 scale).

5 Test Procedure

The pedestrian wind environment in the adjacent footpath areas along Sutton Street, plaza within the site and communal terrace areas were assessed using Omni-directional pressure sensor measurements [4].

Velocity measurements were made using Irwin sensors (Omni-directional pressure sensors) installed at different locations at the adjacent ground level footpath areas and podium level of the proposed development. The test was conducted without any landscaping. The distribution of Irwin sensors has allowed the determination of the variation in velocity sufficient to capture the changes in velocity distribution that can typically occur over such areas. The resolution of measurement locations is in accordance with that prescribed in the Wind Tunnel Testing Quality Assurance Manual of the Australasian Wind Engineering Society.

PVC tubes with 1.3 mm internal diameter linked the Irwin sensors to pressure transducer device using a tuned arrangement to prevent harmonic fluctuations.

Velocity measurements were obtained at 10° wind azimuth increments starting from 0° (north) for a full 360° circle. The sampling time is determined based on the similarity criteria and corresponds to a total time of one hour in full scale. Statistical analysis was carried out on the signals for the mean and standard deviation. All velocity coefficients derived from the wind tunnel were converted to velocities by integrating the data with the regional wind climate and corresponding to design wind speeds with a probability 0.1% of time for safety criterion assessment and 20% of time for comfort criteria assessment.

A total of **32** sensors were used in order to provide a quantitative measure of the ground level wind speeds at various locations around the footpaths and garden. The sensor locations are shown in Figure 15 to Figure 19.




Figure 15: Sensor numbers and locations on the ground level.




Figure 16: Sensor numbers and locations on the ground level (closeup).




Figure 17: Sensor numbers and locations on Level 1.




Figure 18: Sensor numbers and locations on Level 6.




Figure 19: Sensor numbers and locations on Level 11.

6 Results and Discussion

The pedestrian wind environment in the footpath, main entrances and outdoor communal terraces were assessed using omnidirectional pressure sensor tests.

The following configurations were conducted:

Configuration 1: test with the proposed development and existing surrounding developments (Figure 20).

Existing: A reference configuration of existing conditions (Figure 21).

The tests were conducted without any landscaping at the ground level streetscapes.



Figure 20: Overall view of the proposed development model in the wind tunnel (Configuration 1).



Figure 21: Overall view of the proposed development model in the wind tunnel (existing).

The test results are presented as polar plots for the gust wind speeds appended in Appendix A of this report. Figure 22 shows an example of these plots. In the figure, the red circle represents the velocities for the safety criterion and the three sets of data points represent the different test configurations and their predicted gust wind speeds for the 36 directions for Location 14.

The plot shows that with the proposed design, Location 14 was within the recommended safety criterion in Configuration 1. The shape of the graphs tells us that wind conditions are most adverse from the west / south west. However, the predicted hourly mean speed marginally exceeded the recommended walking comfort criterion (). Therefore, wind control measures were recommended for this location to achieve wind speeds within the walking comfort criterion.




Figure 22: Polar plot showing the wind speed compared with safety criteria (Location 14).

Figure 23 and Figure 24 show the comparison between the comfort criteria and predicted hourly mean wind speeds (maximum of statistic mean and GEM). In these figures, the colour lines represent the threshold velocities for the different criteria and the data series (bars) represent the predicted values of the mean velocities (WCM=Wind Control Measures). For the all wind direction combination, there are no particular methods specified in the BADS guidelines, the up-crossing prediction method described in Appendix D was used in the study. It is noted that all direction combined prediction could result in a slightly lower wind speed value than the maximum of direction-by-direction assessment values.

Comfort Criteria

Mean wind speed (20% probability)




Figure 23: Bar plot showing the wind speed compared with comfort criteria (Locations 1 - 21).

Comfort Criteria
 Mean wind speed (20% probability)




Figure 24: Bar plot showing the wind speed compared with comfort criteria (Locations 22- 32).

Based on the tests conducted, the following points were observed.

6.1 Safety Criterion Test

Most locations within the immediate vicinity of the proposed development measured gust windspeeds within the recommended safety criterion for the proposed development. The northern terraces at Level 6 (Locations 27 and 28) failed to meet this criterion for Configuration 1, and the recommended wind control measures will be discussed in Section 6.2.4.2.

6.2 Comfort Criteria

6.2.1 Pedestrian Footpath and Plaza

Most locations measured windspeeds within the recommended walking comfort criterion for Configuration 1.

Location 14 exceeded this criterion. As such, the planter north of this location is recommended to be raised by a minimum 1m.

Location 18 also exceeded the recommended walking comfort criterion. As such, a raised planter of minimum 1m height north of this location is recommended.

All recommendations discussed in this section are illustrated in Figure 25.

6.2.2 Main Building Entrances

Several building entrances (represented by Locations 8, 13, 16, 18, 19 & 20) measured windspeeds within the recommended standing comfort criterion for Configuration 1.

Location 16 measured wind speeds within the walking comfort criterion. The entrances near this location are setback from the building façade (entrances to the Café and Co-Working Business Centre 1). As such, this entrance is expected to be within the standing comfort criterion due to the set-back design. As such, no further recommendations for wind amelioration were required.

Location 18 measured wind speeds within the walking comfort criterion with the raised planter of 1m height (as recommended Section 6.2.1). As such, the entrance into the residential corridor is expected to be within the standing comfort criterion due to the set-back design. As such, no further recommendations for wind amelioration were required.

Location 19 measured wind speeds exceeding the recommended standing comfort criterion, and even exceeds the walking comfort criterion, for Configuration 1. As such, a raised planter of minimum 1m height east of this location is recommended to bring wind speeds down to within the walking comfort criterion; the entrance is then recommended to be setback from the building façade by minimum 1.5m to ensure wind speeds will be within the standing comfort criterion.

Location 20 measured wind speeds exceeding the recommended standing comfort criterion for Configuration 1. However, the 1m high raised planter recommended above brings wind speeds down to within the standing comfort criterion.

All recommendations discussed in this section are illustrated in Figure 25.

6.2.3 Outdoor Seating Areas

As per discussions with the client, seating areas will be proposed in the future, represented by Locations 16 and 32.

Location 16 measured wind speeds well within the walking comfort criterion for Configuration 1. However, in consideration of the location of the seating area (within the setback and under the building overhang) and the landscaping proposed between the plaza and the setback, this area will be shielding from all directions. As such, no adverse winds are expected and wind speeds will be within the recommended sitting comfort criterion at this location.

Location 32 measured wind speeds within the standing comfort criterion for Configuration 1. As such, the seating area is recommended to be relocated towards Location 13; this would subsequently result in relocation of the entrance at Location 13, and we recommend this Airlock entrance to be relocated to the west and setback by 1.5m. A 2-3m high tree is also recommended at the northern planter (Figure 25).




Figure 25: Recommended wind control measures overlaid on the ground floor plan.

6.2.4 Communal Terraces

6.2.4.1 Level 1

The communal terrace on Level 1, represented by Locations 25 & 26, measured wind speeds within the most stringent sitting comfort criterion for Configuration 1. As such, no recommendation for wind amelioration was provided.

6.2.4.2 Level 6

The northern communal terrace on Level 6, represented by Locations 27 & 28, measured wind speeds exceeding the recommended walking comfort criterion for Configuration 1. As such, 1.8m high solid balustrades along the perimeter and 2-3m high trees are recommended at this terrace.

The south eastern communal terrace, represented by Location 29, also measured wind speeds exceeding the recommended walking comfort criterion for Configuration 1. As such, 1.8m high solid balustrades along the perimeter are recommended.

All recommendations discussed in this section are illustrated in Figure 26.

It should be noted that testing was performed as per the architectural drawings. Should the design elements be considered as per the landscaping plans dated 2/06/2022 by Tract Landscape Architects (landscaping at other locations and arbour structures), wind speeds are expected to improve and be within the most stringent sitting comfort criterion.




Figure 26: Recommended wind control measures overlaid on the Level 6 floor plan.

6.2.4.3 Level 11

The communal terrace on Level 11 is represented by Locations 30 & 31. While Location 30 measured wind speeds within the more stringent standing comfort criterion and Location 31 measured wind speeds within the recommended walking comfort criterion. As such no recommendations for wind amelioration was provided.

It should be noted that testing was performed as per the architectural drawings. Should the design elements be considered as per the landscaping plans dated 2/06/2022 by Tract Landscape Architects (landscaping and arbour structures), wind speeds are expected to improve and be within the most stringent sitting comfort criterion.

7 Conclusion

Vipac has carried out an assessment of the pedestrian level winds for the proposed development at **77 Sutton Street, North Melbourne** - S72 Amendment based on a scaled wind tunnel test.

The findings of the study are summarised as follows:

The proposed design of the development:

- fulfils the recommended criterion for **Safety** at all test locations **with recommendations**;
- fulfils the recommended criterion for **Walking** at all footpath locations;
- fulfils the recommended criterion for **Standing** at all building entrances **with recommendations**;
- fulfils the recommended criterion for **Sitting** at all outdoor seating areas **with recommendations**;
- fulfils the recommended criteria for **Walking** within the plaza **with recommendations**; and
- fulfils the recommended criteria for **Walking** at all communal terraces **with recommendations**.

The proposed development would not cause significant adversely impact to the adjacent areas.

As a general statement, common to all new developments, educating occupants about wind conditions at high-level terraces/balconies during high-wind events and tying down loose furniture are highly recommended.

Appendix A References

1. Australian/New Zealand Standard 1170.2:2002, Wind actions
2. Melbourne, W. H., "Criteria for Environmental Wind Conditions", Jour. Industrial Aerodynamics, Vol. 3, 241-249, 1978
3. Simiu E, Scanlan R, "*Wind Effects on Structures*". Wiley-Interscience
4. Aynsley R., Melbourne W., Vickery B., *Architectural Aerodynamics* Applied Science Publishers

Appendix B Drawing List

Received July 2022:

Architectural Drawings

Name



1015_A000_DRAWING REGISTER_T2.pdf
1015_A010_SITE PLAN_T2.pdf
1015_A100_BASEMENT LEVEL 2 FLOOR PLAN_T2.pdf
1015_A101_BASEMENT LEVEL 1 FLOOR PLAN_T2.pdf
1015_A102_GROUND LEVEL FLOOR PLAN_T2.pdf
1015_A103_LEVEL 1 FLOOR PLAN_T2.pdf
1015_A104_LEVEL 2 FLOOR PLAN_T2.pdf
1015_A105_LEVEL 3 FLOOR PLAN_T2.pdf
1015_A106_LEVEL 4 FLOOR PLAN_T2.pdf
1015_A107_LEVEL 5 FLOOR PLAN_T2.pdf
1015_A108_LEVEL 6 FLOOR PLAN_T2.pdf
1015_A109_LEVEL 7 FLOOR PLAN_T2.pdf
1015_A110_LEVEL 8 FLOOR PLAN_T2.pdf
1015_A111_LEVEL 9 FLOOR PLAN_T2.pdf
1015_A112_LEVEL 10 FLOOR PLAN_T2.pdf
1015_A113_LEVEL 11 FLOOR PLAN_T2.pdf
1015_A114_ROOF PLAN_T2.pdf
1015_A300_BASEMENT LEVEL 2 REFLECTED CEILING PLAN_T2.pdf
1015_A400_ELEVATIONS SHEET 1_T2.pdf
1015_A401_ELEVATIONS SHEET 2_T2.pdf
1015_A402_ELEVATIONS SHEET 3_T2.pdf
1015_A403_ELEVATIONS SHEET 4_T2.pdf
1015_A500_SECTION A-A_T2.pdf
1015_A501_SECTION B-B_T2.pdf
1015_A502_SECTION C-C_T2.pdf
1015_A503_SECTION D-D_T2.pdf
1015_A504_SECTION E-E_T2.pdf
1015_A505_SECTION F-F_T2.pdf
1015_A506_SECTION G-G_T2.pdf
1015_A507_SECTION H-H_T2.pdf



Received July 2022:



Landscape Drawings



<u>DRAWING NUMBER</u>	<u>DRAWING TITLE</u>
319-0673-00-L-03 DR-101	- COVER SHEET
319-0673-00-L-03 DR-102	- LANDSCAPE SPECIFICATION
319-0673-00-L-03 DR-103	- LANDSCAPE SCHEDULE - MATERIAL & FINISHES
319-0673-00-L-03 DR-104	- LANDSCAPE SCHEDULE - PLANTING
319-0673-00-L-03 DR-300	- GENERAL ARRANGEMENT PLAN 01 - GROUND FLOOR
319-0673-00-L-03 DR-301	- GENERAL ARRANGEMENT PLAN 02 - LEVEL 01
319-0673-00-L-03 DR-302	- GENERAL ARRANGEMENT PLAN 03 - LEVEL 06
319-0673-00-L-03 DR-303	- GENERAL ARRANGEMENT PLAN 04 - LEVEL 11
319-0673-00-L-03 DR-304	- GENERAL ARRANGEMENT PLAN 05 - SOUTHERN LANEWAY (INTERIM)
319-0673-00-L-03 DR-305	- PLANTERS & SOIL VOLUME PLAN 01 - GROUND FLOOR
319-0673-00-L-03 DR-306	- PLANTERS & SOIL VOLUME PLAN 02 - LEVEL 01
319-0673-00-L-03 DR-307	- PLANTERS & SOIL VOLUME PLAN 03 - LEVEL 06
319-0673-00-L-03 DR-308	- PLANTERS & SOIL VOLUME PLAN 04 - LEVEL 11
319-0673-00-L-03 DR-400	- PLANTING PLAN 01 - GROUND FLOOR
319-0673-00-L-03 DR-401	- PLANTING PLAN 02 - LEVEL 01
319-0673-00-L-03 DR-402	- PLANTING PLAN 03 - LEVEL 06
319-0673-00-L-03 DR-403	- PLANTING PLAN 04 - LEVEL 11
319-0673-00-L-03 DR-404	- PLANTING PLAN 05 - SOUTHERN LANEWAY (INTERIM)
319-0673-00-L-03 DR-600	- LANDSCAPE DETAILS 1 MCC - PAVING
319-0673-00-L-03 DR-601	- LANDSCAPE DETAILS 2 MCC - FURNITURE
319-0673-00-L-03 DR-602	- LANDSCAPE DETAILS 3 ON-STRUCTURE - PAVING
319-0673-00-L-03 DR-603	- LANDSCAPE DETAILS 4 ON-STRUCTURE - PLANTERS
319-0673-00-L-03 DR-604	- LANDSCAPE DETAILS 5 ARBOUR STRUCTURE
319-0673-00-L-03 DR-605	- LANDSCAPE DETAILS 6 FENCING
319-0673-00-L-03 DR-606	- LANDSCAPE DETAILS 7 CUSTOM FURNITURE & JOINERY
319-0673-00-L-03 DR-607	- LANDSCAPE DETAILS 8 SOFT LANDSCAPE



Appendix C Omni Polar Plots - Gust Wind Speed (Safety Criterion)























































Appendix D Up-crossing Prediction

The up-crossing method was used at Boundary Layer Wind Tunnel Laboratory, University of Western Ontario decades ago and adapted at VIPAC recently. The methodology is based on the following theory.

The expected number of excursions beyond a level x per unit time, or the rate of crossing with positive slope, according to Rice's theory (D.2), is given by:

$$N_x(x) = \int_0^{\infty} \dot{x} p(x, \dot{x}) dx \quad (1)$$

where \dot{x} is the rate of change of x and $p(x, \dot{x})$ is the joint probability density function of x and \dot{x} . For a stationary random process, x and \dot{x} are statistically independent, thus

$$p(x, \dot{x}) = p(x) p(\dot{x}) \quad (2)$$

For a Gaussian process,

$$\int_0^{\infty} \dot{x} p(\dot{x}) d\dot{x} = \frac{\sigma_{\dot{x}}}{\sqrt{2\pi}} \quad (3)$$

where $\sigma_{\dot{x}}$ is the standard deviation of $\dot{x}(t)$. Thus, the crossing rate now becomes

$$N_x(x) = \frac{\sigma_{\dot{x}}}{\sqrt{2\pi}} p(x) \quad (4)$$

The statistical frequency or the cycling rate of process $x(t)$ is defined as

$$\nu = \frac{1}{2\pi} \frac{\sigma_{\dot{x}}}{\sigma_x} \quad (5)$$

Substituting this in equation (4) yields

$$N_x(x) = \sqrt{2\pi} \nu \sigma_x p(x) \quad (6)$$

Extending Rice's theory, Davenport (D.3) has shown that for a two-dimensional variable, $x = x(V, \alpha)$, the crossing rate of a particular boundary $x = x_1$ becomes:

$$N_x(x) = \sqrt{2\pi} \nu \sigma \int_0^{2\pi} \sqrt{1 + \left(\frac{dV_1}{V_1 d\alpha} \right)^2} p_V(V_1, \alpha) d\alpha \quad (7)$$

where $x_1 = x(V_1, \alpha)$ and $p_V(V, \alpha)$ is the joint probability density function of V and α .

Approximating the probability distribution of the wind speed V and the direction α by a generalized Weibull distribution,

$$p_V(> V, \alpha) = A(\alpha) e^{-|V/C(\alpha)|^{K(\alpha)}} \quad (8)$$

the probability density function of V and α becomes

$$p_V(V, \alpha) = A(\alpha) \frac{K(\alpha)}{C(\alpha)} \left(\frac{V}{C(\alpha)} \right)^{K(\alpha)-1} e^{-|V/C(\alpha)|^{K(\alpha)}} d\alpha \quad (9)$$

Hence the crossing rate of a particular boundary $x_1 = x_1(V_1, \alpha)$ from Equation (7) becomes:

$$N_x(x_1) = \sqrt{2\pi} \nu \sigma \int_0^{2\pi} \left\{ 1 + \frac{dV_1}{V_1 d\alpha} \right\}^{\frac{1}{2}} A(\alpha) \frac{K(\alpha)}{C(\alpha)} \left(\frac{V}{C(\alpha)} \right)^{K(\alpha)-1} e^{-|V/C(\alpha)|^{K(\alpha)}} d\alpha \quad (10)$$

The cycling rate, ν , and the standard deviation, σ , in Equation (10) are taken as those of the wind speed, V , regardless of direction; namely they are based on the marginal statistical properties of V and \dot{V} . With ν expressed in terms of occurrences per annum, $N_x(x_1)$ gives the yearly crossing rate.

The return period, or the average interval of time between events during which the response equals or exceeds the response boundary $x = x_1$, is the inverse of the crossing rate of that boundary. Consequently, from Equation (10) the return period for the response level $x = x_1$ in years is taken as

$$R_x(x_1) = \frac{1}{N_x(x_1)} \quad (11)$$

The risk of exceeding the response level associated with the return period $R_x(x_T)$ in a time period L is:

$$r(x_T) = 1 - \left(1 - \frac{1}{R_x(x_T)} \right)^L \quad (12)$$

From the above equation, the risk of exceeding x_T within a time interval of $L = R_x(x_T)$ is approximately 63 percent.

Appendix E References

- [D.1] Irwin, P, Garber, J and Ho, E., "Integration of Wind Tunnel Data with Full Scale Wind Climate", 10th Americas Conference on Wind Engineering, Baton Rouge, Louisiana, U.S.A., May 2005.
- [D.2] Rice, S.O., "Mathematical Analysis of Random Noise", Bell Tech. Journal Vol. 18 and 19, 1945.
- [D.3] Davenport, A.G., "The Prediction of Risk Under Wind Loading", 2nd International Conf. on Structural Safety and Reliability (ICOSSAR), Sept. 1977, Munich Germany.