



Leigh Design

waste management plans for all urban developments

Leigh Design Pty Ltd

ABN 37 139 522 437

PO Box 115

Carnegie VIC 3163

P +61 3 8516 5399

E leo@leighdesign.com.au

I www.leighdesign.com.au

Waste Management Plan



Proposed Redevelopment: Simonds College

235-273 Victoria Street, West Melbourne, Victoria

Prepared for:

Simonds Catholic College

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright.

Document Control

**ADVERTISED
PLAN**

Report Date: 3 August 2021 (supersedes report dated 15 December 2020)

Prepared By: Leonardo Russi, BEng (Mech), MEng (Env)

Leigh Design retains copyright and intellectual property rights on this document. Except for planning purposes associated with the above-referenced site, it may not be copied or used in whole or part by any person or entity for this or any other site without prior written consent from Leigh Design.

ADVERTISED PLAN

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

TABLE OF CONTENTS

SECTION	PAGE No.
Waste Management Summary.....	2
Glossary.....	2
1 Space and System for Waste Management.....	3
2 Access for Users, Collectors, and Collection Vehicles	6
3 Amenity, Local Environment, and Facility Design	7
4 Management and Sustainability.....	8
5 Supplementary Information.....	10
6 Contact Information	11
7 Limitations	11
Enclosures:	
- Site Plan with waste storage / collection details	
- Refuse vehicle swept path diagrams	

WASTE MANAGEMENT SUMMARY

- The Operator, as defined below, shall be responsible for managing the waste system and for developing and implementing adequate safe operating procedures.
- Waste shall be stored within the development (hidden from external view).
- Users shall sort their waste and dispose garbage and recyclables into designated collection bins.
- Waste shall be collected within the development and on Howard Street. The collection contractor shall transfer bins between the waste areas and the truck.
- A private contractor shall provide waste collection services.

GLOSSARY

Operator: refers to the Facility Management, who shall manage site operations (via cleaners, staff and contractors, if required).

User: refers to students and school teachers/staff, who shall utilise the waste system.

ADVERTISED PLAN

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

1 SPACE AND SYSTEM FOR WASTE MANAGEMENT

1.1 Development Description and Use

This redevelopment shall consist of alterations to an existing school (refer to Table 1).

Note: The existing waste system shall be adjusted to accommodate added waste from the extension.

1.2 Estimated Garbage and Recycling Generation

The following table summarises the waste estimate (m³/week):

Table 1: Waste Estimate

Waste Source	Base Qty (est.)	Garbage	Commingled Recycling
Simonds College	No. of students = 668	18.70	2.10
TOTAL (m³/wk)		18.70	2.10

Note: Waste figures are based on information from similar facilities. 1m³ = 1,000 litres.

1.3 Collection Services

Based on the anticipated waste volume, a private contractor shall be required to collect waste. The Operator shall choose a waste collection provider, negotiate a service agreement, and pay for these services.

Note: Every rateable tenement is liable to pay for municipal charges irrespective of the level of collection services provided by Council.

1.4 Location, Equipment, and System Used for Managing Waste

The waste management system is summarised as follows:

- Internal receptacles in work/amenity areas.
- Three Bin Stores located at Ground Level.
- Collection bins (kept within the above Bin Stores - refer to Table 2).

The various collection waste-streams are summarised as follows:

Garbage: General waste shall be placed in tied plastic bags and stored within bins.

Recycling: All recyclables shall be commingled into a single type of collection bin (for loose paper, cardboard, glass, aluminium, steel, and plastics).

Green Waste: Garden organics shall be collected and disposed by the future landscape maintenance contractor.

Food Organics: Users shall place selected compostable waste into Organics bins (acceptable materials generally include: food scraps, raw vegetables, coffee grinds, tea bags, paper towels/serviettes, and flowers), subject to service availability. Approved compostable liners are recommended for these bins.

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

Other Waste Streams: The disposal of hard/electronic/liquid and other wastes (polystyrene, batteries, paint, chemicals and detox items, etc) shall be organised with the assistance of the Operator.

These items (including e-waste) shall remain within the development until the Operator arranges a private collection from the subject land in accordance with requirements from the relevant authority. In particular e-waste must not be disposed in landfill.

The Operator shall arrange the storage of used cooking oil and its collection by a recycler and shall organise Grease Interceptor Trap servicing, if any.

The following table summarises bin quantity/capacity, collection frequency, and area requirements (based on Table 1):

Table 2: Bin Schedule and Collection Frequency

Waste Source	Waste Stream	Bin Qty	Bin Litres	Collections per Week	Net Area m²
Simonds College	Garbage	6	1,100	3	9.6
	Recycling	3	240	3	1.5
	Organics	5	240	3	2.5
	Hard/E-Waste/Other	-	-	At Call	3.0
Net Waste Storage Area (excludes circulation), m²:					16.6

Notes:

- The Operator shall organise hard/e-waste/other waste collections (as required).
- Should waste office paper require confidential disposal, the operator shall organise 120 litre private secured paper bins.
- Private bins shall be sourced by the Operator (either purchased from a supplier or leased from the collection contractor).

1.5 Planning Drawings, Waste Areas, and Management of the Waste System

The enclosed plan illustrates sufficient space for onsite bin storage, as required by the above schedule.

Notwithstanding the above, collection days shall be staged appropriately and the Operator shall stipulate procedures for effective management of the available space.

**ADVERTISED
PLAN**

1.6 Collection Bin Information

The following bins shall be utilised (see Sect. 4.4 for signage requirements):

Table 3: Bin Details

Capacity (litres)	Height (mm)	Width (across front, mm)	Depth (side on, mm)	Empty Weight (kg)	Average* Gross Weight (kg)
120	930	480	545	10	26
240	1060	585	730	13	45
1100	1330	1240	1070	65	210

Notes:

- * = Average Gross Weight is based on domestic waste studies (which vary subject to locality and waste-type). Expect greater weight for wet or compacted waste.
- Use the above details as a guide only – variations will occur. The above is based on Sulo plastic (HDPE) flat-lid bins.

Table 4: Melbourne Colour Coding

Bin	Garbage	Commingled Recycling
Lid	Red	Yellow
Body	Green	Green

Note: For private bins, AS4123.7 bin colours can be adopted. Private bins shall be labelled to identify the waste generator and site address. For Food Waste / organics bins, AS 4123.7 bins have a Burgundy lid and a Dark Green or Black body.

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

**ADVERTISED
PLAN**

2 ACCESS FOR USERS, COLLECTORS, AND COLLECTION VEHICLES

2.1 User Access to Waste Facilities

Users shall dispose sorted waste into waste receptacles. The operator shall transfer waste to the collection bins (if required, using a suitable trolley and the lift).

Note: If required, the operator shall have access to the Bin Stores to rotate the bins, ensuring that empty bins are available along the circulation area so that users are able to reach them.

2.2 Collection Arrangements and Access to Waste Facilities

- A private contractor shall collect waste within the onsite playground off-Victoria Street and on Howard St (site's frontage).
- Collection staff (driver and assistant) shall have access to the Bin Stores and transfer bins to the truck and back to the stores.
- The waste collection shall be carried-out by rear-lift vehicles (nom. 6.4m long, 2.1m high, and 6.4 tonnes gross vehicle mass, needing a 2.5m high clearance when lifting 1100L bins).
- Waste collections shall occur outside school hours.

The enclosed plans illustrate the waste system. Also, the enclosed Swept Paths illustrate truck access.

**ADVERTISED
PLAN**

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

ADVERTISED PLAN

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

3 AMENITY, LOCAL ENVIRONMENT, AND FACILITY DESIGN

3.1 Noise Minimisation Initiatives

- Collection bins shall feature rubber wheels for quiet rolling during transfers.
- Waste areas shall meet BCA and AS2107 acoustic requirements.
- Local laws shall be observed for all operations in public and private areas.
- Waste collection times shall be as per Council's local laws. Also, the collector shall protect the acoustic amenity by minimising noise during the collection.

3.2 Litter Reduction and Prevention of Stormwater Pollution

The Operator shall be responsible for:

- Promoting adequate waste disposal into the bins (to avoid waste-dumping).
- Securing the waste areas (whilst affording access to users/staff/contractors).
- Preventing overfilled bins, keeping lids closed and bungs leak-free.
- Abating any site litter and taking action to prevent dumping and/or unauthorised use of waste areas.

The above will minimise the dispersion of site litter and prevent stormwater pollution (thus avoiding impact to the local amenity and environment).

3.3 Ventilation, Washing, and Vermin-Prevention Arrangements

Waste areas shall feature:

- Ventilation in accordance with Australian Standard AS1668.
- Impervious flooring (also, smooth, slip-resistant, and appropriately drained).
- A graded bin wash area, hot and cold mixing hosecocks, hose, and a suitable floor-waste connected in accordance with relevant authority requirements (alternatively, the Operator shall engage a suitable contractor to wash bins in a mobile bin-wash vehicle). The bin and wash areas may overlap, as stored bins can be moved so that a bin can be washed.

The Operator shall regularly clean waste areas/equipment. Also, access doors and bin-lids shall be kept closed.

3.4 Design and Aesthetics of Waste Storage Areas and Equipment

Waste shall be placed within collection bins and stored in designated onsite areas (hidden from external view). Following waste collection activities, bins shall be returned to the storage areas as soon as practicable.

Waste facilities shall be constructed of durable materials and finishes, and maintained to ensure that the aesthetics of the development are not compromised. These facilities and associated passages shall be suitably illuminated (this provides comfort, safety, and security to users, staff, and contractors). Any access doors shall feature keyless opening from within.

The design and construction of waste facilities and equipment shall conform to the Building Code of Australia, Australian Standards, and local laws.

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

4 MANAGEMENT AND SUSTAINABILITY

4.1 Waste Sorting, Transfer, and Collection Responsibilities

Garbage shall be placed within tied plastic bags prior to transferring into collection bins. Cardboard shall be flattened and recycling containers un-capped, drained, and rinsed prior to disposal into the appropriate bin. Bagged recycling is not permitted.

Refer to Section 2 for waste transfer requirements and collection arrangements.

4.2 Facility Management Provisions to Maintain & Improve the Waste System

The Operator shall manage site operations (refer to the glossary in page 2).

It shall be the responsibility of the Operator to maintain all waste areas and components, to the satisfaction of users, staff, and the relevant authority (users shall maintain their internal waste receptacles).

The Operator shall ensure that maintenance and upgrades are carried-out on the facility and components of the waste system. When required, the Operator shall engage an appropriate contractor to conduct services, replacements, or upgrades.

4.3 Arrangements for Protecting Waste Equipment from Theft and Vandalism

It shall be the responsibility of the Operator to protect the equipment from theft and vandalism. This shall include the following initiatives:

- Secure the waste areas.
- Label the bins according to property address.
- The private collection contractor shall transfer bins between the waste areas and the truck (bins shall not be placed on the street).

4.4 Arrangements for Bins/Equipment Labelling and Ensuring Users and Staff are Aware of How to Use the Waste System Correctly

- The Operator shall provide appropriate signage for the bins. Signage is available at the following internet address: www.sustainability.vic.gov.au.
- The Operator shall publish/distribute “house rules” and educational material to:
 - Inform users/staff about the waste management system and the use/location of the associated equipment (provide the summary in page 2 of this report).
 - Improve facility management results (lessen equipment damage, reduce littering, and achieve cleanliness).
 - Advise users/staff to sort and recycle waste with care to reduce contamination of recyclables.

**ADVERTISED
PLAN**

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

4.5 Sustainability and Waste Avoidance/Reuse/Reduction Initiatives

The *Environment Protection Act 1970* includes principles of environment protection and guidance for waste management decision making. Also, the *Sustainability Victoria Act 2005* established Sustainability Victoria as the statutory authority for delivering programs on integrated waste management and resource efficiency.

From a design perspective, the development shall support the acts by providing an adequate waste system with ability to sort waste.

The Operator shall promote the observance of the acts (where relevant and practicable) and encourage users and staff to participate in minimising the impact of waste on the environment. For improved sustainability, the Operator shall consider the following:

- Observe the waste hierarchy in the *Environment Protection Act 1970* (in order of preference): a) waste avoidance, b) reuse, c) recycle, d) recovery of energy, e) treatment, f) containment, and g) disposal.
- Peruse the Sustainability Victoria website: www.sustainability.vic.gov.au.
- Participate in Council and in-house programs for waste minimisation.
- Establish waste reduction and recycling targets; including periodic waste audits, keeping records, and monitoring of the quantity of recyclables found in landfill-bound bins (sharing results with users/staff).

4.6 Waste Management Plan Revisions

For any future appropriate Council request, changes in legal requirements, changes in the development's needs and/or waste patterns (waste composition, volume, or distribution), or to address unforeseen operational issues, the Operator shall be responsible for coordinating the necessary Waste Management Plan revisions, including (if required):

- A waste audit and new waste strategy.
- Revision of the waste system (bin size/quantity/streams/collection frequency).
- Re-education of users/staff.
- Revision of the services provided by the waste collector(s).
- Any necessary statutory approval(s).

**ADVERTISED
PLAN**

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

5 SUPPLEMENTARY INFORMATION

- The Operator shall observe local laws and ensure that bins aren't overfilled or overloaded.
- Waste incineration devices are not permitted, and offsite waste treatment and disposal shall be carried-out in accordance with regulatory requirements.
- For bin traffic areas, either level surfaces (smooth and without steps) or gentle ramps are recommended, including a roll-over kerb or ramp. Should ramp gradients, bin weight, and/or distance affect the ease/safety of bin transfers, the Operator shall consider the use of a suitable tug.
- The Operator and waste collector shall observe all relevant OH&S legislation, regulations, and guidelines. The relevant entity shall define their tasks and:
 - Comply with Worksafe Victoria's Occupational Health and Safety Guidelines for the Collection, Transport and Unloading of Non-hazardous Waste and Recyclable Materials (June 2003).
 - Assess the Manual Handling Risk and prepare a Manual Handling Control Plan for waste and bin transfers (as per regulatory requirements and Victorian COP for Manual Handling).
 - Obtain and provide to staff/contractors equipment manuals, training, health and safety procedures, risk assessments, and adequate personal protective equipment (PPE) to control/minimise risks/hazards associated with all waste management activities. As a starting point, these documents and procedures shall address the following:

Task (to be confirmed)	Hazard (TBC)	Control Measures (TBC)
Sorting waste and cleaning the waste system	Bodily puncture. Biological & electrical hazards	Personal protective equipment (PPE). Develop a waste-sorting procedure
Bin manual handling	Sprain, strain, crush	PPE, staff training. Maintain bin wheel-hubs. Limit bin weight. Provide mechanical assistance to transfer bins
Bin transfers and emptying into truck	Vehicular strike, run-over	PPE. Develop a Hazard Control Plan for transfers and collections. Maintain visibility. Use a mechanical bin-tipper
Truck access (reversing & manoeuvring)	Vehicular incident, strike, run-over	PPE. Use a trained spotter. Develop a truck-manoeuving and traffic-control procedure

Note: The above shall be confirmed by a qualified OH&S professional who shall also prepare site-specific assessments, procedures, and controls (refer to Section 6).

ADVERTISED PLAN

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

6 CONTACT INFORMATION

City of Melbourne (local Council), ph 03 9658 9658

Waste Wise Environmental (private waste collector), ph 1300 550 408

Kartaway (private waste collector), ph 1300 362 362

iDump (private waste collector), ph 1300 443 867

FJP Safety Advisors Pty Ltd (OH&S consultant), ph 03 9255 3660

Electrodrive Pty Ltd (tug & trailer supplier – for bin transfers), ph 1800 033 002

Warequip (tug supplier – for bin transfers), ph 1800 337 711

Sulo MGB Australia (bin supplier), ph 1300 364 388

One Stop Garbage Shop (bin supplier), ph 03 9338 1411

Note: The above includes a complimentary listing of contractors and equipment suppliers. The stakeholders shall not be obligated to procure goods/services from these companies. Leigh Design does not warrant (or make representations for) the goods/services provided by these suppliers.

7 LIMITATIONS

The purpose of this report is to document a Waste Management Plan, as part of a Planning Permit Application.

This report is based on the following conditions:



- Operational use of the development (excludes demolition/construction stages).
- Drawings and information supplied by the project architect.
- The figures presented in this report are estimates only. The actual amount of waste will depend on the development's occupancy rate and waste generation intensity, the user's disposition toward waste and recycling, and the Operator's approach to waste management. The Operator shall make adjustments, as required, based on actual waste volumes (if the actual waste volume is greater than estimated, then the number of bins and/or the number of collections per week shall be increased, STCA).
- This report shall not be used to determine/forecast operational costs, or to prepare feasibility studies, or to document operational/safety procedures.

**ADVERTISED
PLAN**


**WASTE COLLECTION LOCATION 2
COLLECTION OF BIN AREAS 1 & 2**

VICTORIA STREET


**BIN AREA 03:
3x 1100 L GARBAGE BINS
+
1x 240 L RECYCLE BINS
+
1x BIN LIFTER**



**BIN AREA 01:
3x 1100 L GARBAGE BINS
+
2x 240 L RECYCLE BINS
+
1x BIN LIFTER**



**BIN AREA 02:
5x 240 L ORGANIC BINS
+
3 m² HARDWASTE**



**WASTE COLLECTION LOCATION 1
COLLECTION OF BIN AREA 3**

**ADVERTISED
PLAN**



This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright.

WASTE COLLECTION IS PROPOSED OUTSIDE OF SCHOOL HOURS WHEN THE CAR PARK / PLAY GROUND IS LIKELY TO BE VACANT

ADVERTISED PLAN

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

C:\USERS\ELLAC\DESKTOP\LOCALLY SAVED JOB FOLDERS\17334T - 273 VICTORIA STREET, WEST MELBOURNE (SIMONDS CATHOLIC COLLEGE)\SK05 - [2020.11.20]17334T-SK05.DWG



NOTE:
 1) Base Plan Supplied by Chandler Architecture on 16.11.2020
 2) 10km/h maximum vehicle speed

RATIO CONSULTANTS PTY LTD
 ABN 005 422 104
 8 GWYNNE STREET
 CREMORNE, VICTORIA 3121
 TELEPHONE (03)9429 3111
 FACSIMILE (03)9429 3011

Mini-Rear Loader Waste Collection Vehicle

VEHICLE ENVELOPE (FORWARD)
300mm CLEARANCE (FORWARD)
VEHICLE ENVELOPE (REVERSE)
300mm CLEARANCE (REVERSE)

Overall Length 6.345m
 Body Width 1.700m
 Overall Body Height 2.080m
 Min Body Ground Clearance 0.205m
 Track Width 1.670m
 Lock to Lock Time 4.00 sec
 Curb to Curb Turning Radius 6.450m

Simonds Catholic College
 Proposed School Upgrade
 Swept Path Assessment – Waste Collection



RATIO REFERENCE	SHEET No.	SCALE	DATE
17334T-SK05/EC0	1 of 1	1:400@A4	20/11/2020