

**Rocky Valley Ski Club c/o Mountain Creek Architecture
Preliminary Geotechnical Assessment
Proposed ramp and snow fence, Rocky Valley Ski Club, Falls
Creek**

754-MELGE268821AB Rev1

13 May 2020



Pour trust
into your
foundations
and you
can build
anything

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

**ADVERTISED
PLAN**

This page has been left intentionally blank

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

**ADVERTISED
PLAN**

Preliminary Geotechnical Assessment Proposed ramp and snow fence, Rocky Valley Ski Club, Falls Creek

Prepared for
Rocky Valley Ski Club c/o Mountain Creek Architecture
34 Hollonds Street
Mt Beauty VIC 3699

Prepared by
Coffey Services Australia Pty Ltd
Level 1, 436 Johnston Street
Abbotsford
Vic 3067 Australia
t: +61 3 9290 7000 f: +61 3 9290 7499
ABN 55 139 460 521

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

**ADVERTISED
PLAN**

13 May 2020

Document authorisation

Our ref: 754-MELGE268821AB Rev1

We trust this report meets your current requirements for the project. If you have any queries related to this report, or require further assistance, please contact the undersigned.

For and on behalf of Coffey

Robert Wilson
Senior Principal

Quality information

Revision history

Revision	Description	Date	Originator	Reviewer	Approver
0	Preliminary Geotechnical Assessment	13 May 2020	MJ	RW	GM
1	Included site classification	13 May 2020	MJ	RW	GM

Distribution

Report Status	No. of copies	Format	Distributed to	Date
Rev1	1	PDF	Mountain Creek Architecture	13 May 2020
Rev1	1	PDF	Rocky Valley Ski Club	13 May 2020

Table of contents

1. Introduction.....	1
2. Scope of work.....	1
3. SMEC assessment (1999)	1
4. Site conditions	2
4.1. Surface conditions.....	2
4.1.1. Proposed ramp location	2
4.1.2. Proposed snow fence and rock wall.....	2
4.2. Regional geology	3
4.3. Subsurface conditions.....	3
4.4. Drainage and groundwater.....	3
4.5. Observations of slope instability.....	3
5. Landslide risk assessment	4
5.1. Risk assessment procedure	4
5.2. Principles of risk assessment.....	4
5.3. Potential slope hazards and risk to property	4
5.4. Risk of loss of life	5
6. Geotechnical assessment	5
6.1. Excavation conditions	5
6.2. Batter slopes	6
6.3. Foundation recommendations.....	6
6.4. Site classification.....	6
6.5. Groundwater considerations	6
7. Applicability.....	7

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

**ADVERTISED
PLAN**

Tables

Table 1 - Assessed hazard ratings by SMEC

Table 2 - Typical Subsurface Conditions

Table 3 - Summary of slope instability and landslide risk assessments (risk to properties)

Table 4 - Recommended batter slopes

Figures

Figure 1 – Site Plan

Figure 2 – Section AA'

Figure 3 – Section BB' and Section CC'

Figures 4 to 6 – Site photographs

Appendices

Appendix A – Results of the geotechnical assessment

Appendix B - Landslide Risk Management

Appendix C - Erosion Management overlay-Schedule 1 Management of Geotechnical Hazards

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

**ADVERTISED
PLAN**

1. Introduction

This report presents the results of a Preliminary Geotechnical Assessment (PGA) carried out by Coffey Services Australia Pty Ltd (Coffey) for proposed building upgrades at the Rocky Valley Ski Club, No.3 Slalom Street, Falls Creek, Victoria. The study was commissioned by Mr Martin Steel of Rocky Valley Ski Club and was performed in general accordance with Coffey proposal 754-MELGE268821AA dated 26 November 2019.

It is understood that Rocky Valley Ski Club are planning minor building upgrades including a ramp on the east side of the building and snow screens and rock work on the west side of the building.

The objectives of the PGA were to evaluate the subsurface conditions at the site with regard to the proposed development and to provide geotechnical recommendations. A risk assessment of the potential landslide hazards was also carried out as per Schedule 1 of the Erosion Management Overlay in the Alpine Planning Scheme (2004), Victoria.

2. Scope of work

The scope of work carried out to meet the above objectives has included:

- A review of the regional geology;
- A review of the SMEC “Alpine Resorts Geotechnical Stability Review” dated 1999, that included specific assessment of the Rocky Valley Ski Club site;
- Fieldwork was conducted on 15 April 2020 which comprised:
 - A site walkover and geological mapping of the site. A site plan is shown on Figure 1 and a cross sections are shown in Figures 2 and 3. Selected photographs of the site taken during the fieldwork are presented as Figures 4 to 6.
 - Excavation and engineering logging of three hand auger boreholes and Dynamic Cone Penetrometer (DCP) tests at the site. The locations of the boreholes are shown in Figure 1. Engineering logs of the boreholes are presented in Appendix A, preceded by sheets summarising the terms and symbols used in their preparation. The results of the DCP tests are presented on the engineering logs.
- Preparation of this geotechnical report

3. SMEC assessment (1999)

SMEC completed a stability review and hazard assessment for the Falls Creek area in 1999, which included specific assessment of the Rocky Valley Ski Club site. The results of the specific assessment are shown in Table 1.

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

Table 1 - Assessed hazard ratings by SMEC

Site	Type of Slope Failure	Assessed Hazard Rating
Rocky Valley Ski Club	Natural Shallow Landslide	Very Low
	Rock fall	Not applicable
	Cut Excavation	Low
	Fill Embankment	Low

4. Site conditions

**ADVERTISED
PLAN**

4.1. Surface conditions

The Rocky Valley site lies on the south east corner of Slalom Street and Snowgums Lane in Falls Creek. The ski club comprises two buildings of 2 and 4 storeys. Figure 1 presents a plan of the site and Figure 2 presents a section through the site. Site photographs presented in Figures 4 to 6 show typical conditions on and adjacent to the site.

The site is located at the lower reach of a broad spur. Natural ground slopes fall at about 15° to the north west. Reduced levels at the site fall from about RL 1548m AHD at the south east extent of the site to RL 1540m AHD to the north west of the site at the base of the retaining wall and roadway.

The site is bounded by Slalom Street to the west, Snowgums Lane to the north, a gravel driveway to the east and a cut/fill slope to the south. The ski club site and surrounding building sites have been variously levelled. A 2m high cut slope is present at the south west corner of the building. A 2m high embankment and retaining wall is present at the eastern side of the building where the site boundary meets the roadway.

The surface surrounding the site was grass covered. Snowgums and other vegetation was present to the north and south of the building.

4.1.1. Proposed ramp location

Figure 3 shows a section of the ramp location.

The ramp is located at the eastern side of the building and is 2.9m in length. The ramp is located at the top of a 2.1m high cutting.

The cutting is at an angle of 68° and falls to the west. The toe of the cutting is offset 0.5m from the edge of the building. The face of the cutting is protected by a bluestone block wall with cement mortar. The mortar appeared to be intact without cracks. Drainage holes were not observed in the bluestone block wall.

4.1.2. Proposed snow fence and rock wall

Figure 3 shows a section of the proposed snow fence location.

The proposed snow fence is located at the western side of the building and will replace an existing snow fence along the edge of the roof line.

The ground surface at the base of the existing snow fence is gently sloping to the north west (<5°). Several underground services were present adjacent to the western side of the building.

4.2. Regional geology

The 1:50,000 scale “Falls Creek” Geological sheet published by Geological Survey of Victoria indicates the site to be underlain by Silurian age (420 million years old) Cobungra Granite.

4.3. Subsurface conditions

Table 2 summarises the subsurface conditions observed in the three hand auger boreholes drilled at the site. The subsurface conditions typically comprise less than 0.5m to 0.8m of fill overlying residual clay overlying extremely weathered granite comprising clayey sand to sand. Details of the materials encountered in the boreholes are described in the engineering logs presented Appendix A.

Table 2 - Typical Subsurface Conditions

Label	Typical description	Depth to top of unit	Typical thickness
Fill	Sandy CLAY / Gravelly CLAY (CL): low plasticity, dark brown, pale brown, mottled orange, fine to coarse grained sand, fine to coarse grained gravel, moist to wet, firm to stiff. Encountered in all boreholes.	0.0m	0.5-0.8m
	Sandy GRAVEL (GP): fine to coarse grained, pale brown, fine to medium grained sand, moist, medium dense. Encountered in HA1 only.		
Residual Soil	CLAY (CL): low plasticity, dark brown, brown, trace of fine grained sand, stiff to very stiff, moist to wet. Encountered in all boreholes	0.5-0.8m	0.3-0.4m
Extremely Weathered Granite	Clayey SAND to SAND (SC/SP): fine to coarse grained, pale brown, mottled brown and grey, low plasticity clay, trace fine to medium grained gravel, moist, medium dense to dense, inferred to be extremely weathered granite. Encountered in HA2 only.	0.8-1.1m	Not Penetrated
HA1 and HA3 reached refusal at depths of 1.1m and 0.8m respectively. DCP testing in these boreholes was extended to depths of 2.6m and 1.4m			

4.4. Drainage and groundwater

Groundwater was not observed in the boreholes. A local perched groundwater table may be present at other times and fluctuations in their levels and seepage could occur due to rainfall, melting of snow and other factors.

4.5. Observations of slope instability

No evidence indicative of natural slope instability was observed within or adjacent to the site.

5. Landslide risk assessment

5.1. Risk assessment procedure

In accordance with Schedule 1 of Erosion Management Overlay in the Victorian Alpine Planning Scheme (2004), the slope risks associated with development of the site have been considered in the context of the "Landslide Risk Management", published in the Australian Geomechanics Society publication, dated March 2007 (AGS Guidelines). The system is based on identification of likelihood of occurrence, its consequences to the structure and human life for the identified hazards. These assessments are then combined using a risk assessment matrix to obtain a risk assessment for the specific site for each hazard.

5.2. Principles of risk assessment

Risk assessment and management principles applied to slopes can be interpreted as answering the following questions:

- What are the issues? (SCOPE DEFINITION).
- What might happen? (HAZARD IDENTIFICATION).
- How likely is it? (LIKELIHOOD).
- What damage or injury might result? (CONSEQUENCE).
- How important is it? (RISK EVALUATION).
- What can be done? (RISK TREATMENT).

The risk is the combination of the likelihood, the consequences and the exposure to the identified hazard. All these factors are taken into account when evaluating a risk and deciding whether treatment is required. In the following sections of the report we have assessed the risks to properties and life using a qualitative approach as per the recommendations of the AGS Guidelines (2007).

The qualitative likelihood, consequence and risk terms used in this report for risk to property are explained in Appendix B. A matrix that brings together different combinations of likelihood and consequence defines the risk terms. Risk matrices help communicate the results of risk assessment, rank risks, set priorities and develop transparent approaches to decision making. The risk assessment of the sites with regard to the proposed new buildings is presented in Table 3.

5.3. Potential slope hazards and risk to property

Based on the supplied information regarding the proposed works the slope hazard identified at the site comprises failure of the cutting adjacent to the proposed ramp.

Table 3 lists our judgements of the likelihood, consequences and risk to property associated with this potential slope hazard. The assessments are judgements based on our understanding of the landslide hazard in the study area and our knowledge and experience. The assessment applies to the proposed ramp and should there be any changes, the risk assessment presented in this report may change.

**ADVERTISED
PLAN**

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

Table 3 - Summary of slope instability and landslide risk assessments (risk to properties)

Timing of hazard	Potential Hazard	Possible Initiating Circumstances	Likelihood ⁽¹⁾	Consequence	Risk	Revised Risk ⁽²⁾
During construction / Post-construction	Failure of cutting	Construction loads next to embankment / high groundwater	Possible	Minor	Moderate	Low
<p>Notes:</p> <p>(1) – Refer Appendix B for definitions of likelihood, consequence and risk terms.</p> <p>(2) – Revised risk assessment if recommendations provided in Section 6 are incorporated into the design and construction for the works.</p>						

The results of the risk assessment indicate that there is ‘Moderate’ risk classification for the proposed new ramp if poor construction practices are used during construction of the proposed works. If the geotechnical recommendations provided in Section 6 of this report are adopted the potential instability risk hazard would be reduced to ‘Low’.

5.4. Risk of loss of life

The AGS Guidelines recommends that the risk to life should be considered when assessing landslide risk. The landslide record from Australia and elsewhere indicates that most deaths and injuries are associated with fast moving landslides and associated high speed moving objects when there is insufficient warning for people present to take evasive action. People are most vulnerable if buried in open space, trapped in vehicles that are buried and crushed or in a building that collapses or is inundated with debris.

We strongly recommend appropriate construction practices, such as those described in Section 6, are adopted to reduce the likelihood of the event referred to in Table 3 from occurring. Provided such practices are adopted, we assess that the risk to life is not credible.

6. Geotechnical assessment

The proposed works should be carried out in accordance with sound engineering principles and good hillside practice (refer Appendix B). Geotechnical recommendations for the proposed works are provided in the following sections.

6.1. Excavation conditions

Based on the subsurface conditions encountered within the boreholes the materials to be excavated would comprise layers of fill, residual soil and weathered granite.

We assess that excavation of the soils should be able to be carried out using backhoes or tracked excavators.

Boreholes HA1 and HA3 reached refusal at depths of 1.1m and 0.8m respectively. Dynamic Cone Penetrometer (DCP) testing in these boreholes was extended to depths of 2.6m and 1.4m, respectively. It is possible that higher strength rock could exist at greater depths and potentially “floaters” of rock could exist in the weathered granite. It is considered these materials would require larger equipment fitted with ripping and/or rock breaking attachments.

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

6.2. Batter slopes

The recommended temporary and permanent batter slopes for unsupported cuts of up to 3m depth in the various materials are provided in Table 4.

Table 4 - Recommended batter slopes

Description of Material	Temporary Batter Slope	Permanent Batter Slopes
Fill / natural soils	1(V):1(H)	1(V):2(H)

The cutting at the ramp site is about 2.1m high and battered at 68°. It is protected by a bluestone block wall. We recommend the structural designer of the ramp review the nature of this block wall and consider its retention capacity in the context of the proposed new ramp.

It is recommended that no surcharge loadings be placed or located above the plane projected up at 45° from the toe of the cutting or batter. This line is presented on Figure 3 for the proposed ramp location. Surface water should be diverted away from the crests of batter slopes.

6.3. Foundation recommendations

Based on our understanding of the existing development and the proposed works, the proposed ramp and snow fence may be supported on shallow spread footings.

Spread footings may be founded on natural soils of stiff or better consistency, or the extremely weathered granite. These materials were encountered at depths of 0.6m to 0.8m from the existing ground level. Footings founded on such materials may be proportioned on the basis of a maximum allowable bearing pressure of 100 kPa.

It is noted that the ramp footings will lie close to the existing cutting at the eastern side of the building. At this location the footings should be installed below any fill and below the plane projected up at 45° from the toe of the existing cutting. This line is presented on Figure 3.

It is recommended that the base of all spread footing excavations be observed by a suitably experienced person to check that the conditions exposed are consistent with the recommendations in this report.

Footings must not be founded in non-engineered fill or softened or disturbed natural soils. Should such materials be encountered at the design founding level, footing excavations must be deepened, or further advice should be sought.

6.4. Site classification

Fill was encountered in the boreholes to depths of between 0.5m and 0.8m below existing surface level. As the fill is greater than 0.4m thick, a site classification of Class P is applicable for the site in accordance with AS2870-2011 "Residential Slabs and Footings".

Based on the subsurface conditions observed in the hand auger boreholes and Table D1 in AS2870-2011, a site classification of Class M is applicable for footings founded in the natural ground below the fill.

6.5. Groundwater considerations

We consider the groundwater table is likely to be below the proposed excavation level and no significant dewatering would be required during the excavation for foundations. However, we recommend that normal provision should be made for sumps and pumps to control surface and

groundwater seepage that may occur from wet weather and melting of snow. Such seepages should be collected and diverted away from the site.

It is noted that drainage holes were not observed in the bluestone block wall on the eastern side of the building at the ramp location. The covered slope may prevent the dissipation of water behind the wall and cause temporary build-up of groundwater behind the wall. This can reduce the bearing capacity of the foundations behind the wall, as well as leading to instability of the slope.

For the advice in Section 6.3 to apply it is recommended that drainage holes are installed in the bluestone block wall. These drainage holes may comprise small diameter holes (say 20mm diameter) drilled through the wall at staggered 1m horizontal and 1m vertical intervals.

7. Applicability

Recommendations and opinions contained in this report are based on the interpretation of subsurface conditions from a limited number of field tests at point locations and information from published geological maps. The nature and continuity of the subsoil away from the test locations are inferred, but it must be appreciated that actual conditions could vary from the assumed geotechnical model. If conditions other than those described are encountered, Coffey should be engaged to assess whether the recommendations should be revised.

The attached *“Important Information about your Coffey Report”* provides additional information in the uses and limitations of this report.

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

Important information about your Coffey Report

As a client of Coffey you should know that site subsurface conditions cause more construction problems than any other factor. These notes have been prepared by Coffey to help you interpret and understand the limitations of your report.

Your report is based on project specific criteria

Your report has been developed on the basis of your unique project specific requirements as understood by Coffey and applies only to the site investigated. Project criteria typically include the general nature of the project; its size and configuration; the location of any structures on the site; other site improvements; the presence of underground utilities; and the additional risk imposed by scope-of-service limitations imposed by the client. Your report should not be used if there are any changes to the project without first asking Coffey to assess how factors that changed subsequent to the date of the report affect the report's recommendations. Coffey cannot accept responsibility for problems that may occur due to changed factors if they are not consulted.

Subsurface conditions can change

Subsurface conditions are created by natural processes and the activity of man. For example, water levels can vary with time, fill may be placed on a site and pollutants may migrate with time. Because a report is based on conditions which existed at the time of subsurface exploration, decisions should not be based on a report whose adequacy may have been affected by time. Consult Coffey to be advised how time may have impacted on the project.

Interpretation of factual data

Site assessment identifies actual subsurface conditions only at those points where samples are taken and when they are taken. Data derived from literature and external data source review, sampling and subsequent laboratory testing are interpreted by geologists, engineers or scientists to provide an opinion about overall site conditions, their likely impact on the proposed development and recommended actions. Actual conditions may differ from those inferred to exist, because no professional, no matter how qualified, can reveal what is hidden by earth, rock and time. The actual interface between materials may be far more gradual or abrupt than assumed based on the facts obtained. Nothing can be done to change the actual site conditions which exist, but steps can be taken to reduce the impact of unexpected conditions. For this reason, owners should retain the services of Coffey through the development stage, to identify variances, conduct additional tests if required, and recommend solutions to problems encountered on site.

Your report will only give preliminary recommendations

Your report is based on the assumption that the site conditions as revealed through selective point sampling are indicative of actual conditions throughout an area. This assumption cannot be substantiated until project implementation has commenced and therefore your report recommendations can only be regarded as preliminary. Only Coffey, who prepared the report, is fully familiar with the background information needed to assess whether or not the report's recommendations are valid and whether or not changes should be considered as the project develops. If another party undertakes the implementation of the recommendations of this report there is a risk that the report will be misinterpreted and Coffey cannot be held responsible for such misinterpretation.

Your report is prepared for specific purposes and persons

To avoid misuse of the information contained in your report it is recommended that you confer with Coffey before passing your report on to another party who may not be familiar with the background and the purpose of the report. Your report should not be applied to any project other than that originally specified at the time the report was issued.

Interpretation by other design professionals

Costly problems can occur when other design professionals develop their plans based on misinterpretations of a report. To help avoid misinterpretations, retain Coffey to work with other project design professionals who are affected by the report. Have Coffey explain the report implications to design professionals affected by them and then review plans and specifications produced to see how they incorporate the report findings.

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

Data should not be separated from the report

The report as a whole presents the findings of the site assessment and the report should not be copied in part or altered in any way. Logs, figures, drawings, etc. are customarily included in our reports and are developed by scientists, engineers or geologists based on their interpretation of field logs (assembled by field personnel) and laboratory evaluation of field samples. These logs etc. should not under any circumstances be redrawn for inclusion in other documents or separated from the report in any way.

Geoenvironmental concerns are not at issue

Your report is not likely to relate any findings, conclusions, or recommendations about the potential for hazardous materials existing at the site unless specifically required to do so by the client. Specialist equipment, techniques, and personnel are used to perform a geoenvironmental assessment. Contamination can create major health, safety and environmental risks. If you have no information about the potential for your site to be contaminated or create an environmental hazard, you are advised to contact Coffey for information relating to geoenvironmental issues.

Rely on Coffey for additional assistance

Coffey is familiar with a variety of techniques and approaches that can be used to help reduce risks for all parties to a project, from design to construction. It is common that not all approaches will be necessarily dealt with in your site assessment report due to concepts proposed at that time. As the project progresses through design towards construction, speak with Coffey to develop alternative approaches to problems that may be of genuine benefit both in time and cost.

Responsibility

Reporting relies on interpretation of factual information based on judgement and opinion and has a level of uncertainty attached to it, which is far less exact than the design disciplines. This has often resulted in claims being lodged against consultants, which are unfounded. To help prevent this problem, a number of clauses have been developed for use in contracts, reports and other documents. Responsibility clauses do not transfer appropriate liabilities from Coffey to other parties but are included to identify where Coffey's responsibilities begin and end. Their use is intended to help all parties involved to recognise their individual responsibilities. Read all documents from Coffey closely and do not hesitate to ask any questions you may have.

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

**ADVERTISED
PLAN**

Figures


This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

**ADVERTISED
PLAN**



This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

SOURCE: Mountain Creek Architecture



ADVERTISED PLAN



LEGEND

● HA1 BOREHOLE LOCATION
— A-A' SECTION LINE



drawn	MJ
approved	RW
date	22/04/2020
scale	1:250
original size	A4



client:	Rocky Valley Ski Club/o Mountain Creek Architecture		
project:	Rocky Valley Ski Club Preliminary Geotechnical Assessment		
title:	Site Plan		
project no.:	754-MELG268821	Figure no.:	Figure 1
rev.:	0		

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

ADVERTISED PLAN



Note: Distance measurements in metres

drawn	MJ
approved	RW
date	22/04/2020
scale	AS SHOWN
original size	A4



client:	Rocky Valley Ski Club/c/o Mountain Creek Architecture		
project:	Rocky Valley Ski Club Preliminary Geotechnical Assessment		
title:	Section AA'		
project no:	754-MELGEG268821	Figure no:	Figure 2
rev:	0		


B
West

B'
East

C
North West

C'
South East



RVSC building
(indicative only)



ADVERTISED PLAN

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

RVSC building
(indicative only)





Note: Distance measurements in metres

drawn	MJ
approved	RW
date	22/04/2020
scale	AS SHOWN
original size	A4



client:	Rocky Valley Ski Club/c/o Mountain Creek Architecture
project:	Rocky Valley Ski Club Preliminary Geotechnical Assessment
title:	Section B' and Section C'
project no:	754-MELG268821
Figure no:	Figure 3
rev:	0



drawn	MJ	<p>This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach copyright.</p>	client:	ROCKY VALLEY SKI CLUB C/O MOUNTAIN CREEK ARCHITECTURE
approved	RW		project:	Rocky Valley Ski Club
date	23 Apr 2020		title:	Preliminary Geotechnical Assessment Snow Fence and Ramp
scale	-		project no:	754-MELGE268821
original size	A4			

**ADVERTISED
PLAN**



drawn	MJ
approved	RW
date	23 Apr 2020
scale	-
original size	A4




client:	ROCKY VALLEY SKI CLUB / C/O MOUNTAIN CREEK ARCHITECTURE
project:	Rocky Valley Ski Club Preliminary Geotechnical Assessment Snowing Ponds and Ramp
title:	Figure 5 - Site Photographs
project no:	754-MEL-GE26821

This copied document is not made available for the sole purpose of enabling its consideration and review as part of a Planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

ADVERTISED PLAN



drawn	MJ		client:	ROCKY VALLEY SKI CLUB C/O MOUNTAIN CREEK ARCHITECTURE
approved	RW		project:	Rocky Valley Ski Club Preliminary Geotechnical Assessment Snow Fence and Ramp
date	23 Apr 2020		title:	Figure 6 -Site Photographs
scale	-		project no:	754-MELGE268821
original size	A4			

Appendix A – Results of the geotechnical assessment

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

**ADVERTISED
PLAN**

Soil Description Explanation Sheet (1 of 2)

DEFINITION:

In engineering terms soil includes every type of uncemented or partially cemented inorganic or organic material found in the ground. In practice, if the material can be remoulded or disintegrated by hand in its field condition or in water it is described as a soil. Other materials are described using rock description terms.

CLASSIFICATION SYMBOL & SOIL NAME

Soils are described in accordance with the Unified Soil Classification (UCS) as shown in the table on Sheet 2.

PARTICLE SIZE DESCRIPTIVE TERMS

NAME	SUBDIVISION	SIZE
Boulders		>200 mm
Cobbles		63 mm to 200 mm
Gravel	coarse	20 mm to 63 mm
	medium	6 mm to 20 mm
	fine	2.36 mm to 6 mm
Sand	coarse	600 µm to 2.36 mm
	medium	200 µm to 600 µm
	fine	75 µm to 200 µm

MOISTURE CONDITION

Dry Looks and feels dry. Cohesive and cemented soils are hard, friable or powdery. Uncemented granular soils run freely through hands.

Moist Soil feels cool and darkened in colour. Cohesive soils can be moulded. Granular soils tend to cohere.

Wet As for moist but with free water forming on hands when handled.

CONSISTENCY OF COHESIVE SOILS

TERM	UNDRAINED STRENGTH S_u (kPa)	FIELD GUIDE
Very Soft	<12	A finger can be pushed well into the soil with little effort.
Soft	12 - 25	A finger can be pushed into the soil to about 25mm depth.
Firm	25 - 50	The soil can be indented about 5mm with the thumb, but not penetrated.
Stiff	50 - 100	The surface of the soil can be indented with the thumb, but not penetrated.
Very Stiff	100 - 200	The surface of the soil can be marked, but not indented with thumb pressure.
Hard	>200	The surface of the soil can be marked only with the thumbnail.
Friable	-	Crumbles or powders when scraped by thumbnail.

DENSITY OF GRANULAR SOILS

TERM	DENSITY INDEX (%)
Very loose	Less than 15
Loose	15 - 35
Medium Dense	35 - 65
Dense	65 - 85
Very Dense	Greater than 85

MINOR COMPONENTS

TERM	ASSESSMENT GUIDE	PROPORTION OF MINOR COMPONENT IN:
Trace of	Presence just detectable by feel or eye, but soil properties little or no different to general properties of primary component.	Coarse grained soils: <5% Fine grained soils: <15%
With some	Presence easily detected by feel or eye, soil properties little different to general properties of primary component.	Coarse grained soils: 5 - 12% Fine grained soils: 15 - 30%

SOIL STRUCTURE

ZONING		CEMENTING	
Layers	Continuous across exposure or sample.	Weakly cemented	Easily broken up by hand in air or water.
Lenses	Discontinuous layers of lenticular shape.	Moderately cemented	Effort is required to break up the soil by hand in air or water.
Pockets	Irregular inclusions of different material.		

GEOLOGICAL ORIGIN

WEATHERED IN PLACE SOILS

Extremely weathered material Structure and fabric of parent rock visible.

Residual soil Structure and fabric of parent rock not visible.

TRANSPORTED SOILS

Aeolian soil Deposited by wind.

Alluvial soil Deposited by streams and rivers.

Colluvial soil Deposited on slopes (transported downslope by gravity).

Fill Man made deposit. Fill may be significantly more variable between tested locations than naturally occurring soils.

Lacustrine soil Deposited by lakes.

Marine soil Deposited in ocean basins, bays, beaches and estuaries.









Soil Description Explanation Sheet (2 of 2)

ADVERTISED
PLAN

SOIL CLASSIFICATION INCLUDING IDENTIFICATION AND DESCRIPTION

FIELD IDENTIFICATION PROCEDURES (Excluding particles larger than 60 mm and basing fractions on estimated mass)				USC	PRIMARY NAME	
COARSE GRAINED SOILS More than 50% of materials less than 63 mm is larger than 0.075 mm	GRAVELS More than half of coarse fraction is larger than 2.0 mm	CLEAN GRAVELS (Little or no fines)	Wide range in grain size and substantial amounts of all intermediate particle sizes.	GW	GRAVEL	
		GRAVELS WITH FINES (Appreciable amount of fines)	Predominantly one size or a range of sizes with more intermediate sizes missing.	GP	GRAVEL	
		SANDS More than half of coarse fraction is smaller than 2.0 mm	CLEAN SANDS (Little or no fines)	Wide range in grain sizes and substantial amounts of all intermediate sizes missing	SW	SAND
			SANDS WITH FINES (Appreciable amount of fines)	Predominantly one size or a range of sizes with some intermediate sizes missing.	SP	SAND
		SILTS & CLAYS Liquid limit less than 50	Non-plastic fines (for identification procedures see ML below)	GM	SILTY GRAVEL	
			Plastic fines (for identification procedures see CL below)	GC	CLAYEY GRAVEL	
	FINE GRAINED SOILS More than 50% of material less than 63 mm is smaller than 0.075 mm (A 0.075 mm particle is about the smallest particle visible to the naked eye)	IDENTIFICATION PROCEDURES ON FRACTIONS <0.2 mm.				
		None to Low	Quick to slow	None	ML	SILT
		Medium to High	None	Medium	CL	CLAY
		Low to medium	Slow to very slow	Low	OL	ORGANIC SILT
Low to medium		Slow to very slow	Low to medium	MH	SILT	
High		None	High	CH	CLAY	
Medium to High	None	Low to medium	OH	ORGANIC CLAY		
HIGHLY ORGANIC SOILS	Readily identified by colour, odour, spongy feel and frequently by fibrous texture.			Pt	PEAT	
<ul style="list-style-type: none"> • Low plasticity – Liquid Limit W_L less than 35%. • Modium plasticity – W_L between 35% and 50%. 						

COMMON DEFECTS IN SOIL

TERM	DEFINITION	DIAGRAM	TERM	DEFINITION	DIAGRAM
PARTING	A surface or crack across which the soil has little or no tensile strength. Parallel or sub parallel to layering (eg bedding). May be open or closed.		SOFTENED ZONE	A zone in clayey soil, usually adjacent to a defect in which the soil has a higher moisture content than elsewhere.	
JOINT	A surface or crack across which the soil has little or no tensile strength but which is not parallel or sub parallel to layering. May be open or closed. The term 'fissure' may be used for irregular joints <0.2 m in length.		TUBE	Tubular cavity. May occur singly or as one of a large number of separate or inter-connected tubes. Walls often coated with clay or strengthened by denser packing of grains. May contain organic matter	
SHEARED ZONE	Zone in clayey soil with roughly parallel near planar, curved or undulating boundaries containing closely spaced, smooth or slickensided, curved intersecting joints which divide the mass into lenticular or wedge shaped blocks.		TUBE CAST	Roughly cylindrical elongated body of soil different from the soil mass in which it occurs. In some cases the soil which makes up the tube cast is cemented.	
SHEARED SURFACE	A near planar curved or undulating, smooth, polished or slickensided surface in clayey soil. The polished or slickensided surface indicates that movement (in many cases very little) has occurred along the defect.		INFILLED SEAM	Sheet or wall like body of soil substance or mass with roughly planar to irregular near parallel boundaries which cuts through a soil mass. Formed by infilling of open joints.	

Rock Description Explanation Sheet (1 of 2)

The descriptive terms used by Coffey are given below. They are broadly consistent with Australian Standard AS1726-1993.

DEFINITIONS: Rock substance, defect and mass are defined as follows:

Rock Substance In engineering terms rock substance is any naturally occurring aggregate of minerals and organic material which cannot be disintegrated or remoulded by hand in air or water. Other material is described using soil descriptive terms. Effectively homogenous material, may be isotropic or anisotropic.

Defect Discontinuity or break in the continuity of a substance or substances.

Mass Any body of material which is not effectively homogeneous. It can consist of two or more substances without defects, or one or more substances with one or more defects.

SUBSTANCE DESCRIPTIVE TERMS:

ROCK NAME Simple rock names are used rather than precise geological classification.

PARTICLE SIZE Grain size terms for sandstone are:
 Coarse grained Mainly 0.6mm to 2mm
 Medium grained Mainly 0.2mm to 0.6mm
 Fine grained Mainly 0.06mm (just visible) to 0.2mm

FABRIC Terms for layering of penetrative fabric (eg. bedding, cleavage etc.) are:

Massive No layering or penetrative fabric.

Indistinct Layering or fabric just visible. Little effect on properties.

Distinct Layering or fabric is easily visible. Rock breaks more easily parallel to layering of fabric.

ROCK SUBSTANCE STRENGTH TERMS

Term	Abbreviation	Point Load Index, $I_s(50)$ (MPa)	Field Guide
Very Low	VL	Less than 0.1	Material crumbles under firm blows with sharp end of pick; can be peeled with a knife; pieces up to 30mm thick can be broken by finger pressure.

Low	L	0.1 to 0.3	Easily scored with a knife; indentations 1mm to 3mm show with firm bows of a pick point; has a dull sound under hammer. Pieces of core 150mm long by 50mm diameter may be broken by hand. Sharp edges of core may be friable and break during handling.
-----	---	------------	---

Medium	M	0.3 to 1.0	Readily scored with a knife; a piece of core 150mm long by 50mm diameter can be broken by hand with difficulty.
--------	---	------------	---

High	H	1 to 3	A piece of core 150mm long by 50mm can not be broken by hand but can be broken by a pick with a single firm blow; rock rings under hammer.
------	---	--------	--

Very High	VH	3 to 10	Hand specimen breaks after more than one blow of a pick; rock rings under hammer.
-----------	----	---------	---

Extremely High	EH	More than 10	Specimen requires many blows with geological pick to break; rock rings under hammer.
----------------	----	--------------	--

CLASSIFICATION OF WEATHERING PRODUCTS

Term	Abbreviation	Definition
Residual Soil	RS	Soil derived from the weathering of rock; the mass structure and substance fabric are no longer evident; there is a large change in volume but the soil has not been significantly transported.
Extremely Weathered Material	XW	Material is weathered to such an extent that it has soil properties, ie, it either disintegrates or can be remoulded in water. Original rock fabric still visible.
Highly Weathered Rock	HW	Rock strength is changed by weathering. The whole of the rock substance is discoloured, usually by iron staining or bleaching to the extent that the colour of the original rock is not recognisable. Some minerals are decomposed to clay minerals. Porosity may be increased by leaching or may be decreased due to the deposition of minerals in pores.
Moderately Weathered Rock	MW	The whole of the rock substance is discoloured, usually by iron staining or bleaching, to the extent that the colour of the fresh rock is no longer recognisable.
Slightly Weathered Rock	SW	Rock substance affected by weathering to the extent that partial staining or partial discolouration of the rock substance (usually by limonite) has taken place. The colour and texture of the fresh rock is recognisable; strength properties are essentially those of the fresh rock substance.
Fresh Rock	FR	Rock substance unaffected by weathering.

Notes on Weathering:

- AS1726 suggests the term "Distinctly Weathered" (DW) to cover the range of substance weathering conditions between XW and SW. For projects where it is not practical to delineate between HW and MW or it is judged that there is no advantage in making such a distinction, DW may be used with the definition given in AS1726.
- Where physical and chemical changes were caused by hot gasses and liquids associated with igneous rocks, the term "altered" may be substituted for "weathering" to give the abbreviations XA, HA, MA, SA and DA.

Notes on Rock Substance Strength:

- In anisotropic rocks the field guide to strength applies to the strength perpendicular to the anisotropy. High strength anisotropic rocks may break readily parallel to the planar anisotropy.
- The term "extremely low" is not used as a rock substance strength term. While the term is used in AS1726-1993, the field guide therein makes it clear that materials in that strength range are soils in engineering terms.
- The unconfined compressive strength for isotropic rocks (and anisotropic rocks which fall across the planar anisotropy) is typically 10 to 25 times the point load index $I_s(50)$. The ratio may vary for different rock types. Lower strength rocks often have lower ratios than higher strength rocks.

Rock Description Explanation Sheet (2 of 2)

COMMON DEFECTS IN ROCK MASSES		Diagram	Map Symbol	Graphic Log (Note 1)	DEFECT SHAPE	TERMS
Term	Definition					
Parting	A surface or crack across which the rock has little or no tensile strength. Parallel or sub parallel to layering (eg bedding) or a planar anisotropy in the rock substance (eg, cleavage). May be open or closed.				Planar	The defect does not vary in orientation
					Curved	The defect has a gradual change in orientation
					Undulating	The defect has a wavy surface
Joint	A surface or crack across which the rock has little or no tensile strength, but which is not parallel or sub parallel to layering or planar anisotropy in the rock substance. May be open or closed.				Stepped	The defect has one or more well defined steps
					Irregular	The defect has many sharp changes of orientation
Note: The assessment of defect shape is partly influenced by the scale of the observation.						
Sheared Zone (Note 3)	Zone of rock substance with roughly parallel near planar, curved or undulating boundaries cut by closely spaced joints, sheared surfaces or other defects. Some of the defects are usually curved and intersect to divide the mass into lenticular or wedge shaped blocks.				ROUGHNESS TERMS	
					Slickensided	Grooved or striated surface, usually polished
					Polished	Shiny smooth surface
Sheared Surface (Note 3)	A near planar, curved or undulating surface which is usually smooth, polished or slickensided.				Smooth	Smooth to touch. Few or no surface irregularities
					Rough	Many small surface irregularities (amplitude generally less than 1mm). Feels like fine to coarse sand paper.
Crushed Seam (Note 3)	Seam with roughly parallel almost planar boundaries, composed of disoriented, usually angular fragments of the host rock substance which may be more weathered than the host rock. The seam has soil properties.				Very Rough	Many large surface irregularities (amplitude generally more than 1mm). Feels like, or coarser than very coarse sand paper.
					COATING TERMS	
Infilled Seam	Seam of soil substance usually with distinct roughly parallel boundaries formed by the migration of soil into an open cavity or joint, infilled seams less than 1mm thick may be described as veneer or coating on joint surface.				Clean	No visible coating
					Stained	No visible coating but surfaces are discoloured
					Veneer	A visible coating of soil or mineral, too thin to measure; may be patchy
Extremely Weathered Seam	Seam of soil substance, often with gradational boundaries. Formad by weathering of the rock substance in place.				Coating	A visible coating up to 1mm thick. Thicker soil material is usually described using appropriate defect terms (eg, infilled seam). Thicker rock strength material is usually described as a vein.
					BLOCK SHAPE TERMS	
					Blocky	Approximately equidimensional
					Tabular	Thickness much less than length or width
					Columnar	Height much greater than cross section

Notes on Defects:

1. Usually borehole logs show the true dip of defects and face sketches and sections the apparent dip.
2. Partings and joints are not usually shown on the graphic log unless considered significant.
3. Sheared zones, sheared surfaces and crushed seams are faults in geological terms.

Engineering Log - Hand Auger



client: **Rocky Valley Ski Club c/o Mountain Creek Architecture**
 principal:
 project: **Rocky Valley Ski Club PGA**
 location: **Refer to Figure 1**

Borehole ID: **HA1**
 sheet: 1 of 1
 project no.: **754-MELGE268821**
 date started: **15 Apr 2020**
 date completed: **15 Apr 2020**
 logged by: **MJ**
 checked by: **RW**

position: E: 525161; N: 5920189 (WGS84 Zone 55) surface elevation: 1542.70 m (AHD) angle from horizontal: 90° DCP id.: 7
 drill model: drilling fluid: hole diameter : 100 mm

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	soil group symbol	material description	moisture condition	consistency / relative density	hand penetrometer (kPa)	DCP (blows/100 mm)	structure and additional observations
HA	1 2 3		D	1542	0.5		GP	FILL: Sandy GRAVEL: fine to coarse grained, rounded, quartz and granite, pale brown, fine to medium grained sand, trace silt.	M	MD	100 200 300 400	2 4 6 8 10	FILL
							CL	FILL: Sandy CLAY: low plasticity, dark brown, fine to coarse grained sand, trace fine to coarse grained gravel, granite.	M - W	St		VS 65 kPa	
							CL	CLAY: medium plasticity, brown, trace fine grained sand.	St - VSt	VSt		RESIDUAL SOIL VS 115 kPa	
				1541	1.5			Hand Auger HA1 terminated at 1.1 m Refusal					
				1540	2.0								
				1539	3.5								

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear; peak/remoulded (kPa) R refusal HB hammer bouncing	soil group symbol & soil description based on AS 1726:2017	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	moisture condition D dry M moist W wet Wp plastic limit Wl liquid limit	water  10-Oct-12 water level on date shown water inflow water outflow	








CDF_0_9_07_LIBRARY.GLB rev:AU Log COF BOREHOLE: NON CORED + DCP 754-MELGE268821.GPJ <<DrawingFiles>> 12-05-2020 10:54



Engineering Log - Hand Auger

client: **Rocky Valley Ski Club c/o Mountain Creek Architecture**
 principal:
 project: **Rocky Valley Ski Club PGA**
 location: **Refer to Figure 1**

Borehole ID: **HA2**
 project no: **754-MELGE268821**
 date started: **15 Apr 2020**
 date completed: **15 Apr 2020**
 logged by: **MJ**
 checked by: **RW**

position: E: 525197; N: 5920179 (WGS84 Zone 55) surface elevation: 1546.10 m (AHD) angle from horizontal: 90° DCP id.: 7
 drill model: drilling fluid: hole diameter: 100 mm

drilling information				material substance												
method & support	penetration	samples & field tests	water	RL (m)	depth (m)	graphic log	soil group symbol	material description	moisture condition	consistency / relative density	hand penetrometer (kPa)	DCP (blows/100 mm)	structure and additional observations			
		D D D D	D D D D	1546	0.5		CL	FILL: Gravelly CLAY: low plasticity, dark brown mottled brown and orange, fine to coarse grained gravel.	M	F - St	100 200 300 400		FILL			
										PVC offcut recovered	M - W					
											plastic sheeting recovered					
								1545	1.0		CL	CLAY: low plasticity, dark brown to brown, trace fine grained sand.		St		
				1545	1.5		SC	CLAYEY SAND: fine to medium grained, pale brown, low plasticity clay, trace of fine to medium grained gravel, granite, very low strength.	M	MD - D			COBUNGRA GRANITE			
				1544	2.0		SP	SAND: fine to coarse grained, mottled pale brown, brown, grey, trace of low plasticity clay.								
				1543	2.5											
					3.0											
					3.5			Hand Auger HA2 terminated at 3.2 m Target depth								

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear; peak/remoulded (kPa) R refusal HB hammer bouncing	soil group symbol & soil description based on AS 1726:2017	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  no resistance ranging to refusal	water  10-Oct-12 water level on date shown water inflow water outflow	moisture condition D dry M moist W wet Wp plastic limit Wl liquid limit	

CDF_0_9_07_LIBRARY.GLB rev:AU Log COF BOREHOLE: NON CORED + DCP 754-MELGE268821.GPJ <<DrawingFiles>> 12-05-2020 10:54

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach copyright.



Engineering Log - Hand Auger

client: **Rocky Valley Ski Club c/o Mountain Creek Architecture**
 principal:
 project: **Rocky Valley Ski Club PGA**
 location: **Refer to Figure 1**

Borehole ID: **HA3**
 sheet: **1 of 1**
 project no: **754-MELGE268821**
 date started: **15 Apr 2020**
 date completed: **15 Apr 2020**
 logged by: **MJ**
 checked by: **RW**

position: E: 525195; N: 5820178 (WGS84 Zone 55) surface elevation: 1546.30 m (AHD) angle from horizontal: 90° DCP id.: 7
 drill model: drilling fluid: hole diameter: 100 mm

drilling information				material substance									
method & support	penetration	water	samples & field tests	RL (m)	depth (m)	graphic log	soil group symbol	material description	moisture condition	consistency / relative density	hand penetrometer (kPa)	DCP (blows/100 mm)	structure and additional observations
HA	N			1546	0.5		CL	FILL: Sandy CLAY: low plasticity, pale brown, fine grained sand. man made fibres recovered	M	F - St	100 200 300 400		FILL
									CL	CLAY: low plasticity, dark brown to brown.	M - W	St	
				1545	1.0			Hand Auger HA3 terminated at 0.8 m Refusal					
				1544	1.5								
				1543	3.5								

method AD auger drilling* AS auger screwing* HA hand auger W washbore HA hand auger	support M mud C casing N nil	samples & field tests B bulk disturbed sample D disturbed sample E environmental sample SS split spoon sample U## undisturbed sample ##mm diameter HP hand penetrometer (kPa) N standard penetration test (SPT) N* SPT - sample recovered Nc SPT with solid cone VS vane shear; peak/remoulded (kPa) R refusal HB hammer bouncing	soil group symbol & soil description based on AS 1726:2017	consistency / relative density VS very soft S soft F firm St stiff VSt very stiff H hard Fb friable VL very loose L loose MD medium dense D dense VD very dense
* bit shown by suffix e.g. AD/T B blank bit T TC bit V V bit	penetration  water 	moisture condition D dry M moist W wet Wp plastic limit Wl liquid limit		

CDF_0_9_07_LIBRARY.GLB rev:AU Log COF BOREHOLE: NON CORED + DCP 754-MELGE268821.GPJ <<DrawingFiles>> 12-05-2020 10:54

Appendix B - Landslide Risk Management

**ADVERTISED
PLAN**

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007
APPENDIX C: LANDSLIDE RISK ASSESSMENT
QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY

**ADVERTISED
PLAN**

QUALITATIVE MEASURES OF LIKELIHOOD

Approximate Annual Probability		Implied Indicative Landslide Recurrence Interval		Description	Descriptor	Level
Indicative Value	Notional Boundary					
10 ⁻¹	5x10 ⁻²	10 years	20 years	The event is expected to occur over the design life.	ALMOST CERTAIN	A
10 ⁻²		100 years		The event will probably occur under adverse conditions over the design life.	LIKELY	B
10 ⁻³	5x10 ⁻³	1000 years	2000 years	The event could occur under adverse conditions over the design life.	POSSIBLE	C
10 ⁻⁴		10,000 years		The event might occur under very adverse circumstances over the design life.	UNLIKELY	D
10 ⁻⁵	5x10 ⁻⁵	100,000 years	20,000 years	The event is conceivable but only under exceptional circumstances over the design life.	RARE	E
10 ⁻⁶		1,000,000 years		200,000 years	The event is inconceivable or fanciful over the design life.	BARELY CONCEIVABLE

Note: (1) The table should be used from left to right; use Approximate Annual Probability or Description to assign Descriptor, not *vice versa*.

This copied document to be made available for public use solely for the purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright.

QUALITATIVE MEASURES OF CONSEQUENCES TO PROPERTY

Approximate Cost of Damage		Description	Descriptor	Level
Indicative Value	Notional Boundary			
200%	100%	Structure(s) completely destroyed and/or large scale damage requiring major engineering works for stabilisation. Could cause at least one adjacent property major consequence damage.	CATASTROPHIC	1
60%		Extensive damage to most of structure, and/or extending beyond site boundaries requiring significant stabilisation works. Could cause at least one adjacent property medium consequence damage.	MAJOR	2
20%	40%	Moderate damage to some of structure, and/or significant part of site requiring large stabilisation works. Could cause at least one adjacent property minor consequence damage.	MEDIUM	3
5%		10%	Limited damage to part of structure, and/or part of site requiring some reinstatement stabilisation works.	MINOR
0.5%	1%	Little damage. (Note for high probability event (Almost Certain), this category may be subdivided at a notional boundary of 0.1%. See Risk Matrix.)	INSIGNIFICANT	5

- Notes:** (2) The Approximate Cost of Damage is expressed as a percentage of market value, being the cost of the improved value of the unaffected property which includes the land plus the unaffected structures.
- (3) The Approximate Cost is to be an estimate of the direct cost of the damage, such as the cost of reinstatement of the damaged portion of the property (land plus structures), stabilisation works required to render the site to tolerable risk level for the landslide which has occurred and professional design fees, and consequential costs such as legal fees, temporary accommodation. It does not include additional stabilisation works to address other landslides which may affect the property.
- (4) The table should be used from left to right; use Approximate Cost of Damage or Description to assign Descriptor, not *vice versa*

PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

APPENDIX C: – QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY (CONTINUED)

QUALITATIVE RISK ANALYSIS MATRIX – LEVEL OF RISK TO PROPERTY

LIKELIHOOD		CONSEQUENCES TO PROPERTY (With Indicative Approximate Cost of Damage)				
	Indicative Value of Approximate Annual Probability	1: CATASTROPHIC 200%	2: MAJOR 60%	3: MEDIUM 20%	4: MINOR 5%	5: INSIGNIFICANT 0.5%
A – ALMOST CERTAIN	10 ⁻¹	VH	VH	VH	H	M or L (5)
B - LIKELY	10 ⁻²	VH	VH	H	M	L
C - POSSIBLE	10 ⁻³	VH	H	M	M	VL
D - UNLIKELY	10 ⁻⁴	H	M	L	L	VL
E - RARE	10 ⁻⁵	M	L	L	VL	VL
F - BARELY CREDIBLE	10 ⁻⁶	L	VL	VL	VL	VL

Notes: (5) For Cell A5, may be subdivided such that a consequence of less than 0.1% is Low Risk.

(6) When considering a risk assessment it must be clearly stated whether it is for existing conditions or with risk control measures which may not be implemented at the current time.

RISK LEVEL IMPLICATIONS

Risk Level		Example Implications (7)
VH	VERY HIGH RISK	Unacceptable without treatment. Extensive detailed investigation and research, planning and implementation of treatment options essential to reduce risk to Low; may be too expensive and not practical. Work likely to cost more than value of the property.
H	HIGH RISK	Unacceptable without treatment. Detailed investigation, planning and implementation of treatment options required to reduce risk to Low. Work would cost a substantial sum in relation to the value of the property.
M	MODERATE RISK	May be tolerated in certain circumstances (subject to regulator’s approval) but requires investigation, planning and implementation of treatment options to reduce the risk to Low. Treatment options to reduce to Low risk should be implemented as soon as practicable.
L	LOW RISK	Usually acceptable to regulators. Where treatment has been required to reduce the risk to this level, ongoing maintenance is required.
VL	VERY LOW RISK	Acceptable. Manage by normal slope maintenance procedures.

Note: (7) The implications for a particular situation are to be determined by all parties to the risk assessment and may depend on the nature of the property at risk; these are only given as a general guide.

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright



ADVERTISED PLAN

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

Landslide Risk Management

Important Information about AGS 2007 Appendix C (1 of 2)

INTRODUCTION

This sheet provides important information on the following Appendix C which has been copied from "Practice note guidelines for landslide risk management 2007". The "Practice Note" and accompanying "Commentary" (References 1 & 2, hereafter referred to as AGS2007) are part of a series of documents on landslide risk management prepared on behalf of, and endorsed by, the Australian Geomechanics Society. These documents were primarily prepared to apply to residential or similar development.

It should be noted that AGS2007 define landslides as "the movement of a mass of rock, debris or earth down a slope". This definition includes falls, topples, slides, spreads and flows from both natural and artificial slopes.

LANDSLIDE LIKELIHOOD ASSESSMENT

The assessment of the likelihood of landsliding requires evidence-based judgements.

Judging how often and how much an existing landslide will move is difficult. Judging the likelihood of a new landslide occurring is even harder. Records of past landslides can provide some information on what has happened, but are invariably incomplete and often provide little or no guidance on less frequent events that may occur. Often judgements have to be made about the likelihood of infrequent events with serious consequences, with little or no help from historical records. Slope models, which reflect evidence-based knowledge of how a slope was formed, how it behaved in the past and how it might behave in the future, are used to support judgements about what might happen. Because of the difficulties in assessing landslide likelihood, different assessors may make different judgements when presented with the same information.

The likelihood terms in Appendix C can be taken to imply that it is possible to distinguish between low probability events (e.g. between events having a probability of 1 in 10,000 and 1 in 100,000). In many circumstances it will not be possible to develop defensibly realistic judgements to do so, and so joint terms need to be used (e.g. Likely or Possible). For further discussion on landslide likelihood and other matters see References 3, 4 and 5.

CONSEQUENCES OF LANDSLIDES

There can be direct (e.g. property damage, injury / loss of life) and indirect (e.g. litigation, loss of business confidence) consequences of a landslide. The assessment of the importance (seriousness) of the consequences is a value judgement best made by those most affected (e.g. client, owner, regulator, public). The main role of the expert is usually to understand and explain what and who might be affected, and what damage or injury might occur.

Appendix C implies that we can anticipate total cost (direct and indirect) of landslide damage to about half an order of magnitude (e.g. the difference between \$30,000 and \$100,000). This involves predicting the location, size, travel distance and speed of a landslide, the response of a building (often before it has been built), the nature and the extent of damage, repair costs as well as indirect consequences such as legal costs, accommodation etc. There can be other direct and indirect consequences of a landslide which can be difficult to anticipate, let alone quantify and cost. The situation is analogous to the cost of work place accidents where the hidden costs can range from less than one to more than 20 times the visible direct costs (Reference 5).

In many circumstances it will not be possible to develop defensibly realistic judgements to enable use of a single consequence descriptor from Appendix C, and so joint terms need to be used (e.g. Minor or Medium). In our experience, explicit descriptions of potential consequences (e.g. rocks up to 0.5m across may fall on a parked car) help those affected to make their own judgements about the seriousness of the consequences.

RISK MATRIX

The main purpose of a risk matrix is to help rank risks, set priorities and help the decision making process. The risk terms should be regarded only as a guide to the relative level of risk as they are the product of an evidence-based quantitative judgement of likelihood and a value judgement about consequences, both of which involve considerable uncertainty. Different assessors may arrive at different judgements on the risk level.

Using Appendix C, many existing houses on sloping land will be assessed to have a Moderate Risk.



Landslide Risk Management

Important Information about AGS 2007 Appendix C (2 of 2)

RISK LEVEL IMPLICATIONS

In general, it is the responsibility of the client and/or owner and/or regulatory authority and/or others who may be affected to decide whether to accept or treat the risk. The risk assessor and/or other advisers may assist by making risk comparisons, discussing treatment options, explaining the risk management process, advising how others have reacted to risk in similar situations, and making recommendations. Attitudes to risk vary widely and risk evaluation often involves considering more than just property damage (e.g. environmental effects, public reaction, political consequences, business confidence etc).

The risk level implications in Appendix C represent a very specific example and are unlikely to be generally applicable. In our experience the typical response of regulators to assessed risk is as follows:

Assessed risk	Typical response of client/ owner/ regulator/ person affected
Very High, High ¹	Treats seriously. Usually requires action to reduce risk. Will generally avoid development.
Moderate	May accept risk. Usually looks for ways to reduce risk if reasonably practicable.
Low, Very Low ¹	Usually regards risk as acceptable. May reduce risk if reasonably practicable.

¹ The distinctions between Very High and High and between Low and Very Low risks are usually used to help set priorities.

REFERENCES

1. AGS (2007). "Practice note guidelines for landslide risk management 2007". Australian Geomechanics, Vol. 42, No. 1, pp 63-114.
2. AGS (2007). "Commentary on practice note guidelines for landslide risk management 2007". Australian Geomechanics, Vol. 42, No. 1, pp 115-158.
3. Baynes, F.J., Lee I.K. and Stewart, I.E., (2002). "A study of the accuracy and precision of some landslide risk analyses." Australian Geomechanics, Vol. 37, No. 2, pp 149-156.
4. Baynes, et. al., (2007). "Concerns about the Practice Note Guidelines for Landslide Risk Management 2007." Letter to the editor, Australian Geomechanics, Vol. 2, No. 4, pp 63-114.
5. Moon, A.T., and Wilson, R.A., (2004). "Will it happen? – Quantitative judgements of landslide likelihood". Proceedings of the Australia New Zealand conference on Geomechanics, Centre of continuing education, University of Auckland, Vol. 2, pp 754-760.

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

ADVERTISED PLAN

PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

APPENDIX G - SOME GUIDELINES FOR HILLSIDE CONSTRUCTION

GOOD ENGINEERING PRACTICE

POOR ENGINEERING PRACTICE

ADVICE

GEOTECHNICAL ASSESSMENT	Obtain advice from a qualified, experienced geotechnical practitioner at early stage of planning and before site works.	Prepare detailed plan and start site works before geotechnical advice.
-------------------------	---	--

PLANNING

SITE PLANNING	Having obtained geotechnical advice, plan the development with the risk arising from the identified hazards and consequences in mind.	Plan development without regard for the Risk.
---------------	---	---

DESIGN AND CONSTRUCTION

HOUSE DESIGN	Use flexible structures which incorporate properly designed brickwork, timber or steel frames, timber or panel cladding. Consider use of split levels. Use decks for recreational areas where appropriate.	Floor plans which require extensive cutting and filling. Movement intolerant structures.
SITE CLEARING	Retain natural vegetation wherever practicable.	Indiscriminately clear the site.
ACCESS & DRIVEWAYS	Satisfy requirements below for cuts, fills, retaining walls and drainage. Council specifications for grades may need to be modified. Driveways and parking areas may need to be fully supported on piers.	Excavate and fill for site access before geotechnical advice.
EARTHWORKS	Retain natural contours wherever possible.	Indiscriminatory bulk earthworks.
CUTS	Minimise depth. Support with engineered retaining walls or batter to appropriate slope. Provide drainage measures and erosion control.	Large scale cuts and benching. Unsupported cuts. Ignore drainage requirements
FILLS	Minimise height. Strip vegetation and topsoil and key into natural slopes prior to filling. Use clean fill materials and compact to engineering standards. Batter to appropriate slope or support with engineered retaining wall. Provide surface drainage and appropriate subsurface drainage.	Loose or poorly compacted fill, which if it fails, may flow a considerable distance including onto property below. Block natural drainage lines. Fill over existing vegetation and topsoil. Include stumps, trees, vegetation, topsoil, boulders, building rubble etc in fill.
ROCK OUTCROPS & BOULDERS	Remove or stabilise boulders which may have unacceptable risk. Support rock faces where necessary.	Disturb or undercut detached blocks or boulders.
RETAINING WALLS	Engineer design to resist applied soil and water forces. Found on rock where practicable. Provide subsurface drainage within wall backfill and surface drainage on slope above. Construct wall as soon as possible after cut/fill operation.	Construct a structurally inadequate wall such as sandstone flagging, brick or unreinforced blockwork. Lack of subsurface drains and weepholes.
FOOTINGS	Found within rock where practicable. Use rows of piers or strip footings oriented up and down slope. Design for lateral creep pressures if necessary. Backfill footing excavations to exclude ingress of surface water.	Found on topsoil, loose fill, detached boulders or undercut cliffs.
SWIMMING POOLS	Engineer designed. Support on piers to rock where practicable. Provide with under-drainage and gravity drain outlet where practicable. Design for high soil pressures which may develop on uphill side whilst there may be little or no lateral support on downhill side.	
DRAINAGE		
SURFACE	Provide at tops of cut and fill slopes. Discharge to street drainage or natural water courses. Provide general falls to prevent blockage by siltation and incorporate silt traps. Line to minimise infiltration and make flexible where possible. Special structures to dissipate energy at changes of slope and/or direction.	Discharge at top of fills and cuts. Allow water to pond on bench areas.
SUBSURFACE	Provide filter around subsurface drain. Provide drain behind retaining walls. Use flexible pipelines with access for maintenance. Prevent inflow of surface water.	Discharge roof runoff into absorption trenches.
SEPTIC & SULLAGE	Usually requires pump-out or mains sewer systems; absorption trenches may be possible in some areas if risk is acceptable. Storage tanks should be water-tight and adequately founded.	Discharge sullage directly onto and into slopes. Use absorption trenches without consideration of landslide risk.
EROSION CONTROL & LANDSCAPING	Control erosion as this may lead to instability. Revegetate cleared area.	Failure to observe earthworks and drainage recommendations when landscaping.

DRAWINGS AND SITE VISITS DURING CONSTRUCTION

DRAWINGS	Building Application drawings should be viewed by geotechnical consultant	
SITE VISITS	Site Visits by consultant may be appropriate during construction/	

INSPECTION AND MAINTENANCE BY OWNER

OWNER'S RESPONSIBILITY	Clean drainage systems; repair broken joints in drains and leaks in supply pipes. Where structural distress is evident see advice. If seepage observed, determine causes or seek advice on consequences.	
------------------------	--	--


**ADVERTISED
PLAN**

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright


This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

ADVERTISED PLAN

EXAMPLES OF GOOD HILLSIDE PRACTICE



EXAMPLES OF POOR HILLSIDE PRACTICE



Appendix C - Erosion Management overlay- Schedule 1 Management of Geotechnical Hazards

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

**ADVERTISED
PLAN**

ALPINE RESORTS PLANNING SCHEME
Erosion Management Overlay – Schedule 1 Management of Geotechnical Hazard

FORM 1

Declaration and/or verification made by geotechnical engineer or engineering geologist as part of a geotechnical report

Name of application: _____

Address of subject site: _____

I, _____ of _____
(insert name) (trading or company name)

on _____
(insert date)

certify that I am a geotechnical engineer or engineering geologist as defined by the Erosion Management Overlay (Schedule 1 – Management of Geotechnical Hazard) and I have: (tick appropriate box):

prepared the Geotechnical Report referenced below in accordance with the Australian Geomechanics Society's Geotechnical Risk Management Guidelines and Clause 3 of the EMO1

or

technically verified that the geotechnical report referenced below has been prepared in accordance with the AGS's Geotechnical Risk Management Guidelines and Clause 3 of the EMO1.

Geotechnical report details:

Report title:	This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright
Report date:	
Report reference:	
Author:	
Author's affiliation:	

Documentation relied upon in report preparation:

I am aware that the Geotechnical Report I have either prepared or am technically verifying for the above development is to be submitted in support of a development application for the proposed development _____ (name of development) requiring approval from the Minister for Planning.

Further, I hold a current professional indemnity insurance policy of at least \$2 million, evidence of which is attached with this form.

Name _____ Signature G. Moulman

Date _____

**ADVERTISED
PLAN**

Certificate of Currency

Date of Issue: 27 September 2019

Contact: Bruce Curby
t: 61 2 9253 7556
e: Bruce.Curby@aon.com

We hereby certify that the under mentioned insurance policy is current as at the date of this certificate, please refer to the important notices below.

Policy Type	Professional Indemnity
Insured	<ol style="list-style-type: none">1. Tetra Tech Coffey Holding Pty Ltd2. Coffey International Limited3. Coffey Corporate Pty Ltd4. Coffey Services Australia Pty Ltd5. Coffey Environments Australia Pty Ltd6. Coffey Geotechnics Pty Ltd7. Coffey International Development Pty Ltd8. Coffey Projects Australia Pty Ltd9. Coffey Services (NZ) Ltd10. Coffey Projects (New Zealand) Ltd11. Tetra Tech Australia Pty Ltd12. Proteus Engineers Pty Ltd13. And or/all of their subsidiary companies <p>All for their respective rights, interests and liabilities.</p>
Insurer	Lexington Insurance Company (Lead)
Policy Number(s)	028182375
Period of Insurance	From: 4.00 pm 1 October 2019 Local Standard Time To: 4.00 pm 1 October 2020 Local Standard Time
Limits of Liability	AUD2,000,000 any one Claim and in the aggregate during the period of insurance
Geographical Limit	Worldwide
Remarks	Subject as always to the full terms and conditions of the policy.

**ADVERTISED
PLAN**

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

Further Information

Should you have any queries, please contact us on the details set out at the top of the page.

Important notes

- Aon does not guarantee that the insurance outlined in this Certificate will continue to remain in force for the period referred to as the Policy may be cancelled or altered by either party to the contract, at any time, in accordance with the terms of the Policy and the Insurance Contracts Act 1984 (Cth).
- Aon accepts no responsibility or liability to advise any party who may be relying on this Certificate of such alteration to or cancellation of the Policy.
- Subject to full payment of premium
- This certificate does not:
 - represent an insurance contract or confer rights to the recipient; or
 - amend, extend or alter the Policy
 - contain the full policy terms and conditions

This page has been left intentionally blank

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

**ADVERTISED
PLAN**