

Waste Management Plan

ADVERTISED
PLAN

*44-76 Simcock Avenue,
Spotswood*

This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright

Urbis staff responsible for this report were:

Director

Senior Consultant

Consultant

Project Code

P0058526

**ADVERTISED
PLAN**

Revision	Date	Details
1	30/01/2026	Draft Waste Management Plan
2	12/02/2026	Waste Management Plan
3	26/03/2026	Waste Management Plan
4	08/07/2026	Waste Management Plan for Submission
5	24/07/2026	Waste Management Plan for Submission

Acknowledgment of Country

Urbis acknowledges the Traditional Custodians of the lands we operate on. We recognise that First Nations sovereignty was never ceded and respect First Nations peoples continuing connection to these lands, waterways and ecosystems for over 60,000 years. We pay our respects to First Nations Elders, past and present.

Urbis is committed to incorporating our respect for First Nations cultures, peoples and storytelling in our work across the Country. We are proud to have partnered with Darug Nation artist, **Hayley Pigram**, and to profile her artwork – **Sacred River Dreaming**.

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright



The river is the symbol of the Dreaming and the journey of life. The circles and lines represent people meeting and connections across time and space. When we are working in different places, we can still be connected and work towards the same goal.

All information supplied to Urbis in order to conduct this research has been treated in the strictest confidence. It shall only be used in this context and shall not be made available to third parties without client authorisation. Confidential information has been stored securely and data provided by respondents, as well as their identity, has been treated in the strictest confidence and all assurance given to respondents have been and shall be fulfilled.

© Urbis Ltd
50 105 256 228

All Rights Reserved. No material may be reproduced without prior permission.
You must read the important disclaimer appearing within the body of this report.

urbis.com.au

Contents

Executive Summary	4
Introduction	5
Land Use and Development Summary	5
Site Layout	6
1 Data Centre Waste Management	8
1.1 Waste Stream Systems	8
1.2 Waste Generation	10
1.3 Internal Waste Transfer and Handling	11
1.4 Waste Management Equipment	11
1.5 Waste Storage and Location	11
1.6 Waste Collection Methodology	12
2 Standards and Compliance	14
2.1 Bin Supplier and Colours	14
2.2 Signage	14
2.3 Ventilation	15
2.4 Bin Washing	15
2.5 Noise Reduction	15
2.6 Vermin Prevention	15
3 Waste Equipment Details	16
3.1 Typical Equipment Dimensions	16
3.2 High Level Purchasing Schedule	16
3.3 Supplier Contact information	17
Disclaimer	18

Figures

Figure 1 – Site Phases Drawing	6
Figure 2 – Bin Station Examples	8
Figure 3 – Example of Sustainability Victoria Signage	14

Tables

Table 1 – Waste Collection Summary	4
Table 2 – Waste Collection Summary	5
Table 3 – Development summary	5
Table 4 – Commercial Waste Streams	8
Table 5 – Additional Waste Stream Methodology ..	9
Table 6 – Tenancy Use	10
Table 7 – Waste Generations	10
Table 8 – Waste Generation Assessment	10
Table 9 – Waste Equipment Capacity & Volume	11
Table 10 – Waste Storage Area Requirements	11
Table 11 – Waste Collection Summary	12
Table 12 – Typical Storage Unit Dimensions	16
Table 13 – Equipment Supply Schedule	16
Table 14 – Supplier Contact List	17

**ADVERTISED
PLAN**

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

Executive Summary

The below is a summary of the waste management strategy proposed for the subject site. The complete report must be read in detail prior to implementing the waste management plan.

Located at **44-76 Simcock Avenue, Spotswood** the proposed project will deliver a data centre spanning 2 levels and a rooftop level. The subject development will include approximately **30,192sqm of data hall spaces, 2,287sqm of office spaces** and other amenities.

This **Waste Management Plan (WMP)** has been prepared for all phases (**Phase 1 to 10**) of the Data Centre under this application, however, detailed design for each phase is sought to be rationalised via a staged planning permit

Due to the extent of the building at finalisation of **Phase 10**, there has been proposed to split waste management areas into two; each room adjacent to the loading dock of Building A and B (Refer to Table 10 and Appendix A for further detail).

Each area will service approximately half of the site, with all the bins and/or areas to be collected concurrently. The following waste systems and collection arrangements are proposed for the final development:

Table 1 – Waste Collection Summary

Stream	Item	Collections per Week	Collection
Garbage	3x 1100 Litre Bins	1	Private Contractor
Commingle Recycling	2x 1100 Litre Bins	1	
Cardboard	4x 1100 Litre Bins	1	
Food Organics	2x 120 Litre Bins	2	
Soft Plastics	2x 1100 Litre Bins	1	
E-waste	6x 1100 Litre Bins	Up to 1	
Extended Waste Streams	Bins or Allocated Storage Area as Appropriate	As Required*	

* Extended waste streams (i.e. pallets, hard waste) will be collected on an as required basis due to the requirement to accumulate a sufficient volume of material prior to collection. Anticipated collection of approx. 1 per month per stream.

All waste collections will occur on-site directly from the **loading dock areas**. An **8.8m MRV** or smaller collection vehicle will be utilised to perform all collections, entering and exiting the *loading dock areas* via the internal road, accessed at **Simcock Avenue**.

A minimum height clearance of **4.0m throughout** vehicle path of travel has been allowed for within the loading dock and associated access. Swept path analysis showing sufficient access is provided in **Appendix B**.

Collection vehicles will prop within the *loading dock area*, with operators to collect the material directly from the waste room and return empty storage containers (if appropriate) immediately upon emptying.

No bins will be stored outside of the title boundary or presented to kerb for collection at any time.

Building Management will ensure sufficient access is provided for collection vehicle operators during collection times.

Introduction

The following **Waste Management Plan (WMP)** has been prepared for the proposed **Phase 1** of the Data Centre development at **44-76 Simcock Avenue, Spotswood**.

This WMP has been prepared based on **Sustainability Victoria's Waste and Recycling for Commercial and Industrial Facilities, Better Practice Guidance (2023)**, **Hobsons Bay City Council Waste Management, Building Design for a Sustainable Future** and best practice waste management methodology and technologies commonly available in Australia.

The waste generation rates provided within have been prepared based on case study data held by Urbis and based on Data Hall spaces.

The waste services proposed throughout this WMP will be reviewed with respect to any change in the operational requirements of the subject development over time. Revised waste management plans will be issued to Council for approval prior to adoption.

Land Use and Development Summary

Table 2 – Waste Collection Summary

Client:	The Proponent
Land Use Type:	Commercial & Industrial
Number Levels:	2 levels and the roof top

Common areas of the overall components shown below (i.e. store, plant, services, circulation, etc.) are not considered to generate additional waste.

Waste generated by these ancillary areas is created in service of the areas shown in the Table 3 below and is therefore incorporated into the rates shown in each of the analysis sections.

Table 3 – Development summary

Use	NLA Area
Office	2,287 m ²
Data Halls	30,192 m ²

ADVERTISED
PLAN

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

Site Layout

Figure 1 below provides the location of **the final development**.




Figure 1 – Site Phases Drawing

ADVERTISED PLAN

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

1

Waste Management

This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright

Data Centre

1 Data Centre Waste Management

This WMP has been prepared based on **Sustainability Victoria's Waste and Recycling for Commercial and Industrial Facilities, Better Practice Guidance (2023)**, **Hobsons Bay City Council Waste Management, Building Design for a Sustainable Future** and best practice waste management methodology and technologies commonly available in Australia.

The waste generation rates provided within have been prepared based on case study data held by Urbis and based on data hall spaces

1.1 Waste Stream Systems

Waste shall be sorted on-site by management as appropriate into the following streams. **Extended Waste streams are not mandatory to be separated and subject to building management preference.**

Table 4 – Commercial Waste Streams

Core Waste Streams	Extended Waste Streams
General Waste (Garbage)	Hard Waste / Bulky Waste
Commingled Recycling	Electronic Waste
Cardboard	Secure Paper
Soft Plastics	Soft Plastics
Food Organics	

1.1.1 Core Waste Streams

Throughout the facility it will be ensured that it is as easy to dispose of all core waste streams as it is garbage. This will be achieved by ensuring the development is appropriately furnished with bin stations throughout the ancillary spaces and communal areas. Clear signage will be appropriately displayed in combination with the bin stations to identify the segregation of waste streams and correct use of the bins.

Bin stations will be used to encourage the separation of waste streams and diversion from landfill. The bin stations incorporate the provision of multiple bins for different waste streams at central locations and common areas for ease of disposal. This system is beneficial as users are required to make a conscious decision as to which bin they place their waste, typically resulting in a reduced volume of garbage (landfill).

The use of bin stations also reduces the amount of locations cleaners are required to service throughout the development.



Figure 2 – Bin Station Examples

**ADVERTISED
PLAN**

ADVERTISED PLAN

1.1.1.1 General Waste, Commingled Recycling and Cardboard

Staff/cleaners will be responsible for transferring and disposing garbage, commingled recycling and cardboard into the corresponding 1100 litre bins located in the waste room, adjacent to the loading dock as required.

Garbage waste is to be disposed of bagged and commingled recycling and cardboard is to be disposed of folded within the provided bins.

1.1.1.2 Food Organics

Only a small amount of food waste is expected to be generated by the office spaces. No food is expected to be cooked on site, with food waste being generated by food scraps. All food waste will be managed via kitchen organics caddys, with a minimum capacity of 7 litres for the temporary holding of food organics waste. Cleaners will transfer these caddys to the waste room and dispose the material within the 120L bin.

1.1.2 Extended Waste Streams

1.1.2.1 Hard Waste

A dedicated 3sqm hard waste area within the waste room will be used by staff/cleaners to temporarily store their hard waste inclusive of pallets, bulky items, broken office furniture. Hard waste will be collected on an as required basis.

1.1.2.2 Soft Plastics

Based on the waste stream composition of similar developments, it is anticipated that a moderate volume of soft plastics will be generated from the proposed development which supports independent stream management. This type of waste is often accounted for in the general waste stream, hence the space can be substituted for such strategy.

Soft plastic will be managed via the vertical baler (provided for cardboard management), with 660L bins for the temporary holding of soft plastics until a full load is sufficient for a complete bale. At all other times, the baler will be used for cardboard management, as per section 3.1.1.2.

1.1.2.3 Electronic Waste

Based on the waste stream composition of similar developments, it is anticipated that a high volume of electronic waste will be generated from the proposed development which supports independent stream management. It is expected that the building management will engage a private contractor to assist with appropriate management and disposal of electronic waste. All electronic waste will be managed via the use of 1100L bins.

E-waste will be collected on an as required basis which is expected to be no more than two times per week.

1.1.2.4 Additional Waste Streams

The following list of waste streams have not been individually included within the equipment provision but rather are a suggestion of streams that are typically found in commercial waste generation, and its separation will increase the diversion from landfill.

Table 5 – Additional Waste Stream Methodology

Waste Stream	Storage Method
Secure Paper	To be managed internally within the office areas via 240L secure bins. Once full, these bins will be transferred to the loading dock area for collection.
Expanded Polystyrene (EPS)	To be stored within a gathering stand or an 1100 litre bin subject to collection contractor preference.

Unique Recyclables

Generally stored within smaller bins appropriate to the stream within a dedicated area as nominated adjacent to the loading dock. This includes fluorescent tubes, secure paper, lighting bulbs.

1.2 Waste Generation

To provide a conservative waste volume estimate, a commercial waste generation rate has been adopted for each proposed use as outlined in Table 6.

Table 6 – Tenancy Use

Proposed Use (As per Development Summary)	Adopted Waste Generation Rate	Area (m ²)	Assumed Operational Days per week
Office	Commercial Office	2,287	7
Data Hall	Urbis – Data Centres*	30,192	7

*Data Centres rates are based on waste volume data held by Urbis sourced from a number of similar operational developments and Australian guidelines.

Waste generation rates per week are shown in Table 7.

Table 7 – Waste Generations

Use	Weekly Generation Rate (Litres / 100m ² / Week)				
	General Waste	Recycling	Cardboard	Food Organics	Soft Plastics
Office	56	28	42	7	7
Data Hall	3	1	9	-	5

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

Weekly waste generation assessment for the residential development component is shown in Table 8.

Common areas of the data centre (i.e. store, plant, services, circulation, etc.) are not considered to generate additional waste. Waste generated by these ancillary areas is created in service of the functional areas and is therefore incorporated into the rates shown above.

Table 8 – Waste Generation Assessment

Use	Area (m ²)	Weekly Waste Volume (Litres / Week)				
		General Waste	Recycling	Cardboard	Food Organics	Soft Plastics
Office	2,287	1,281	640	961	160	160
Data Hall	30,192	906	302	2,717	-	1,510
TOTAL		2,187	942	3,678	160	1,670

**ADVERTISED
PLAN**

1.3 Internal Waste Transfer and Handling

All waste transfer paths are to be exclusively within the site title boundary and should not require staff/cleaners to exit title to perform operations. Transfer routes for waste collections are not to include stairs or gradients greater than 1:14.

1.4 Waste Management Equipment

Table 9 details the storage method, size, capacity and frequency of collection required for the development.

Table 9 – Waste Equipment Capacity & Volume

Stream	Storage Method	Size	Qty	Collections per Week	Weekly Capacity (L)	Weekly Volume (L)
General Waste	Bin Based	1100 Litre	3	1	3,300	2,187
Commingled Recycling	Bin Based	1100 Litre	2	1	2,200	942
Cardboard	Bin Based	1100 Litre	4	1	4,400	3,678
Food Organics	Bin Based	120 Litre	2	2	480	160
Soft Plastics	Bin Based	1100 Litre	2	1	2,200	1,670
Electronic Waste	Bin Based	1100 Litre	6	Up to 1	6,600	Up to 6,600*
*Based on bin capacity						

Due to the requirement for a suitable volume of each extended waste stream (refer to Section 1.1.2) to be generated prior to collection, all extended streams will be collected on an as-required basis by a private collection contractor once the storage capacity is reached.

1.5 Waste Storage and Location

Table 10 demonstrates the cumulative area requirements (excluding circulation) in comparison to the designed provision of waste storage to demonstrate the adequacy of the area provided.

Due to the extent of the building at finalisation of Phase 10, there has been proposed to split waste management areas into two. Each area will service approximately half of the site and will be collected

Table 10 – Waste Storage Area Requirements

Location	Waste Equipment	Area Required (m²)	Area Provided (m²)
Adjacent to Loading dock Tech Building A	9no. 1100L Bins	11.97	62.00
	1no. 120L Bins	0.26	
	10 sqm Hard Waste / Bulky / Pallets	15.00	
Adjacent to Loading dock Tech Building B	9no. 1100L Bins	11.97	82.00
	1no. 120L Bins	0.26	
	10 sqm Hard Waste / Bulky / Pallets	15.00	
TOTAL		54.46m²	144.00m²

1.6 Waste Collection Methodology

All waste will be collected via private contractor.

Table 11 – Waste Collection Summary

Stream	Item	Collections per Week	Collection
Garbage	3x 1100 Litre Bins	1	Private Contractor
Commingled Recycling	2x 1100 Litre Bins	1	
Cardboard	4x 1100 Litre Bins	1	
Food Organics	2x 120 Litre Bins	2	
Soft Plastics	2x 1100 Litre Bins	1	
E-waste	6x 1100 Litre Bins	Up to 1	
Extended Waste Streams	Bins or Allocated Storage Area as Appropriate	As Required*	

* Extended waste streams (i.e. pallets, hard waste) will be collected on an as required basis due to the requirement to accumulate a sufficient volume of material prior to collection. Anticipated collection of approx. 1 per month per stream.

All waste collections will occur on-site directly from the **loading dock areas**. An **8.8m MRV** or smaller collection vehicle will be utilised to perform all collections, entering and exiting the *loading dock areas* via the internal road, accessed at **Simcock Avenue**.

A minimum height clearance of *4.0m throughout* vehicle path of travel has been allowed for within the loading dock and associated access. Swept path analysis showing sufficient access is provided in **Appendix B**.

Collection vehicles will prop within the *loading dock area*, with operators to collect the material directly from the waste room and return empty storage containers (if appropriate) immediately upon emptying.

No bins will be stored outside of the title boundary or presented to kerb for collection at any time.

Building Management will ensure sufficient access is provided for collection vehicle operators during collection times.

**ADVERTISED
PLAN**

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

2

Standards, Compliance

This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright

Following sections details on best practice waste
management methodology, , standards required for waste
rooms and equipment details.

2 Standards and Compliance

2.1 Bin Supplier and Colours

All bins and equipment mentioned in this WMP will be provided by private supplier. The below bin colours are specified by Australian Standard AS4123.7 2006, however due to the private nature of the collection, these are only recommendations and are not mandatory:

- Garbage (general waste) bins shall have red lids with dark green or black body.
- Recycle bins shall have yellow lids with dark green or black body.
- Cardboard bins shall have blue lids with blue body.

Private collection contractors often supply their own bins for collection.

2.2 Signage

Waste drop-off areas and bins will be clearly marked and signed with the approved Sustainability Victoria waste disposal signage, or equivalent, examples of which are provided in Figure 3. Staff / cleaners will be instructed by building management to adhere to these requirements.




Figure 3 – Example of Sustainability Victoria Signage

**ADVERTISED
PLAN**

2.3 Ventilation

Ventilation for waste room areas is provided in accordance with Australian Standard AS1668.

2.4 Bin Washing

An appropriately drained wash down area will be provided within each of the waste areas, in which each bins can be regularly washed by building management (or equivalent). Bin washing areas or bin wash bays must discharge to a grease trap.

Alternatively, a third-party bin washing service may be engaged to perform regular washing of bins. Bin washing suppliers must retain all waste water to within their washing apparatus and not impact on the drainage provisions of the site.

2.5 Noise Reduction

All waste areas shall meet BCA and AS2107 acoustic requirements as appropriate with operational hours and collection times assigned to minimise acoustic impact on surrounding premises.

2.6 Vermin Prevention

All waste areas are enclosed and kept clean for prevention of vermin ingress. Regular washing of areas and bins will occur.

**ADVERTISED
PLAN**

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

3 Waste Equipment Details

3.1 Typical Equipment Dimensions

The below table details the typical waste equipment dimensions.

Table 12 – Typical Storage Unit Dimensions

Unit	Width (mm)	Depth (mm)	Height (mm)
1100 Litre Bin	1,240	1,070	1,330
120 Litre Bin	480	545	930

3.2 High Level Purchasing Schedule

Table 13 list the equipment supply required for the core waste streams as per the conditions proposed within this report.

All service requirements noted are indicative only and must be confirmed with the supplier prior to commencement of construction.

Table 13 – Equipment Supply Schedule

Item	Quantity	Typical Services Requirement (s)*	Supplier
1100L Bin	3 x Garbage 2 x Recycling 4 x Cardboard 2 x Soft Plastics 6 x Electronic Waste	Nil	Private Supplier (SULO or equivalent)
120L Bin	2 x Food Organics	Nil	Private Supplier (SULO or equivalent)

** Services requirements are indicative only and must be confirmed with the manufacturer prior to the commencement of construction.*

**ADVERTISED
PLAN**

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

3.3 Supplier Contact information

A complimentary listing of contractors and equipment suppliers is provided in **Table 14** below for your reference. Urbis is not associated with these suppliers, and there is no obligation to procure goods or services from these companies. This is not intended to be a complete list of available suppliers. Urbis does not warrant or make representations regarding the goods or services provided by these suppliers.

Table 14 – Supplier Contact List

Service Type	Contractor/Supplier Name	Phone	Website
Private Waste Collectors	Premier Waste Management PTY LTD	1300 219 001	www.premierwaste.com.au
	SUEZ Environment	13 13 35	www.sita.com.au
	Cleanaway	13 13 39	www.cleanaway.com.au
	Veolia	132 955	www.veolia.com
Equipment Suppliers	Wastech Engineering (Compactors, Bin Lifters)	(03) 8787 1600	www.wastech.com.au
	Sulo Australia (Bins)	1300 364 388	www.sulo.com.au
	Sitecraft (Bin Tug Equipment)	1300 363 152	www.sitecraft.net.au
Bin Washing Services	The Bin Butlers	1300 788 123	www.thebinbutlers.com.au
	Kerbside Clean-A-Bin	(03) 9830 7381	www.kerbsidecleanabin-srp.com.au
	Calcorp Services	1800 225 267	www.calcorpservices.com.au
	WBCM Environmental Australia	1800 800 621	www.wbcm-aust.com.au
E-Waste Collection Services	TechCollect	1300 229 837	www.techcollect.com.au
	Mobile Muster	1800 249 113	www.mobilemuster.com.au
	ToxFree	1300 869 373	www.toxfree.com.au
CDS Collection	Scouts Victoria	(03) 8543 980	www.scoutscds.com.au
	Return It	1300 237 010	www.returnit.com.au

**ADVERTISED
PLAN**

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

Disclaimer

This report is dated 24 July 2026 and incorporates information and events up to that date only and excludes any information arising, or event occurring, after that date which may affect the validity of Urbis Ltd (**Urbis**) opinion in this report. Urbis prepared this report on the instructions, and for the benefit only, of Green Square DC (**Instructing Party**) for the purpose of Waste Management Plan for Development Application (**Purpose**) and not for any other purpose or use. To the extent permitted by applicable law, Urbis expressly disclaims all liability, whether direct or indirect, to the Instructing Party which relies or purports to rely on this report for any purpose other than the Purpose, and to any other person which relies or purports to rely on this report for any purpose whatsoever (including the Purpose).

In preparing this report, Urbis was required to make judgements which may be affected by unforeseen future events, the likelihood and effects of which are not capable of precise assessment.

All surveys, forecasts, projections and recommendations contained in or associated with this report are made in good faith and on the basis of information supplied to Urbis at the date of this report, and upon which Urbis relied. Achievement of the projections and budgets set out in this report will depend, among other things, on the actions of others over which Urbis has no control.

In preparing this report, Urbis may rely on or refer to documents in a language other than English, which Urbis may arrange to be translated. Urbis is not responsible for the accuracy or completeness of such translations and disclaims any liability for any statement or opinion made in this report being inaccurate or incomplete arising from such translations.

Whilst Urbis has made all reasonable inquiries it believes necessary in preparing this report, it is not responsible for determining the completeness or accuracy of information provided to it. Urbis (including its officers and personnel) is not liable for any errors or omissions, including in information provided by the Instructing Party or another person or upon which Urbis relies, provided that such errors or omissions are not made by Urbis recklessly or in bad faith.

This report has been prepared with due care and diligence by Urbis and the statements and opinions given by Urbis in this report are given in good faith and in the reasonable belief that they are correct and not misleading, subject to the limitations above.

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

**ADVERTISED
PLAN**

Appendix A – Sketch Comments

**ADVERTISED
PLAN**


**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**

ADVERTISED
PLAN

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

Other Waste Room Requirements

- Internal room clearance to be no less than 1,200mm.
- Room to be suitably drained to an approved sewerage connection, holding tank or treatment system and have a water tap and hose.
- Appropriate ventilation in accordance with Australian Standard AS1668.



1 GENERAL ARRANGEMENT - GROUND FLOOR
1:750

Waste Systems Proposed

- 3x 1100L Garbage @ 1 collection per week
- 2x 1100L Recycling @ 1 collection per week
- 4x 1100L Cardboard @ 1 collection per week
- 2x 120L Food Organics @ 2 collections per week
- 2x 1100L Soft Plastics @ 1 collections per week
- 6x 1100L Electronic Waste @ up to 1 collection per week
- 30m² Bulky waste area collected as required

SITE LEGEND


- PROPERTY BOUNDARY
- BUILDING SETBACK

Standard Equipment dimensions (mm):

1100L Bin	1240W x 1070D x 1330H
120L Bin	480W x 545D x 930H

PROJECT
GreenSquareDC Spotswood
44-76 SIMCOCK AVENUE
SPOTSWOOD VIC 3015

Scale
As
indicated



DRAWING
GENERAL ARRANGEMENT PLAN - GF

PROJECT STATUS
SCHEMATIC DESIGN

PRINT DATE
06.07.2026

DRAWING NO.
MEL1-ST000-ARC-GBA-DRG-X-00-000009

Issue	Date	Description
1	06.02.2026	PLANNING APPLICATION FOR INFORMATION
2	24.02.2026	PLANNING APPLICATION
3	25.02.2026	PLANNING APPLICATION
4	27.02.2026	PLANNING APPLICATION
5	06.07.2026	PLANNING APPLICATION

CLIENT
Green SquareDC
HOME OF AI
GreenSquareDC
LEVEL 5/143 MACQUARIE STREET
SYDNEY NSW 2000 AUSTRALIA

Greenbox
A WOOLPERT COMPANY


GREENBOX ARCHITECTURE PTY LTD
LEVEL 22/68 PITT STREET
SYDNEY NSW 2000 AUSTRALIA
+61 2 8069 8930
ABN: 79 139 779 098
Nominated Architect - Gerard Page; NSW reg No.7247, Vic reg No.17664, QLD reg No.4538
ISO 9001 CERTIFIED QUALITY SYSTEM

- NOTES
- Use written dimensions only
 - Do not scale from drawing
 - Contractors shall confirm all dimensions on-site prior to commencing any work or producing any shop drawings
 - All materials to be used in accordance with the manufacturer's specifications and instructions and shall comply with the relevant Australian Standards
 - Copyright of this drawing and design remain the property of Greenbox Architecture Pty Ltd
 - Nominated Architect - Gerard Page; NSW reg No.7247, Vic reg No.17664, QLD reg No.4538

NORTH

ISSUE
REV 5
A1

ADVERTISED
PLAN



SITE SETBACK LEGEND

- PROPERTY BOUNDARY
- BUILDING SETBACK
- LANDSCAPE SETBACK


1 GENERAL ARRANGEMENT - LEVEL 1
1:750

PROJECT

GreenSquareDC Spotswood
44-76 SIMCOCK AVENUE
SPOTSWOOD VIC 3015

Scale

As
indicated



DRAWING

GENERAL ARRANGEMENT PLAN -
L1

PRINT DATE

27.02.2026

DRAWING NO.

MEL1-ST000-ARC-GBA-DRG-X-00-000010

PROJECT STATUS

DEVELOPMENT
APPLICATION

Issue

Date

1	06.02.2026
2	25.02.2026
3	27.02.2026

Description

PLANNING APPLICATION
PLANNING APPLICATION
PLANNING APPLICATION

CLIENT



GreenSquareDC
LEVEL 3/143 MACQUARIE STREET
SYDNEY NSW 2000 AUSTRALIA




GREENBOX ARCHITECTURE PTY LTD
LEVEL 22/69 PITT STREET
SYDNEY NSW 2000 AUSTRALIA

+61 2 8069 8930
ABN: 79 139 779 098
ISO 9001 CERTIFIED QUALITY SYSTEM

NOTES

- Use written dimensions only
- Do not scale from drawing
- Contractors shall confirm all dimensions on-site prior to commencing any work or producing any shop drawings
- All materials to be used in accordance with the manufacturer's specifications and instructions and shall comply with the relevant Australian Standards
- Copyright of this drawing and design remain the property of Greenbox Architecture Pty Ltd
- Nominated Architect - Gerard Page; NSW reg No.7247, Vic reg No.17664, QLD reg No.4538


NORTH



ISSUE

REV 3

ADVERTISED
PLAN



This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

1 GENERAL ARRANGEMENT - LEVEL 2
1:750

SITE SETBACK LEGEND


- PROPERTY BOUNDARY
- BUILDING SETBACK
- LANDSCAPE SETBACK

PROJECT

GreenSquareDC Spotswood
44-76 SIMCOCK AVENUE
SPOTSWOOD VIC 3015

Scale

As indicated



DRAWING

GENERAL ARRANGEMENT PLAN - L2

PRINT DATE

27.02.2026

DRAWING NO.

MEL1-ST000-ARC-GBA-DRG-X-00-000011

PROJECT STATUS

DEVELOPMENT APPLICATION

Issue

Date

1	06.02.2026
2	25.02.2026
3	27.02.2026

Description

PLANNING APPLICATION
PLANNING APPLICATION
PLANNING APPLICATION

CLIENT



GreenSquareDC
LEVEL 3/143 MACQUARIE STREET
SYDNEY NSW 2000 AUSTRALIA




GREENBOX ARCHITECTURE PTY LTD
LEVEL 22/66 PITT STREET
SYDNEY NSW 2000 AUSTRALIA

+61 2 8069 8930
ABN: 79 139 779 098
ISO 9001 CERTIFIED QUALITY SYSTEM

NOTES

- Use written dimensions only
- Do not scale from drawing
- Contractors shall confirm all dimensions on-site prior to commencing any work or producing any shop drawings
- All materials to be used in accordance with the manufacturer's specifications and instructions and shall comply with the relevant Australian Standards
- Copyright of this drawing and design remain the property of Greenbox Architecture Pty Ltd
- Nominated Architect - Gerard Page; NSW reg No.7247, Vic reg No.17664, QLD reg No.4538

NORTH



ISSUE



REV 3

A1

Appendix B – Swept Paths

**ADVERTISED
PLAN**

**This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright**



LEGEND	
---	500m BODY CLEARANCE
---	VEHICLE BODY - FORWARD
---	VEHICLE BODY - REVERSE

ADVERTISED PLAN

12.5m HEAVY RIGID VEHICLE LOADING ACCESS

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

PRELIMINARY ADVICE ONLY
NOT FOR CONSTRUCTION

ALL DRAWINGS ARE DESIGNED TO BE PRINTED AND READ IN COLOUR
IT IS THE CONTRACTORS' RESPONSIBILITY TO PRINT DRAWINGS IN COLOUR TO AVOID ANY POTENTIAL DISCREPANCIES IF DRAWINGS ARE PRINTED IN BLACK AND WHITE



44-76 Simcock Avenue, Spotswood
Swept Path Assessment

Olderfleet, Level 10, 477 Collins Street | Melbourne VIC 3000 AUSTRALIA | +61 3 8663 4888 | URBIS Pty Ltd | ABN 50 105 256 228

ARCHITECTURAL DRAWING REF	
DWG NAME:	
MEL1-ST000-GBA-DRG-X-00-00004-SITE PLAN	
DATE: 07/07/2026	
NEARMAP IMAGE	
DATE:10/12/2025	



REV	DESCRIPTION	JD	KD	DATE
C	Swept Path Assessment	JT	KD	07/07/26
B	Swept Path Assessment	JT	KD	25/03/26
A	Preliminary Issue	JT	KD	06/02/26

DISCLAIMER
Copyright by Urbis Pty Ltd. This drawing or parts thereof may not be reproduced for any purpose or used for another project without the consent of Urbis. The plan must not be used for ordering, supply or installation and no relevance should be placed on this plan for any financial dealing of the land. This plan is conceptual and is for discussion purposes only and subject to further detail study, Council approval, engineering input, and survey. Cadastral boundaries, areas and dimensions are approximate only. Written figured dimensions shall take preference to scaled dimensions.

CLIENT
GreenSquareDC
Level 3/143 Macquarie Street
Sydney NSW 2000



PROJECT NO. P0058526
SHEET NO. 07 OF 13
DATE 07/07/26
REVISION C



LEGEND	
---	500m BODY CLEARANCE
---	VEHICLE BODY - FORWARD
---	VEHICLE BODY - REVERSE

ADVERTISED PLAN

STAGE 1
12.5m HEAVY RIGID VEHICLE SITE EXIT MOVEMENT

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

PRELIMINARY ADVICE ONLY
NOT FOR CONSTRUCTION

ALL DRAWINGS ARE DESIGNED TO BE PRINTED AND READ IN COLOUR
IT IS THE CONTRACTORS' RESPONSIBILITY TO PRINT DRAWINGS IN COLOUR TO AVOID ANY POTENTIAL DISCREPANCIES IF DRAWINGS ARE PRINTED IN BLACK AND WHITE



44-76 Simcock Avenue, Spotswood
Swept Path Assessment

Olderfleet, Level 10, 477 Collins Street | Melbourne VIC 3000 AUSTRALIA | +61 3 8663 4888 | URBIS Pty Ltd | ABN 50 105 256 228

ARCHITECTURAL DRAWING REF	
DWG NAME:	
MEL1-ST000-GBA-DRG-X-00-00004-SITE PLAN	
DATE: 07/07/2026	
NEARMAP IMAGE	
DATE:10/12/2025	



REV	DESCRIPTION	JD	KD	DATE
C	Swept Path Assessment	JT	KD	07/07/26
B	Swept Path Assessment	JT	KD	25/03/26
A	Preliminary Issue	JT	KD	06/02/26

DISCLAIMER
Copyright by URBIS Pty Ltd. This drawing or parts thereof may not be reproduced for any purpose or used for another project without the consent of URBIS. The plan must not be used for ordering, supply or installation and no relevance should be placed on this plan for any financial dealing of the land. This plan is conceptual and is for discussion purposes only and subject to further detail study, Council approval, engineering input, and survey. Cadastral boundaries, areas and dimensions are approximate only. Written figured dimensions shall take preference to scaled dimensions.

CLIENT
GreenSquareDC
Level 3/143 Macquarie Street
Sydney NSW 2000



PROJECT NO. P0058526
SHEET NO. 08 OF 13
DATE 07/07/26
REVISION C



LEGEND	
---	500m BODY CLEARANCE
---	VEHICLE BODY - FORWARD
---	VEHICLE BODY - REVERSE

12.5m HEAVY RIGID VEHICLE LOADING ACCESS

ADVERTISED
PLAN

This copied document to be made available for the sole purpose of enabling its consideration and review as part of a planning process under the Planning and Environment Act 1987. The document must not be used for any purpose which may breach any copyright

PRELIMINARY ADVICE ONLY
NOT FOR CONSTRUCTION

ALL DRAWINGS ARE DESIGNED TO BE PRINTED AND READ IN COLOUR
IT IS THE CONTRACTORS' RESPONSIBILITY TO PRINT DRAWINGS IN COLOUR TO AVOID ANY POTENTIAL DISCREPANCIES IF DRAWINGS ARE PRINTED IN BLACK AND WHITE

This copied document to be made available
for the sole purpose of enabling
its consideration and review as
part of a planning process under the
Planning and Environment Act 1987.
The document must not be used for any
purpose which may breach any
copyright

Shaping cities
and communities
for a better future.