



Traffic & Transportation Direction



Maffra Solar Farm

Maffra-Briagolong Road, Maffra

Traffic Impact Assessment

October 2022

**ADVERTISED
PLAN**

Reference: 400 rep 221006 final

Maffra Solar Farm

Maffra-Briagolong Road, Maffra

Traffic Impact Assessment

Prepared for: NGH Pty Ltd

Status: Draft report

Date: 6 October 2022

Reference: 400 rep 221006 final

**ADVERTISED
PLAN**

Contact

Website: www.amberorg.com.au

E: info@amberorg.com.au

Phone: 1800 022 363

Table of Contents

1.	Background	1
1.1	Background.....	1
1.2	Purpose of Document.....	1
2.	Existing Conditions.....	3
2.1	Site Location.....	3
2.2	Road Network	3
2.3	Traffic Volumes	4
2.4	Restricted Vehicle Access.....	4
2.5	Public Transport Services	5
2.6	Crash History.....	5
3.	Traffic Assessment	6
3.1	Traffic Generation.....	6
3.2	Traffic Distribution	7
3.3	Traffic Assessment.....	8
3.4	Cumulative Traffic Impacts.....	8
4.	Route Assessment	9
5.	Intersection Assessment	10
5.1	Site Access Turn Treatments.....	10
5.2	Sight Distance.....	11
6.	Construction Traffic Management Plan	12
7.	Conclusion	13

Appendix A

Access Design

**ADVERTISED
PLAN**



1. Background

ADVERTISED PLAN

1.1 Background

Amber Organisation Pty Ltd has been engaged by NGH Pty Ltd to conduct a review of the traffic implications of the Maffra Solar Farm and prepare a Traffic Impact Assessment.

The solar farm is located approximately 2.5km north of Maffra and is proposed to have a capacity of 5MW. Access to the site is proposed via a new access to Maffra-Briagolong Road in the north-western corner of the site. Staff are expected to primarily be located in Maffra and Sale with all plant expected to be delivered from Port of Melbourne.

Figure 1 shows the proposed layout of the site in relation to the road network, access locations and existing infrastructure.

Figure 1: Site Layout



Source: NGH Pty Ltd

1.2 Purpose of Document

This Traffic Impact Assessment has been prepared to assess the construction and operational traffic impacts, and the access arrangements of the solar farm. The assessment details how road

impacts of the project traffic, particularly from heavy vehicle use, will be avoided or managed using road-use management strategies.

More specifically, the report addresses the following key matters:

- Details of both light and heavy vehicle traffic volumes and proposed transport routes;
- An assessment of the potential traffic impacts of the project on road network function and safety;
- An assessment of the capacity of the existing road network to accommodate the type and volume of traffic generated by the project;
- Details of measures to mitigate and / or manage potential impacts, including construction traffic control, road dilapidation surveys and measures to control soil erosion and dust generated by traffic volumes; and
- Details of access roads and how these connect to the existing road network and ongoing operational maintenance.

The traffic assessment has been undertaken in conjunction with consultation with Department of Transport and Wellington Shire Council. It also responds to the requirements outlined within the *Department of Environment, Land, Water and Planning Solar Energy Facilities Design and Development Guideline*.

**ADVERTISED
PLAN**




2. Existing Conditions

ADVERTISED PLAN

2.1 Site Location

The site forms Lot 13 TP23981 and is located approximately 2.5km north of Maffra on the eastern side of Maffra-Briagolong Road. Figure 2 shows the location of the site in relation to the surrounding transport network.

Figure 2: Site Location



Source: Melways

The site is zoned as Farming Zone (FZ) and is occupied by agricultural land, with the surrounding land use also being predominantly agricultural. Access to the site is currently provided via an informal farm access to Maffra-Briagolong Road in the north-western corner of the site.

2.2 Road Network

Maffra-Briagolong Road is a Secondary State Arterial Road under the care and management of Department of Transport and is classified as a TRZ2 Principal Road Network Zone. It runs in a

general north-south alignment between Forbes Street in Briagolong and its continuation as Powerscourt Street in Maffra. Within the vicinity of the site, it has a carriageway width of approximately 7.0 metres accommodating one lane of traffic in each direction and has a speed limit of 100km/hr.


2.3 Traffic Volumes

Traffic volume data from the Department of Transport database indicates Maffra-Briagolong Road accommodates in the order of 190 vehicle movements in each of the peak hours, and 1,510 vehicles per day which are relatively evenly distributed between north and southbound movements. Accordingly, the road network currently accommodates a low level of traffic which is well within the operating capacity.

2.4 Restricted Vehicle Access

The DoT Gazetted Roads for B-Doubles Map for the surrounding area is provided within Figure 3. The green lines indicate B-Double declared roads with Maffra-Briagolong Road being a B-Double declared road.

Figure 3: DoT Gazetted Roads for B-Doubles Map



Source: VicRoads Gazetted Roads for B-Doubles Map

**ADVERTISED
PLAN**

2.5 Public Transport Services

No public transport services are provided within the vicinity of the site.

2.6 Crash History

Amber has conducted a review of the DoT Crashstats database for all injury crashes within 2.0 kilometres of the site. The crash database provides the location and severity of all injury and fatal crashes for the five-year period from 2015 to 2019. The crash search revealed no crashes within the search year and as such, it is concluded that the road network is currently operating in a relatively safe manner.

**ADVERTISED
PLAN**

3. Traffic Assessment

3.1 Traffic Generation

3.1.1 Construction

The solar farm construction is expected to take approximately 6 months, with the peak construction period expected to take 1-2 months. Construction activities would be undertaken during standard daytime construction hours, as follows:

- Monday to Friday: 7am – 6pm
- Saturday: 7am – 1pm
- No work on Sundays or public holidays.

Any construction outside of these normal working hours would only be undertaken with prior approval from relevant authorities.

A maximum of 50 staff will be on-site during peak construction periods. It is understood that shuttle buses will be provided that can accommodate the majority of staff, with the remaining staff to access the site using private vehicles.

Construction traffic generated by the solar farm can broadly be separated into the following three categories:

- Light vehicles associated with transporting staff to/from the site, including shuttle buses and personal vehicles;
- Medium and Heavy Rigid Trucks (MRV and HRV as defined within AS 2890.2:2018) will be used to deliver raw materials and smaller plant; and
- Articulated Vehicles and B-Doubles (AV and B-Double as defined within AS 2890.2:2018) will be used to transport larger plant.

Restricted Access Vehicles / oversized and overmass (OSOM) vehicles will be required for the delivery of larger plant to the site such as the substation transformer and are subject to separate permit applications and regulations. The impacts of the OSOM vehicles are discussed within Section 4 with the following assessment focusing on the impacts of the light and heavy vehicles which generate the bulk of the traffic and represent the typical traffic impact of the project on a day-to-day basis.

The construction traffic volumes for the project have been provided by the Applicant. It is anticipated that during peak construction the site could generate up to 38 heavy and 108 light vehicle movements per day. It is noted that a vehicle movement is classified as a vehicle travelling in one direction (i.e. a truck accessing the site would generate one movement towards the site and one movement away from the site when it departs).

Table 1 summarises the traffic movements generated during the construction period of the solar farm.

**ADVERTISED
PLAN**

Table 1: Traffic Generation During Peak Construction Periods

Vehicle Type	Average Vehicle Movements per Day		Peak Vehicle Movements per Day	
	Daily (vpd)	Peak Hour (vph)	Daily (vpd)	Peak Hour (vph)
Light Vehicle (car / 4WD)	30	15	100	50
Shuttle Bus	4	2	8	2
MRV/HRV	6	1	8	2
AV	4	1	20	2
B-Double	4	1	10	1
Total	48	20	146	57

Overall, the site is expected to generate approximately 57 vehicle movements during the morning and evening peak hours during the peak construction period, which will reduce to 20 vehicle movements over the typical construction periods.

3.1.2 Operational Traffic

During operation the solar farm is expected to generate a minimal level of traffic associated with maintenance and operation services. The solar farm is expected to be operated by up to 5 staff resulting in a traffic generation of up to 10 vehicle movements per day which would result in a negligible change to the traffic environment.

3.1.3 Decommissioning Traffic

At the end of the operational life of the project all above ground infrastructure will be dismantled and removed from the project site. Internal roads, if not required for ongoing farming purposes or fire access, would be removed and the site reinstated as close as possible to its original state.

Traffic generation during decommissioning would be similar to traffic generation during the average construction period. A comprehensive Construction Traffic Management Plan would be prepared prior to the decommissioning phase in conjunction with the relevant road authorities. This would aim to ensure adequate road safety and road network operations are maintained.

3.2 Traffic Distribution

Traffic accessing the site will do so via Maffra-Briagolong Road which is a Secondary State Arterial Road. Staff will primarily be located in Maffra and Sale with all plant expected to be delivered from the Port of Melbourne. The following provides a breakdown of the access distribution for each of the vehicle classifications outlined within Table 1:

- Light Vehicles: It is anticipated that most staff will be local within Maffra and Sale, with 100% of staff travelling from the south.
- MRV/HRV: These vehicles will predominantly be water trucks and vehicles transporting materials such as concrete and fencing supplies which will be sourced within the surrounding area. The Applicant has advised that 95% will be travelling from the south and 5% travelling from the north.
- AV/B-Double: Plant will be transported from Port of Melbourne to the site along Maffra-Briagolong Road from the south.

The peak hour for the solar farm will occur at the start and end of the day when staff are transported to/from the site. During the morning peak all vehicle movements will be towards the site and in the evening peak all vehicle movements will be away from the site. Heavy vehicle movements will be distributed throughout the day and will be split evenly between inbound and outbound movements.

3.3 Traffic Assessment

Maffra-Briagolong Road is currently estimated to be carrying in the order of 190 vehicles in the peak hour. During peak construction the traffic volumes would increase to approximately 247 vehicles movements per hour. The traffic volumes can be readily accommodated on the road network and Maffra-Briagolong Road is expected to continue to operate with a good level of service. Accordingly, it is concluded that the road network is able to accommodate the traffic generated by the solar farm during the construction period.

3.4 Cumulative Traffic Impacts

A review has been undertaken for any other renewable projects in the surrounding area. The VicPlan Map Tool indicates that the only other renewable energy project on the area is the approved 30MW Maffra Solar Farm which is located approximately 1 kilometre south of the site at 148 Brewers Hill Road, Maffra.

The proximity of the Maffra Solar Farm suggests there is the potential for construction of the solar farm to coincide with the construction of the proposed solar farm and may result in increased traffic volumes in the area. There may also be additional movements generated within Maffra and Sale with staff for these projects being located within nearby towns.

The traffic assessment provided within this report demonstrates that the road network is expected to continue to operate with a good level of service with ample spare capacity. As such, the combined increase in traffic generated by the projects is expected to have a minimal cumulative impact on the road network, including through Maffra and Sale. Further, it is noted that the peak traffic generated by these projects during construction occurs before 7:00am and after 6:00pm which is outside of the peak times of the road network.

**ADVERTISED
PLAN**

4. Route Assessment

Port of Melbourne has been identified as the location where the solar farm plant will be imported. The proposed construction traffic access route from the port to the site is expected to be via M1/Princes Highway, Maffra-Rosedale Road, Traralgon-Maffra Road, Johnson Street, Powerscourt Street, and Maffra-Briagolong Road. The arterial roads are designated for B-Double vehicles as outlined within the DoT Gazetted Roads for B-Doubles Map provided within Figure 3. Accordingly, the access route is able to accommodate the loads and type of vehicle movement to be generated during construction of the solar farm.

It is also noted that some oversize and overmass vehicles will be required to deliver larger plant to the site such as the sub-station transformer and earthmoving equipment. The vehicles are subject to specific road permits that will be applied for by the contractor once the dimensions of the load and the specific delivery vehicle are known.


**ADVERTISED
PLAN**

5. Intersection Assessment

5.1 Site Access Turn Treatments

Austrroads Guide to Traffic Management Part 6: Intersections, Interchanges, and Crossings specifies the turning treatments required at intersections. Figure 3.25 of the guide specifies the required turn treatments on the major road at unsignalised intersections and is provided below in Figure 4.

Figure 4: Figure 3.25 of Austrroads Guide to Traffic Management Part 6



The requirement to provide turn facilities is primarily generated during the morning peak hour when staff access the site which occurs from 6:00am to 7:00am. Table 2 identifies the required turning treatments based on the expected traffic volumes at the intersection.

Table 2: Turning Volumes for Turn Treatment Calculations

Turning Treatment	Traffic Volume (vph)		Requirement
	Turn Volume	Major Road	
Right Turn	57	85	BAR
Left Turn	0	85	BAL

Therefore, the intersection would require a Basic Right Turn (BAR) treatment.

Following discussions with Department of Transport Officers it has been agreed that the site access is to be designed in accordance with Guideline Drawing *AGRD Part 4 - Typical Design to Rural Properties*. The drawing is provided within Appendix A and provides the design requirements for access by a B-Double vehicle. The design does not specify turn treatments which are not proposed at the access based on the following:

- The construction period is expected to occur for approximately 6 months with a peak construction period of 1-2 months which represents a temporary increase in traffic volumes. Outside of the construction period the site is expected to generate a minimal level of traffic.

**ADVERTISED
 PLAN**

- The majority of turn movements into the site occur when staff access the site in the morning peak hour. During peak construction staff are expected to generate 50 vehicle movements to the site and during the average construction period they are expected to generate 15 vehicle movements. These vehicle movements occur before 7:00am which is outside of the peak time of the road network.
- Through the day the site is expected to generate a minimal number of turn movements into the site which is expected to be in the order of 2-3 vehicle movements per hour.
- The intersection has excellent sight distance for vehicles travelling along Maffra-Briagolong Road to see turning vehicles.
- A CTMP will be prepared prior to construction of the site. The CTMP will include measures to inform staff of the reduced turn treatment and to encourage suitable safety initiatives.

Accordingly, the site access is expected to be able to accommodate the traffic generated by the solar farm in a safe manner subject to the adoption of the guideline drawing.

5.2 Sight Distance

Austrroads Guide to Road Design Part 4A: Unsignalised and Signalised Intersections specifies the Safe Intersection Sight Distance (SISD) as the minimum sight distance which should be provided along the major road at any intersection. Table 3.1 of the guide specifies the SISD required for various design speeds. Given Maffra-Briagolong Road has a speed limit of 100km/hr a design speed of 110km/hr has been adopted which requires an SISD of 285 metres.

The available sight distance at the site access exceeds the Austrroads requirements given the relatively flat and straight alignment of Maffra-Briagolong Road and vehicles are expected to be able to safely enter and exit the site.

**ADVERTISED
PLAN**

6. Construction Traffic Management Plan

A Construction Traffic Management Plan (CTMP) will be prepared prior to construction commencing by the appointed contractor. The CTMP will provide additional information regarding the traffic volumes and distribution of construction vehicles that is not available at this time, including:

- Road transport volumes, distribution and vehicle types broken down into:
 - Hours and days of construction.
 - Schedule for phasing/staging of the project.
- The origin, destination and routes for:
 - Employee and contractor light traffic.
 - Heavy vehicle traffic.
 - Oversize and overmass traffic.

The following provides recommended measures that should be adopted within the CTMP to minimise the impact of construction traffic along the road network:

- Neighbours of the solar farm be consulted and notified regarding the timing of major deliveries which may require additional traffic control and disrupt access.
- Loading and unloading is proposed to occur within the work area. No street or roads will be used for material storage at any time.
- All vehicles will enter and exit the site in a forward direction.
- Management of vehicular access to and from the site is essential in order to maintain the safety of the general public as well as the labour force. The following code is to be implemented as a measure to maintain safety within the site:
 - Utilisation of only the designated transport routes.
 - Construction vehicle movements are to abide by finalised schedules as agreed by the relevant authorities.
- Implementation of a proactive erosion and sediment control plan for on-site roads, hardstands and laydown areas.
- All permits for working within the road reserve must be received from the relevant authority prior to works commencing.
- A map of the primary haulage routes highlighting critical locations.
- An induction process for vehicle operators and regular toolbox meetings.
- A complaint resolution and disciplinary procedure.
- Local climatic conditions that may impact road safety of employees throughout all project phases (e.g. fog, wet and significant dry, dusty weather).

The above recommendations will ensure the construction traffic will create a minimal impact to the capacity and safety of the surrounding road network.

**ADVERTISED
PLAN**

7. Conclusion

Amber has assessed the traffic impacts of the 5MW solar farm located approximately 2.5km north of Maffra. Access to the site will be provided via a new access to Maffra-Briagolong Road in the north-western corner of the site. Staff will primarily be located in Maffra and Sale with all plant expected to be delivered from Port of Melbourne. The above assessment determined the following:

- The site will generate up to 108 vehicle movements per day during peak construction times, including 38 truck movements;
- The road network is able to accommodate the traffic generated by the development during the construction, operation and decommissioning stages;
- The site access is proposed to be constructed to accommodate B-Double vehicles and any OSOM vehicles;
- The proposed construction traffic access route from Port of Melbourne to the site is proposed to be via M1/Princes Highway, Maffra-Rosedale Road, Traralgon-Maffra Road, Johnson Street, Powerscourt Street, and Maffra-Briagolong Road. The roads are designated for B-Double vehicles and as such, the access route is able to accommodate the loads and type of vehicle movement to be generated during construction of the solar farm;
- It is noted that some oversize and overmass vehicles will be required to deliver larger plant to the site such as the sub-station transformer and earthmoving equipment. The vehicles are subject to specific road permits that will be applied for by the contractor once the dimensions of the load and the specific delivery vehicle are known; and
- In order to mitigate the impacts of the development during construction a CTMP will be prepared which should include the recommendations provided within this document.

Accordingly, based on the assessment above, it is concluded that the proposed access arrangements for the solar farm are suitable to accommodate the expected construction vehicle types and traffic volumes during the construction and operation phase of the project.

**ADVERTISED
PLAN**

Appendix A

Access Design

**ADVERTISED
PLAN**



ISSUE	APPROVED BY	DATE	AMENDMENT
A	M-RD&SSE	12/21	REVISED PAVEMENT DETAILS AND GENERAL NOTES 1, 2, 3, 4, & 5




TABLE 2: ACCESS SETOUT DETAILS

VEHICLE TYPE	A	B	C	D	E	F	J	K	L	M	R1	R2	G
26m B-DOUBLE	15.0	30.3	20.4	11.0	6.1	3.7	2.1	5.3	9.4	15.3	45	13	4.3
19m SEMI TRAILER	15.0	24.6	17.2	10.3	5.2	3.0	1.9	4.6	9.3	15.7	30	14	4.2
ARTICULATED 19m BUS	15.0	21.9	14.4	7.5	4.4	2.9	2.1	5.4	9.6	14.7	26	15	4.0
12.5m SINGLE UNIT	15.0	20.1	12.9	6.4	4.1	3.0	2.2	5.6	9.7	16.3	23	18	4.0
TRUCK + 3 AXLE TRAILER	15.0	18.3	11.8	6.2	4.0	3.0	2.2	5.7	9.8	14.2	18	18	4.0
TRUCK + 4 AXLE TRAILER	15.0	19.2	12.2	6.0	4.0	3.0	2.3	5.9	9.8	14.0	20	17	4.0
8.8m SERVICE VEHICLE	15.0	12.6	8.7	5.4	4.1	3.5	1.8	4.1	6.7	9.6	10	13	4.0
PASSENGER VEHICLE	5.0	9.3	3.8	1.8	-	-	2.2	7.5	-	-	7.5	-	3.6

SETOUT DETAILS TO BE BASED ON THE DESIGN VEHICLE SELECTED.
 CHECK VEHICLE MAY ENCR OACH ON TO OPPOSING TRAFFIC LANE IN <80KM/H SPEED ZONE FOR LOW VOLUME ROADS WITHOUT A CENTRAL BARRIER.


PLAN - DRIVEWAY ACCESS LAYOUT

ADVERTISED PLAN

TABLE 1: SIGHT DISTANCES

DESIGN SPEED (Km/h)	'd' SAFE INTERSECTION SIGHT DISTANCE (m)	CORRECTION (m)							
		ROADWAY UPGRADE				ROADWAY DOWNGRADE			
		2%	4%	6%	8%	2%	4%	6%	8%
60	123	-2	-4	-6	-7	2	5	8	11
70	151	-3	-5	-8	-10	3	7	11	15
80	181	-4	-7	-10	-13	4	9	14	20
90	226	-5	-9	-13	-16	5	11	18	25
100	262	-6	-11	-16	-20	6	14	22	31
110	300	-7	-13	-19	-24	8	17	26	38

THE DESIGN SPEED IS ASSUMED TO BE 10km/h GREATER THAN THE POSTED SPEED LIMIT FOR RURAL HIGHWAYS AND ROADS



MINIMUM VISIBILITY REQUIREMENTS (NOT TO SCALE)

GENERAL NOTES:

- THE DIAGRAM IS A GUIDE FOR A TYPICAL LAYOUT OF A DRIVEWAY ACCESS FOR A RURAL PROPERTY FOR VEHICLES AS SPECIFIED IN TABLE 2. THIS GUIDE WAS DEVELOPED IN THE INTEREST OF ROAD SAFETY AND TO PROTECT THE ARTERIAL ROAD PAVEMENT AT THE ACCESS LOCATION.
 - SLIGHT VARIATIONS MAY OCCUR AFTER SITE INSPECTION, ANALYSIS AND APPROVAL OF THE LOCATION.
 - THE PAVEMENT COMPOSITION SHALL BE IN ACCORDANCE WITH THAT SHOWN IN DETAIL A. THE PAVEMENT TYPE SHOWN IN DETAIL B IS ONLY SUITABLE FOR INFREQUENT HEAVY VEHICLE TRAFFIC. AN ALTERNATIVE PAVEMENT COMPOSITION WILL REQUIRE APPROVAL BY THE DEPARTMENT OF TRANSPORT. NEW PAVEMENT MUST BE KEYPED INTO EXISTING PAVEMENT AND CRACK SEALED.
 - ANY PROPOSED ALTERNATIVE PAVEMENT DESIGNS SHALL BE UNDERTAKEN IN ACCORDANCE WITH VICROADS CODE OF PRACTICE RC 500.22 SELECTION AND DESIGN OF PAVEMENTS AND SURFACINGS AND AUSTRROADS GUIDE TO PAVEMENT TECHNOLOGY PART 2 PAVEMENT STRUCTURAL DESIGN. PAVEMENT MATERIALS AND EARTHWORK LAYERS NEED TO BE IN ACCORDANCE WITH DOT STANDARD SECTIONS AND/OR LOCAL GOVERNMENT SPECIFICATION REQUIREMENTS.
 - A PLANNING PERMIT IS REQUIRED FOR A NEW ACCESS OR ALTERATION TO AN EXISTING DRIVEWAY AND MAY BE REQUIRED FOR THE REMOVAL OF NATIVE VEGETATION.
 - A TRAFFIC MANAGEMENT PLAN MUST COMPLY WITH THE ROAD MANAGEMENT ACT AND APPLICABLE CODES IN RELATION TO ANY WORKS UNDERTAKEN WITHIN THE ROAD RESERVE.
 - TRUCK WARNING SIGNS & GUIDE POSTS SHOULD BE INSTALLED IN ACCORDANCE WITH AUSTRROADS GUIDE TO TRAFFIC MANAGEMENT & VICROADS SUPPLEMENTS.
 - THE DRIVEWAY ACCESS CONSTRUCTION AND MAINTENANCE IS THE RESPONSIBILITY OF THE PROPERTY OWNER. MAINTENANCE ALSO INCLUDES ASSOCIATED DRAINAGE WORKS.
- SIGHT DISTANCE:
- A DRIVER, WHEN LOCATED 7.0M (5.0M MIN) FROM THE CONFLICT POINT TAKEN AS THE CENTRE OF THE TRAFFIC LANE, NEEDS TO SEE A VEHICLE APPROACHING IN EITHER DIRECTION. REFER TABLE 1 FOR APPROPRIATE SIGHT DISTANCES.
 - TREE CANOPIES, BUSHES OR OTHER OBJECTS SHALL BE REMOVED TO PROVIDE GOOD VISIBILITY. ANY TREE CANOPIES OVERHANGING THE PATH OF A TRUCK SHALL BE A MINIMUM OF 5.0M ABOVE THE GROUND SURFACE.
 - SIGHT LINES MUST ACHIEVE THE MINIMUM SAFE INTERSECTION SIGHT DISTANCE BASED ON AN EYE HEIGHT OF 1.1M TO AN OBJECT HEIGHT OF 1.25M.

VicRoads Drawing No. 720453

- NOTES:
- ALL DIMENSIONS ARE IN METRES, UNLESS SHOWN OTHERWISE
 - THIS DRAWING FORMS PART OF THE VRS TO AGRD PART 4 AND SHOULD BE READ IN CONJUNCTION WITH THOSE REFERENCES

- REFERENCES:
- AUSTRROADS GUIDE TO ROAD DESIGN PART 4
 - AUSTRROADS GUIDE TO ROAD DESIGN PART 4A
 - AUSTRROADS GUIDE TO ASSET MANAGEMENT PART 5
 - AUSTRROADS GUIDE TO PAVEMENT TECHNOLOGY PART 2
 - AUSTRROADS GUIDE TO TRAFFIC MANAGEMENT
 - VICROADS SUPPLEMENTS TO AUSTRROADS GUIDES

- VICROADS CODE OF PRACTICE RC 500.22
- SELECTION AND DESIGN OF PAVEMENTS AND SURFACINGS
- SD 1991 DRIVEABLE CULVERT ENDWALLS (TYPE 1)



AGRD PART 4
 TYPICAL ACCESS TO RURAL PROPERTIES


NOT TO SCALE	APPROVED M-SSE	GD NO. 07/2020	ISSUE GD4010	A
--------------	-------------------	-------------------	-----------------	---



Entry Manoeuvre



Exit Manoeuvre



B-Double

**ADVERTISED
PLAN**



Maffra Solar Farm
Maffra-Briagolong Road, Maffra
Swept Path Assessment

DRAWN: MW
DATE: 06/10/2022
DWG NO: 400-S01A
SCALE at A3: 1:500

